

Report to Committee

Planning and Development Department

To:

Planning Committee

Date: April 24, 2015

From:

Wayne Craig

File:

RZ 14-676660

Re:

Director of Development

Application by Trico Developments (B.C.) Inc. for Rezoning at

3600/3620 Blundell Road from Two-Unit Dwellings (RD1) to Single Detached

(RS2/B)

Staff Recommendation

That Richmond Zoning Bylaw 8500, Amendment Bylaw 9207, for the rezoning of 3600/3620 Blundell Road from "Two-Unit Dwellings (RD1)" to "Single Detached (RS2/B)", be introduced and given first reading.

Wayne Craig

Director of Development

AY:blg Att.

REPORT CONCURRENCE

ROUTED To:

CONCURRENCE

CONCURRENCE OF GENERAL MANAGER

Affordable Housing

Staff Report

Origin

Trico Developments (B.C.) Inc. has applied to the City of Richmond to rezone the properties at 3600/3620 Blundell Road from "Two-Unit Dwellings (RD1)" zone to "Single Detached (RS2/B)" zone to permit subdivision into two (2) lots fronting Blundell Road. An existing duplex situated on the lot is to be demolished. A map and aerial photograph showing the location of the subject site is included in Attachment 1. A preliminary subdivision plan is provided in Attachment 2.

Findings of Fact

A Development Application Data Sheet providing details about the development proposal is included in Attachment 3.

Surrounding Development

The subject site is located in the Seafair Planning Area. Existing development immediately surrounding the subject site is as follows:

- To the north, directly across Blundell Road, are single-family residential lots zoned "Single-Detached (RS1/E)".
- To the east, are single-family residential lots zoned "Single Detached (RS2/B)" which were rezoned and redeveloped in 2011-2012.
- To the south, are single-family residential lots zoned "Single-Detached (RS1/E)".
- To the west, are lots zoned "Two-Unit Dwellings (RD1)", with existing duplex dwellings.

Related Policies & Studies

2041 Official Community Plan (OCP)

The Official Community Plan (OCP) designation of the subject site is "Neighbourhood Residential (NRES)". The proposed single-family residential development complies with the OCP land use designation.

Single-Family Lot Size Policy 5474

The subject site is located within the area bounded by Single-Family Lot Size Policy 5474, which was adopted by Council on May 20, 2008 (see Attachment 4). The Policy permits lots with existing duplexes to rezone and subdivide into two (2) equal lots. The proposed redevelopment complies with Single-Family Lot Size Policy 5474.

Flood Management

The proposed redevelopment must meet the minimum requirements of Richmond Flood Plain Designation and Protection Bylaw No. 8204. Registration of a flood indemnity covenant on Title of the subject properties is required prior to final adoption of the rezoning bylaw.

Public Consultation

The rezoning information sign has been installed on the subject site. In response, one (1) neighbourhood resident of the property immediately west of the subject site inquired about site drainage requirements for the proposed redevelopment. Staff advised that perimeter drainage is required to be installed on all sites undergoing new dwelling construction, as part of the Building Permit review and inspection process.

Analysis

Existing Legal Encumbrances

A restrictive covenant is currently registered on title of both subject strata lots which restricts each strata lot to be used only as a site for a one-family dwelling, such that the entire strata plan may only consist of a total of two (2) dwelling units (Registration No. BE316033 / BE316034). Prior to final adoption of the rezoning bylaw, the applicant must discharge the covenant from title of both subject properties. The applicant must also wind up and cancel the strata plan for the two (2) properties prior to subdivision.

Site Servicing and Vehicle Access

There are no site servicing concerns regarding the proposed rezoning.

Vehicle access to both proposed lots is to be from Blundell Road. At Subdivision stage, the developer is required to pay servicing costs associated with driveway relocation and restoration of the sidewalk and boulevard along the Blundell Road frontage.

Trees and Landscaping

A Certified Arborist's Report and Tree Retention Plan was submitted by the applicant. The report identifies four (4) bylaw-sized trees located on-site proposed for removal and four (4) trees located on neighbouring property proposed for retention. A copy of the Tree Retention Plan is included in Attachment 5.

The City's Tree Preservation Coordinator has reviewed the Arborist's Report, conducted an on-site Visual Tree Assessment, and concurs with the Arborist's recommendations as follows:

• Three (3) trees located on-site (Tag#'s 21-23) are in poor condition and have been previously topped, causing significant structural defects. As a result, these trees are not good candidates for retention and should be replaced.

- One (1) tree located on-site (Tag# 24) is a multi-stemmed Japanese Maple tree growing in a raised planter that has sustained heading cuts throughout the canopy. This tree is located in the middle of the proposed building envelope of the future east subdivided lot and cannot be retained.
- Four (4) trees located on neighbouring property (Tags A-D) are to be protected.

Parks Department staff have authorized the removal of the Laurel hedge along the subject property frontage as it will conflict with future driveway construction to serve the subdivided lots.

Tree protection fencing is to be installed on-site around the drip lines of Tree Tags A-D located on neighbouring property. The fencing must be installed to City standard and in accordance with the City's Bulletin-03 prior to demolition of existing buildings and must remain in place until all construction and landscaping works are completed on-site. To ensure the protection of these trees, the applicant is required to enter into a contract with a Certified Arborist for the supervision of works conducted within close proximity to the tree protection zones of the trees to be retained.

Consistent with the 2:1 tree replacement guideline ratio in the OCP, the applicant has agreed to plant eight (8) replacement trees on-site (four [4] on each subdivided lot). The trees must be a minimum size of 6 cm deciduous caliper or 3.5 cm high conifer. Suitable tree replacement species include the Japanese Maple (*Acer Palmatum*), the Kousa Dogwood (*Cornus Kousa*) and the Serbian Spruce (*Picea Omorika*). To ensure that the replacement trees are planted and maintained on-site, the applicant is required to submit a Landscaping Security in the amount of \$4,000 (\$500/tree) prior to final adoption of the rezoning bylaw.

Affordable Housing Strategy

For single-family rezoning applications, Richmond's Affordable Housing Strategy requires a secondary suite within a dwelling on 50% of new lots created through rezoning and subdivision, or a cash-in-lieu contribution of \$1.00/ft² of total building area towards the City's Affordable Housing Reserve Fund.

The applicant proposes to provide a legal secondary suite in the dwelling on both lots proposed at the subject site. To ensure that at least one (1) secondary suite is built to the satisfaction of the City in accordance with the City's Affordable Housing Strategy, the applicant is required to enter into a legal agreement registered on Title, stating that no final Building Permit inspection will be granted until the secondary suite is constructed to the satisfaction of the City in accordance with the BC Building Code and the City's Zoning Bylaw. Registration of the legal agreement is required prior to final adoption of the rezoning bylaw. This agreement will be discharged from Title (at the initiation of the applicant) on the lot where the secondary suite is not required by the Affordable Housing Strategy after the requirements are satisfied.

Note: Should the applicant change their mind about the Affordable Housing option selected, a voluntary contribution to the City's Affordable Housing Reserve Fund in-lieu of providing the secondary suite will be accepted. In this case, the voluntary contribution would be required to be submitted prior to final adoption of the rezoning bylaw, and would be based on \$1.00/ft² of total building area of the single detached dwellings to be constructed (i.e., \$5,278).

Subdivision Stage

At Subdivision stage, the developer is required to pay servicing costs for engineering servicing and frontage upgrades as outlined in Attachment 6.

Financial Impact or Economic Impact

None.

Conclusion

This rezoning application to permit the subdivision of the subject site into two (2) lots zoned "Single Detached (RS2/B)" is consistent with the applicable policies and land use designations outlined within the Official Community Plan (OCP) and with Single-Family Lot Size Policy 5474.

The applicant has agreed to the list of rezoning considerations (signed concurrence on file) outlined in Attachment 6.

On this basis, it is recommended that Zoning Bylaw 8500, Amendment Bylaw 9207 be introduced and given first reading.

Andrew Yu

Planning Technician (Temp)

AY (blg)

Attachment 1: Location Map and Aerial Photograph


Attachment 2: Preliminary Subdivision Plan

Attachment 3: Development Application Data Sheet Attachment 4: Single-Family Lot Size Policy 5474

Attachment 5: Proposed Tree Retention Plan

Attachment 6: Rezoning Considerations






N

RZ 14-676660

Revision Date:

Note: Dimensions are in METRES







RZ 14-676660

Original Date: 11/24/14

Revision Date: 04/28/15


Note: Dimensions are in METRES

SURVEY PLAN OF STRATA PLAN NWS118 SECTIONS 21 AND 22 BLOCK 4 NORTH RANGE 7 WEST NEW WESTMINSTER DISTRICT


FOR THE PURPOSE OF APPLICATION FOR SUBDIVISION & NUMEROUS PERMITS

CIVIC ADDRESSES #3600 & 3620 BLUNDELL ROAD RICHMOND, B.C.

ZONING: RS2







- ELEVATIONS ARE IN METRES AND ARE DERIVED FROM CITY OF RICHMOND HPN MONUMENT #234 (77H4891) WITH AN ELEVATION OF 1.125 METRES.
- PROPERTY LINE DIMENSIONS ARE DERIVED FROM LAND TITLE OFFICE RECORDS AND LEGAL FIELD SURVEYS.
- ALL DESIGNATED TREES AS DEFINED BY CITY OF RICHMOND BYLAW NO. 8057, ARE SHOWN HEREON.
- -- STRATA PLAN NWS118 SUBJECT TO STATUTORY RIGHT OF OF WAY CHARGES A52644, A52645, & A52646

© COPYRIGHT

MATSON PECK & TOPLISS


SURVEYORS & ENGINEERS

#320 - 11120 HORSESHOE WAY RICHMOND, B.C., V7A 5H7 PH: 604-270-9331

FAX: 604-270-4137

CADFILE: 17731-001-TPG-001.DWG

LEGEND SCALE 1: 250



x indicates spot elevation 由LS Indicates Lamp Standard

O MH INDICATES MANHOLE


PP INDICATES POWER POLE

OIC INDICATES INSPECTION CHAMBER
OLB INDICATES LAWN BASIN

GE INDICATES ROUND CATCH BASIN

O WM INDICATES WATER METER

INDICATES IRON POST



CLIENT REF: ALBERT WONG & TRICO DEVELOPMENTS INC.

■ LP

DATE OF SURVEY: OCTOBER 28, 2014



Development Application Data Sheet

Development Applications Division

RZ 14-676660 Attachment 3

Address: 3600/3620 Blundell Road

Applicant: Trico Developments (B.C.) Inc.

Planning Area(s): Seafair (Mores Neighbourhood)

	Existing	Proposed
Owner:	Trico Developments (B.C.) Inc., No. BC0699780	TBD
Site Size (m²):	891.6 m ²	Proposed west lot: 445.8 m ² Proposed east lot: 445.8 m ²
Land Uses:	Two-family residential (duplex)	Single-family residential
OCP Designation:	Neighbourhood Residential	No change
702 Policy Designation:	Single-Family Lot Size Policy 5474	Complies
Zoning:	Two-Unit Dwellings (RD1)	Single Detached (RS2/B)
Number of Lots:	One (1)	Two (2)

On Future Subdivided Lots	Bylaw Requirement	Proposed	Variance
Floor Area Ratio:	Max. 0.55	Max. 0.55	none permitted
Lot Coverage – Building:	Max. 45%	Max. 45%	none
Lot Coverage – Building, structures, non-porous surfaces:	Max. 70%	Max. 70%	none
Lot Coverage – Landscaping with live plant material:	Min. 25%	Min. 25%	none
Setback – Front & Rear Yards (m):	Min. 6.0 m	Min. 6.0 m	none
Setback – Interior Side Yards (m):	Min. 1.2 m	Min. 1.2 m	none
Height:	Max. 21/2 storeys	Max. 2½ storeys	none
Lot Size (m²):	Min. 360 m²	Proposed west lot: 445.8 m ² Proposed east lot: 445.8 m ²	none
Lot Width (m):	Min. 12 m	Proposed west lot: 12.2 m Proposed east lot: 12.2 m	none
Lot Depth (m):	Min. 24 m	Proposed west lot: 36.6 m Proposed east lot: 36.6 m	none
Lot Frontage (m):	Min. 6.0 m	Proposed west lot: 12.2 m Proposed east lot: 12.2 m	none

Other: Tree replacement compensation required for loss of significant trees.



City of Richmond

Policy Manual

Page 1 of 2	Adopted by Council: May 20, 2008	olicy 5474
File Ref: 4430	SINGLE-FAMILY LOT SIZE POLICY IN QUARTER-SECTIONS 21	-4-7: 8: 22-4-7

Policy 5474:


The following policy establishes lot sizes in Sections 21-4-7 & 22-4-7, in the area generally bounded by Blundell Road, No. 1 Road, Francis Road, and West Dyke Trail as shown on the attached map:

1. That properties within the area generally bounded by Blundell Road, No. 1 Road, Francis Road, and West Dyke Trailin Section 21-4-7 & 22-4-7, as shown on the attached map, be permitted to subdivide in accordance with the provisions of Single-Family Housing District, Subdivision Area E (R1/E) in Zoning and Development Bylaw No. 5300 with the following exceptions:

That lots with existing duplexes be permitted to rezone and subdivide into two (2) equal halves lots;

and that this policy be used to determine the disposition of future single-family rezoning applications in this area, for a period of not less than five years, unless amended according to Zoning and Development Bylaw No. 5300.

2. Multiple-family residential development shall not be permitted.





Policy 5474 21-4-7 & 22-4-7 Original Date: 02/29/08

Amended Date: 05/20/08

Note: Dimensions are in METRES

TREE PROTECTION GUIDELINES:

inkinistali kisin or camhraism flut flut what oil card jeachea' is all o this actual to the privately eller may lest described beach flut from or occupants of companies and the statement of the - Anna lices kind to gigned of box (20 π, tom στη properly fro cad of loot) λλ m from στη roads, "plus, coles bown, also and when releasing box, and of a might meeting to the cade of the properly from the cade of the cade of the properly from the cade of the cade ving spragating a conceptual schamalis of replacement (res cianting recommunantantions in context to municipal sorts, setterston at typical and the string of trees must conform to the municipal standards.

TREE PLANTING GUIDELINES

opman lass are to conform to Curach IDC Londscope. Standards or published and upsteland from times to liene by BCSLA/IDC.(NA action to see conform from the preparation of separation for quality, superficiely, the pseparations, handling mathrades, staking and establishingent. The indicate indexes are for confidentian mark if eigenote species are defined by the owner, the species mail conferm to the morning of the indicates are indicated conferm to the confidence of the indicates are indicated to the indicate indicates that the indicates the indicates that the indicates the indicates the indicates that the indicates the in

resources resources transmission in sharped least it blood on to thanking bod with shuke settler behooded a greated the land is several and to complicate the past of the several to the several the several to the several the several to the severa

discipie carelliciti vii, not requissi premoranti algodino olere valobiletiment. Howeveri staglim veolaridog, forti alano ilica giorgiaci, patrono nella proficio. Na pavade recomplande va montro venergi allono roi. andan veolagia, pogo posizio, os el emposere interna impostion palane. Illa veoladino stekacia albusti astrono andan veolagia, pogo positi si ropusorge lo menticata fino recei basi est hydrologia. On o conceptivoli.

6. THE BOTTOM ONE-THRID OF THE BACKFLL SHOULD BE TAMPED FIRMLY AROUND THE ROOT BALL TO PROVIDE STRUCTURAL SUPPORT. 4. THE TOP HALF OF THE WINEBASSET AND/OR TWINE AND BUSINED DOWN TO ALLOW UNDBSTRUCTED ROOF GROWIN. 2. STAKE, AND JIES SHOUD BE INSTALLED FOR TREES BAST ARE NOT STABLE A FIRER PLANTING TOR TREES DEPRENDING ON FORMS, GOOD BAST, THE AND SUR! STAKES, AND TES MAST BE RELOVED ONE TOAK AFTER PLANTING UM ESS OTHERWISE SPECIESD. 5. PLANTING HOLE-AND ROOT BALL MUST BE. COVERGE WITH SOME IZ INCLESS OF COMEOSTED MUSCH. THE MUCH SHOULD NOT BE PLACED WITHOUT SOO AND IS NOWED. 3. TRUNK FLARE (ROOT COLLAS), OF THE ROOT ALL MUST BE SET TO MATCH SURROUNDING GRADES. 9. A 75mm (3 INCH) HIGH BEBM (DYRE) OF SOL ANST BE FUSINLED AT THE FEBLETER OF FILE NOO! AALL TO ALD IN SECTING. SUPPLEMENTAL WATER TO THE ROO! NOTE PLANTING DETAIL

DIMUM SIZE AND SPECES. MANAGEMENPRACHES AND BESLADELMASRECIPICATIONS FO MINTENANCE. SUGGESTED PLANT LIST:

NA VAR. PUPUREA HUS X YEDGENSIS TAX JAPON GUS INGA REHCIUAI A WORY SUK

load dolong controllers reasonate for them, or well or during the carping pressure.

- and the prolection reasonates for them or well or during the carping pressure.

- get and the prolection reconstruction prescription.

- get and prolection reconstruction prescription.

- get and prolection reconstruction properties to be required to provide out costs for the following troolons of the properties of the


but not firmlited to: catocist to attend and diffect the compliance to protection inequires during the clearing

I file project orbida to attent and unear transmirrance in the project orbital of the IPE and the standard orbital populary tokas, pointing fires on the ground, and/or piacing rape

n phases of the project as follows: and to FPZ.

shipping of organic self for hard landscape ins n or condult installation,

is intervent concernous or manufactured leads in the second of a middle from the conception of the second of the s mild lifts, arons at alter overhand equipment is residited in proximity to retained frees and simulatine; the photoid the crown of the free accordingly.



SEE SHEET 2 FOR DRAWING DETAILS

Rolect Protuct

> Seyers, specifical base le neith with carriered bigarches. Historically pruned to the fencer ine via those snotute. Not scattle allocation are not sometimes. For the second on the certificial based by dela, evaluation is possible the self-rated categories for the second.

14 ... Tellevical (195 mit Text 16-19/dis referring in heigh principle based to the south

31 \$+35 Westernandenstear

25+25 Chouy

NA, ilipin Herra altoch ol base, Grawing in arakusi picalar - Root gravin is obsessed, Kisloilcafy, punse evia heri singestis. Hadpatow comissing of stitums within instancing datance of the subject site, ranging 12 Nem. 1984. Hataico a Joppod at to helejal of the obsets grade. Crawn overstangs the site by Inn.

24 (34)34)2 Joponesen

12-13 Est. 18

CONSULTING admission of CLUMBIA SUITE 200-3740 CHAINAM STREET, RICHMOND, BC CANADA VF 223 ARBORTECH

FRASER VALLEY REGIONAL OFFICE: SUITE 109 - 1528 MCCALLUM ROAD, ABBOTSTORD, BC CANADA V28 BAS

SHEET: 1 OF 2 ADDRESS: 3600 & 3620 BLUNDELL RD, RICHMOND TREE MANAGEMENT DRAWING PROJECT: PROPOSED 2-LOT SUBDIVISION CLIENT: TRICO DEVELOPMENT (BC) INC ACL FILE: 15136 p 804.755.713g p 604.275.3484

THE REPORT OF THE PROPERTY OF

all to hashpoon to fact condition that has a pre-antitying moderate rated related that the fact fact condition from proposed byted run but it conditions to the condition of the proposed byted run but it conditions to the condition for the condition of the condition for the condition for the condition of the con


occornocation?

Adhie notice this papered beathcard of the lac within the current designs you appear one downling for one state of the form of the for

Rapi-Kranly diped. Docoyed Hum oli bato, Iwa kradzus altock at 8,5m with long Jackindukipa. Pomanjed Han in sweed boatlonalons. Hilde closik mund vite heading outs for UC Hydro, reskilling in hisavy asymmetry and desayed passing wounds. i ido diathi loppad at i halqini at tin obavo, gʻoʻch'ordiC. Niqda isolay salsaat. Repidaniani saladi, visa okoʻcapad at salsa linici ilm anif osini avali avali avali salsaasi. salsa boosilanni bahingi gʻoʻci qay salsa ili qoʻci at salsa bahingi biladi.

Namor Crajo

21+19





Rezoning Considerations

Development Applications Division 6911 No. 3 Road, Richmond, BC V6Y 2C1

Address: 3600/3620 Blundell Road File No.: RZ 14-676660

Prior to final adoption of Richmond Zoning Bylaw 8500, Amendment Bylaw 9207, the developer is required to complete the following:

- 1. Submission of a landscaping security in the amount of \$4,000 (\$500/tree) to ensure that eight (8) replacement trees (four [4] on each subdivided lot) are planted and maintained on-site. The replacement trees must be a minimum size of 6 cm deciduous caliper or 3.5 m high conifer.
- 2. Submission of a Contract entered into between the applicant and a Certified Arborist for supervision of any on-site works conducted within the tree protection zone of the trees to be retained. The Contract should include the scope of work to be undertaken, including: the proposed number of site monitoring inspections, and a provision for the Arborist to submit a post-construction assessment report to the City for review.
- 3. Registration of a flood indemnity covenant on title.
- 4. Registration of a legal agreement on Title to ensure that no final Building Permit inspection is granted until a secondary suite is constructed on one (1) of the two (2) future lots, to the satisfaction of the City in accordance with the BC Building Code and the City's Zoning Bylaw.
 - **Note:** Should the applicant change their mind about the Affordable Housing option selected prior to final adoption of the Rezoning Bylaw, the City will accept a voluntary contribution of \$1.00 per buildable square foot of the single-family developments (i.e. \$5,278) to the City's Affordable Housing Reserve Fund in-lieu of registering the legal agreement on Title to secure a secondary suite.
- 5. Discharge of Covenant Registration No. BE316033 from title of the property at 3600 Blundell Road.
- 6. Discharge of Covenant Registration No. BE316034 from title of the property at 3620 Blundell Road.

At Demolition Permit* Stage, the developer must complete the following requirements:

1. Installation of appropriate tree protection fencing around all trees to be retained as part of the development prior to any construction activities, including building demolition, occurring on-site.

Prior to Building Permit Issuance, the developer must complete the following requirements:

- 1. Submission of a Construction Parking and Traffic Management Plan to the Transportation Division. Management Plan shall include location for parking for services, deliveries, workers, loading, application for any lane closures, and proper construction traffic controls as per Traffic Control Manual for works on Roadways (by Ministry of Transportation) and MMCD Traffic Regulation Section 01570.
- 2. Obtain a Building Permit (BP) for any construction hoarding. If construction hoarding is required to temporarily occupy a public street, the air space above a public street, or any part thereof, additional City approvals and associated fees may be required as part of the Building Permit. For additional information, contact the Building Approvals Division at 604-276-4285.

At Subdivision* stage, the developer must complete the following requirements:

1. Pay servicing costs for the design and construction of frontage and engineering infrastructure improvements via City Work Order. Works include, but may not be limited to the following:

Water	Works:
water	works:

Initial:	

- Using the OCP Model, there is 106.8 L/s of water available at a 20 psi residual at the Blundell Road frontage. Based on the proposed development, the site requires a minimum fire flow of 95.0 L/s. The Developer is required to submit Fire Underwriter Survey (FUS) or International Organization for Standardization (ISO) fire flow calculations to confirm the development has adequate fire flow for on-site fire protection. Calculations must be signed and sealed by a Professional Engineer and be based on Building Permit Stage Building designs.
- At the Developers cost, the City is to cut and cap the existing water service connection at the water main along the Blundell Road frontage, and install two (2) new 25 mm water service connections complete with meters and meter boxes along the Blundell Road frontage.

Storm Sewer Works:

• At the Developers cost, the City is to cap the existing storm service connection at the northwest corner of the subdivision site, and install a new storm IC with two (2) new service connections at the common property line of the two (2) lots along the Blundell Road frontage.

Sanitary Sewer Works:

• At the Developers cost, the City is to cap the existing sanitary service connection at the northeast corner of the subdivision site, and install a new sanitary IC with two (2) new service connections near the common property line of the two (2) lots along the Blundell Road frontage.

Frontage Improvements:

- Developer is to coordinate with BC Hydro, Telus and other private communication service providers:
 - To underground proposed Hydro service lines.
 - When relocating/modifying any existing power poles and/or guy wires within the property frontages.
 - To determine if above ground structures are required and coordinate their locations (e.g. Vista, PMT, LPT, Shaw cabinets, Telus Kiosks, etc).
- Developer is required to pay servicing costs for driveway relocation, sidewalk restoration and boulevard upgrades along the subject property frontage on Blundell Road. Upgrades to include the planting of two (2) trees along the existing grassed boulevard in front of the subject site.

General Items:

The 3 m BC Hydro SRW shall remain along the southern property line of the subdivided lots.

Note:

- * This requires a separate application.
- Where the Director of Development deems appropriate, the preceding agreements are to be drawn not only as personal covenants of the property owner but also as covenants pursuant to Section 219 of the Land Title Act.
 - All agreements to be registered in the Land Title Office shall have priority over all such liens, charges and encumbrances as is considered advisable by the Director of Development. All agreements to be registered in the Land Title Office shall, unless the Director of Development determines otherwise, be fully registered in the Land Title Office prior to enactment of the appropriate bylaw.
 - The preceding agreements shall provide security to the City including indemnities, warranties, equitable/rent charges, letters of credit and withholding permits, as deemed necessary or advisable by the Director of Development. All agreements shall be in a form and content satisfactory to the Director of Development.
- Additional legal agreements, as determined via the subject development's Servicing Agreement(s) and/or Development Permit(s), and/or Building Permit(s) to the satisfaction of the Director of Engineering may be required including, but not limited to, site

CNCL - 247

Initial:	

investigation, testing, monitoring, site preparation, de-watering, drilling, underpinning, anchoring, shoring, piling, pre-loading, ground densification or other activities that may result in settlement, displacement, subsidence, damage or nuisance to City and private utility infrastructure.

• Applicants for all City Permits are required to comply at all times with the conditions of the Provincial Wildlife Act and Federal Migratory Birds Convention Act, which contain prohibitions on the removal or disturbance of both birds and their nests. Issuance of Municipal permits does not give an individual authority to contravene these legislations. The City of Richmond recommends that where significant trees or vegetation exists on site, the services of a Qualified Environmental Professional (QEP) be secured to perform a survey and ensure that development activities are in compliance with all relevant legislation.

[signed copy on file]		
Signed	Date	



Richmond Zoning Bylaw 8500 Amendment Bylaw 9207 (RZ 14-676660) 3600/3620 Blundell Road

The Council of the City of Richmond, in open meeting assembled, enacts as follows:

1. The Zoning Map of the City of Richmond, which accompanies and forms part of Richmond Zoning Bylaw 8500, is amended by repealing the existing zoning designation of the following area and by designating it "SINGLE DETACHED (RS2/B)".

P.I.D. 001-124-170

Strata Lot 1 Section 22 Block 4 North Range 7 West New Westminster District Strata Plan NW118 Together With an Interest in the Common Property in Proportion to the Unit Entitlement of the Strata Lot as shown on Form 1

P.I.D. 000-856-461

Strata Lot 2 Section 22 Block 4 North Range 7 West New Westminster District Strata Plan NW118 Together With an Interest in the Common Property in Proportion to the Unit Entitlement of the Strata Lot as shown on Form 1

2. This Bylaw may be cited as "Richmond Zoning Bylaw 8500, Amendment Bylaw 9207".

FIRST READING	CITY OF RICHMOND
A PUBLIC HEARING WAS HELD ON	APPROVED by
SECOND READING	APPROVED by Director
THIRD READING	or Solicitor Lil
OTHER CONDITIONS SATISFIED	
ADOPTED	
MAYOR	CORPORATE OFFICER