



# City of Richmond

## Report to Committee Planning and Development Division

**To:** Planning Committee

**Date:** January 10, 2017

**From:** Wayne Craig  
Director, Development

**File:** RZ 14-678448

**Re:** Application by 1004732 BC Ltd. for Rezoning at 6840 & 6860 No. 3 Road and 8051 Anderson Road from "Downtown Commercial (CDT1)" to "City Centre High Density Mixed Use with Office (ZMU31) – Brighthouse Village"

### Staff Recommendation

That Richmond Zoning Bylaw 8500, Amendment Bylaw 9510 to create the "City Centre High Density Mixed Use with Office (ZMU31) – Brighthouse Village" zone, and to rezone 6840 & 6860 No. 3 Road and 8051 Anderson Road from "Downtown Commercial (CDT1)" to "City Centre High Density Mixed Use with Office (ZMU31) – Brighthouse Village", be introduced and given first reading.

Wayne Craig  
Director, Development

WC:jd

Att.

REPORT CONCURRENCE		
ROUTED TO:	CONCURRENCE	CONCURRENCE OF GENERAL MANAGER
Affordable Housing	<input checked="" type="checkbox"/>	
Community Services	<input checked="" type="checkbox"/>	

## Staff Report

### Origin

1004732 BC Ltd. has applied to the City of Richmond for permission to rezone the properties at 6840 & 6860 No. 3 Road and 8051 Anderson Road (Attachments 1&2) from “Downtown Commercial (CDT1)” to a new site-specific zone, “City Centre High Density Mixed Use with Office (ZMU31) – Brighthouse Village”, in order to permit the development of a high-density, mixed commercial and residential use building in City Centre’s Brighthouse Village (Attachment 3). Key components of the proposal include:

- a podium and tower form of development;
- a total floor area of 18,701 m<sup>2</sup> (201,292 ft<sup>2</sup>) comprised of approximately:
  - 1,149 m<sup>2</sup> (12,371 sq.ft.) of retail space on the ground level,
  - 9,794 m<sup>2</sup> (105,420 sq.ft.) of office space in a twelve-storey tower component facing No. 3 Road, and,
  - 7,757 m<sup>2</sup> (83,501 sq.ft.) of multi-family residential space in a ten-storey mid-rise component facing Anderson Road;
- a total of seventy-five (75) studio through three-bedroom dwelling units including:
  - sixty-seven (67) one-storey apartment units, and
  - eight (8) two-storey apartment units;
- 5% of the residential floor area allocated to five (5) affordable housing units;
- a variety of utility, transportation and parks improvements and cash contributions along with development of an enhanced public realm along No 3 Road;
- cash-in-lieu contributions of \$515,105.15 for child care, \$1,417,398.31 for community facilities, \$50,304.72 for community planning and \$114,861.64 for public art; and
- a LEED Silver-equivalent building designed and constructed to connect to the future district energy utility (DEU) system.

Conceptual plans of the rezoning proposal are provided (Attachment 5). A list of Rezoning Considerations (Attachment 6) is provided (signed copy on file).

### Findings of Fact

A Development Application Data (Attachment 4) is provided for comparison of the proposed development with the proposed site specific zone requirements.

### Site and Surrounding Development

The subject site is located on the northeast corner of No. 3 Road and Anderson Road. The site is relatively flat and is currently preloaded in preparation for construction. The previous low scale development has been removed.

Properties in the surrounding area have been or are likely to be redeveloped with higher density commercial, residential and mixed used developments. Please refer to the Brighthouse Village Specific Land Use Map for additional information (Attachment 3). Current and future potential surrounding development includes:

To the North: Three lots fronting No. 3 Road developed with low scale commercial buildings

and surface parking to the rear. Also, to the north, two lots facing Park Road. All lots to the north could be redeveloped under the current Downtown Commercial (CDT1) zoning or could be rezoned under the CCAP, resulting in a commercial or mixed use podium and tower development with an FAR ranging between 3.0 and 4.0 and a maximum height of 47.0 m GSC.

To the South: Across Anderson Road, four lots fronting No. 3 Road developed with low scale commercial buildings and surface parking to the rear, and, at 8080 Anderson Road, an affordable housing development (currently under construction) that was approved with an FAR of 3.48 and a height of 43.5 m GSC (*DP 12-605094*). The properties fronting No. 3 Road could be redeveloped under the current Downtown Commercial (CDT1) zoning or could be rezoned under the CCAP, resulting in a commercial or mixed use podium and tower development with an FAR of between 3.0 and 4.0 and a maximum height of 47 m GSC.

To the East: An existing commercial and residential podium and tower development, with internal parking (*DP 91-000172*). Further to the east, a recently approved mixed use podium and tower development will be constructed (*DP 13-645286*).

To the West: Across No. 3 Road, the Richmond City Hall precinct with an eight-storey civic building, landscaped grounds and a combination of underground and surface parking. Additionally, across No. 3 Road, the Richmond Centre site which is currently developed with a two-storey mall surrounded by surface parking and is also under application to amend the OCP to adjust land use designation boundaries (*CP 16-752923*).

## **Related Policies**

### **A. Official Community Plan/City Centre Area Plan**

Official Community Plan: The Official Community Plan (OCP) designates the site as “Downtown Mixed Use”. The proposed rezoning is consistent with this designation.

City Centre Area Plan: The City Centre Area Plan (CCAP) designates the site as “Urban Core T6 (45m)”. The proposed rezoning is consistent with this designation.

### **B. Other Policies, Strategies and Bylaws**

Flood Protection Management Strategy: The proposed redevelopment must meet the requirements of the Richmond Flood Plain Designation and Protection Bylaw 8204. Registration of a flood indemnity covenant is required prior to final adoption of the rezoning bylaw.

Aircraft Noise Sensitive Development Policy: The proposed development is located in Area 4 on the Aircraft Noise Sensitive Development Map. The proposed redevelopment must address the requirements of the Aircraft Noise Policy including provision of an acoustic consultant report regarding sound attenuation measures to be incorporated into the development. Registration of aircraft noise covenant is required prior to final adoption of the rezoning bylaw.

Mixed Use Noise and Ambient Noise: The proposed development must address additional OCP Noise Management Policies, specifically Mixed Use Noise and Ambient Noise. Requirements include provision of an acoustic consultant report regarding sound attenuation measures and registration of associated noise covenants before final adoption of the rezoning bylaw.

Affordable Housing Strategy: The proposed development provides for affordable housing. Registration of an Affordable Housing Agreement is required prior to final adoption of the rezoning bylaw. The specific details of the affordable housing proposal are provided in Analysis, Section B.2 – Affordable Housing.

Richmond Public Art Policy: The proposed development addresses the Richmond Public Art Policy and provides for a financial contribution toward public art in the Brighthouse No. 3 Road Art Walk. The specific details of the affordable housing proposal are provided in Analysis, Section B.3 – Community Amenities.

District Energy Utilities: The proposed development will be designed to utilize energy from a District Energy Utility when a neighbourhood DEU is implemented. Connection to the future DEU system will be secured with a legal agreement.

### **Public Consultation**

A rezoning notification sign was installed on the subject property. In response, staff received comments from existing tenants, residents of an adjacent property and owners of nearby commercial properties.

Existing Tenants: Existing tenants were concerned about being displaced by the proposed development. The developer and tenants resolved their issues, the tenants have since relocated their businesses and the previous development removed from the site.

Neighbouring Residential Properties: The occupants of one of the mid-level residential units in the building immediately to the east of the subject site (8111 Anderson Road) expressed concern that the new development would eliminate existing western views and reduce privacy. The site is being developed in accordance with the City Centre Area Plan. The applicant has responded to neighbours' privacy concerns with multiple changes to the eastern end of the development. Changes include:

- increasing the side yard setback by approximately 1.5 m at the relevant building level;
- orienting the main windows of the proposed development to the north and south;
- making most of the east façade solid with a few, carefully placed, small windows;
- eliminating access to two deck areas parallel to the east property line;
- adding hedge and tree screening on a second, larger deck area also parallel to the east property line; and
- changing the programming of the second deck to focus on urban agriculture rather than ongoing socializing.

Neighbouring Commercial Properties: Owners of nearby commercial developments have expressed concerns about the impacts of site preloading on the structure and finishing of their buildings. Staff have referred the property owners to the applicant as this is considered to be a civil matter.

## **Advisory Design Panel**

The design of the proposed development (DP 15-708092) was forwarded to the ADP for comment on November 18, 2015. Feedback from the Panel (Attachment 7) led to elimination of an east-west pedestrian connection between No. 3 Road and the evolving east-west lane system to the east. Otherwise, the proposal was well received by Panel members, who recommended a variety of small changes.

## **Analysis**

Staff have reviewed the proposed rezoning and find that it is generally consistent with City policy objectives described in the Official Community Plan (OCP) and City Centre Area Plan (CCAP) including but not limited to: public and private infrastructure; community benefits and amenities; and, basic development conditions such as land use, density and height. Further, the proposed development contributes to an enhanced public realm and addresses potential impacts on surrounding developments.

The applicant has agreed to undertake the considerations of rezoning related to the foregoing as well as those related to subdivision, indemnification and other legal agreements to be registered on title (Attachment 6).

### **A. Proposed Zoning**

The proposed rezoning is consistent with the Brighthouse Village Specific Land Use Map transect land use designation, Urban Core T6 (45 m), which provides for up to 3.0 FAR of mixed use density and eligibility for an additional 1.0 FAR of Village Centre Bonus (VCB) commercial density.

A new site specific zone, "City Centre High Density Mixed Use with Office (ZMU31) – Brighthouse Village", is proposed that incorporates specific requirements regarding the relative amounts of commercial and residential uses, the provision of affordable housing on-site and various form of development parameters.

### **B. CCAP Implementation Policies**

#### **1. Utility, Transportation and Parks Infrastructure**

The proposed infrastructure improvements are summarized below and will be realized through a Servicing Agreement (SA). The infrastructure improvements are not eligible for Development Cost Charge (DCC) credits and will be funded by the developer.

City Utilities: The developer is required to undertake a variety of water, storm water drainage and sanitary sewer frontage works. Included are:

- a water main upgrade on Anderson Road;
- a storm sewer upgrade on Anderson Road;
- a lane drainage upgrade to the north of the subject site as well as the site to the east; and
- a combination of temporary sanitary sewer work and permanent upgrades on Anderson Road that will connect with a new sanitary sewer to be constructed on Buswell Street under the City's Capital Plan.

The frontage and other infrastructure improvements are detailed in the Servicing Agreement section of the Rezoning Considerations (Attachment 6).

Private Utilities: Undergrounding of Hydro service lines is required.

Transportation Network: The CCAP encourages completion and enhancement of the City street and lane network. Based on the City's road network objectives and the submitted Traffic Impact Analysis (TIA) frontage and off-site street, lane and intersection improvements are as follows.

- No. 3 Road: The No. 3 Road vehicle lane widths will remain the same. The back-of-curb cross-section will be widened to accommodate a boulevard, bikeway, greenway and sidewalk, all of which are intended to support an enhanced public realm. A property dedication is required.
- Anderson Road: The Anderson Road vehicle and back-of-curb cross-section widths will remain the same. No dedications are required. The finishing of the back of curb areas will be upgraded, including the frontage of 8111 Anderson Road, to establish a consistent frontage design between No. 3 Road and Buswell Street.
- North-South Lane: Development of a formalized north-south lane system to the east of No. 3 Road will begin with the creation of a new north-south connection through the subject site. Because of the configuration of the site and building, this connection will occur at ground level only and will be secured as a volumetric statutory right of way (SRW). The connection is designed to be used by cars, trucks and pedestrians.
- East-West Lane: There is an evolving east-west lane system running from Buswell Street to the site. The proposed development will contribute to this system with a 3.0 m land dedication from the north east edge of the site along with associated frontage improvements. (Note: Additional contributions to the interim functioning of the evolving east-west lane system are discussed in Analysis, Section C.2 – *Site Access-Off-site*).
- Transportation Impact Analysis Measures (TIA): Based on the findings of the TIA study, various off-site improvements are required as follow.
  - pedestrian upgrades at the No. 3 Road and Anderson Road intersection including:
    - upgrade the crosswalks at the intersection with decorative stamped asphalt treatment and yellow tactile warning pavers at the curb ramps to improve visibility and accessibility of crosswalks;
  - pedestrian upgrades at the Anderson Road and Buswell Road intersection including:
    - installation of two special crosswalk signals (side-mounted) with APS for the north and south legs of the intersection and service panel; pedestrian detection and communications conduit, cable and junction boxes;
    - add new curb ramps on east side per City Engineering Design Specification standards with tactile warning strips; and
  - street sign upgrades at the Granville Avenue and Buswell Street intersection including:
    - upgrade intersection with illuminated street name signs.

Parks and Open Space Network: The CCAP identifies No 3 Road as part of the City's greenway system. The No. 3 Road back-of-curb cross-section accommodates greenway functions.

Public Realm Design – No. 3 Road: Detailed design development of the required frontage improvements will be undertaken through the Development Permit and Servicing Agreement processes. The preliminary public realm plan for the subject development (Attachment 8) shows

the proposed locations and designs for various paths, spaces, hard and soft landscape, street furnishings and finishing. However, as the CCAP envisions an “art walk” along No. 3 Road from the Canada Line Station to Granville Ave., staff are hoping to work with current developers and/or a consultant to develop a comprehensive public realm vision that unifies and celebrates the Brighthouse Village Centre and the Brighthouse section of the No. 3 Road corridor.

Public Realm Design - North-South Lane SRW: The proposed north-south lane runs through the middle of the ground level of the proposed development. To encourage pedestrian use, increase safety and reduce the visual impact of a large opening in the streetwall, the applicant proposes an enhanced design treatment on the ground, walls and ceiling using coloured concrete banding interspersed with embedded lighting. The enhanced design will be implemented through the Development Permit and Servicing Agreement processes.

**2. Affordable Housing**

The CCAP Implementation Strategy, in conjunction with the Affordable Housing Strategy, provides for density bonusing to achieve low end market rental units in residential and mixed use development of 80 or more units. Where there are fewer than 80 units, cash-in-lieu may be provided.

Low End Market Rental Housing (LEMR): Although the proposed development is less than 80 units, the developer has chosen to provide the affordable housing on-site. The proposal includes a total of five (5) LEMR units, with a combined floor area of 395.7 m<sup>2</sup> (4,259.28 sq.ft.) which is 5% of the residential floor area. The proposed LEMR unit allocation includes:

Unit Type	Affordable Housing Strategy Requirements			Project Targets (2)	
	Minimum Unit Area	Maximum Monthly Unit Rent (1)	Total Maximum Household Income (1)	Unit Mix	# of Units
Bachelor	37 m <sup>2</sup> (400 ft <sup>2</sup> )	\$850	\$34,000 or less	0%	0
1-Bedroom	50 m <sup>2</sup> (535 ft <sup>2</sup> )	\$950	\$38,000 or less	40%	2
2- Bedroom	80 m <sup>2</sup> (860 ft <sup>2</sup> )	\$1,162	\$46,500 or less	60%	3
3-Bedroom	91 m <sup>2</sup> (980 ft <sup>2</sup> )	\$1,437	\$57,500 or less	0%	0
TOTAL		N/A	N/A	100%	5

- (1) May be adjusted periodically, as provided for under adopted City policy.
- (2) 100% of affordable housing units shall meet Richmond Basic Universal Housing (BUH) standards or better.

The units will be secured with a housing agreement which will include terms regarding the integration of the affordable units with the market units; tenant access to the indoor and outdoor common amenity areas; and, provision of affordable parking spaces at no additional charge.

**3. Community Amenities**

The CCAP Implementation Strategy includes density bonusing and other measures to support community enhancements that are desirable in the context of City Centre densification. The proposed rezoning includes offers to contribute to the following community amenities in accordance with the OCP.

Child Care: The proposed rezoning is located in the Brighthouse Village Specific Land Use Map “T6” area and is subject to a density bonus provision requiring that one percent (1%) of the residential floor area (excluding affordable housing floor area) be provided to the City in the

form of child care space or a cash-in-lieu contribution to the Childcare Development Reserve Fund and Childcare Operating Contributions accounts (90% and 10% respectively). Community Services staff have reviewed the location of the development and the potential for child care in the available floor area and recommend that the City accept a total cash-in-lieu contribution based on the finished value of the space (a minimum of \$515,105.15 calculated using the proposed floor area  $[0.01 \times 7,361.8 \text{ m}^2 \times \$6,997/\text{m}^2]$ ).

Community Facilities: The proposed rezoning is located in the Brighthouse Village Specific Land Use Map “Village Centre Bonus (VCB)” area and incorporates a VCB density increase of 0.83 FAR. Five percent (5%) of this area is expected to be provided back to the City in the form of community amenity space or a cash-in-lieu contribution to the City Centre Facility Development Fund (100%). Community Services staff have reviewed the location of the development and the potential for community amenities in the limited floor area (202.6 m<sup>2</sup>) and recommend that the City accept a cash-in-lieu contribution based on the finished value of the space (a minimum of \$1,417,398.31 calculated using the proposed floor area  $[0.05 \times .83 \times 4,881.26 \text{ m}^2 \times \$6,997/\text{m}^2]$ ).

Community Planning: The proposed rezoning is subject to a community planning implementation contribution to the CC-Community Planning and Engineering account contribution for future community planning (a minimum of \$50,304.72 calculated using the proposed floor area  $[18,700.64 \text{ m}^2 \times \$2.69/\text{m}^2]$ ).

Public Art: The CCAP looks to public art to enrich and animate the public realm. The subject site is located on No. 3 Road between Granville Avenue and the Brighthouse Canada Line Station, an area specifically identified for development of an “art walk” in the public and adjacent private realm. Community Services staff have considered public art contribution options for this area and recommend that the City accept a cash-in-lieu contribution to the Public Art Provision account (15%) and the Public Art Reserve account (85%) so that a co-ordinated approach for the full length of the art walk (Granville Avenue to the Canada Line Station) can be pursued. The public art contribution is calculated on both the commercial and residential space (a minimum of \$114,861.64 calculated using the proposed floor areas  $[10,943.14 \text{ m}^2 \times \$4.63/\text{m}^2 + 7361.8 \text{ m}^2 \times \$8.72/\text{m}^2]$ ).

**C. Other CCAP Development Policies**

**1. Households and Housing**

Seniors and Special Needs: The CCAP encourages inclusion of seniors and special needs housing close to shops, services, transit and community amenities. The proposed development is consistent with the policy and includes a variety of independent living unit types to support aging in place and different ability needs.

Type	Affordable	Market	Intent	Standard
Aging in Place	0	66	- support mobility and usability	Per OCP
Adaptable + Basic Universal Housing	4	4	- reno potential for wheelchair plus added floor area for manoeuvring	Per BCBC and RZB
Barrier Free	1	0	- move in with wheelchair - includes basic universal housing	Per BCDH



## 2. Transportation

Site Access: Pedestrian and vehicular access is provided as follows.

- Site Access - On-site: Pedestrian access is provided to individual shop fronts on the two street frontages, to an office lobby on No. 3 Road and to a residential lobby on Anderson Road. Vehicular access is provided via the new north-south lane SRW, which can be entered from Anderson Road on the south and from the evolving east-west lane system on the north.
- Site Access - Off-site: The applicant is proposing to utilize the evolving east-west lane system on the north side of the site to support truck movement. To establish a functional lane width, the current dedicated portions of the lane must be supplemented with statutory rights of way (SRWs) on various properties to the north of the subject site. Provision of the SRWs as well as interim upgrades such as curbing and paving are a consideration of rezoning.

Parking and Loading: The proposal addresses the City's parking and loading policy objectives as follows.

- Parking: The proposed parking rates are consistent with the parking provisions of the Richmond Zoning Bylaw including the opportunity to reduce parking in conjunction with transportation demand management (TDM) measures. A 10% TDM reduction is proposed for the commercial (retail) parking and the following TDM measures are offered.
  - On-Site Measures: Proposed on-site measures, to be implemented through the DP, include:
    - end of trip facilities for the commercial uses; and
    - provision of two EV quick-charge car share spaces within the development with cars provided and managed for a minimum of three years by a car share company.
  - Off-Site Measures: Proposed off-site measures, to be implemented through the SA, include:
    - back of curb frontage improvements across the width of 8111 Anderson Road to match those of subject site;
    - lane improvements including installation of a 1.5 m sidewalk along the north side of 8111 Anderson Road; and
    - a contribution of \$50,000 to future upgrading of the traffic signal at Park Road and Buswell Street.
- Loading: The proposed development is consistent with the Richmond Zoning Bylaw loading provisions for medium and large size trucks. An agreement regarding shared commercial/residential use of the medium size truck spaces is required.

Electric Vehicles: The OCP supports integration of new vehicle technologies that reduce use of non-renewable energy. The proposed rezoning will incorporate EV charging into 20% of the residential parking stalls, prepare a further 25% of the residential parking stalls for future installation of EV charging and provide EV charging for 1 per 10 Class 1 bicycle spaces.

## 3. Ecology and Adaptability

Living Landscape: The CCAP looks to development to support and enhance ecological functioning in City Centre through the creation of a continuous and interconnected landscape

system. The proposed development will contribute to the ecological network through a number of measures including:

- retention of existing street trees along No. 3 Road;
- addition of street trees along Anderson Road;
- provision of soft landscape areas in the back-of-curb public realm areas of No. 3 and Anderson Roads that will be designed as multi-layered habitats complete with trees;
- provision of extensive soft landscape, including trees, in the development's common outdoor amenity areas, which are located on multiple floor levels and the residential roof level; and
- provision of intensive/extensive green roofs on other roof levels.

Further review of the landscape proposal will occur with the Development permit process.

Greening of the Built Environment: The proposed development will be designed to achieve a sustainability level equivalent to the Canada Green Building Council LEED Silver certification.

#### **4. Development Concept Review**

The CCAP includes a variety of policies intended to shape development to be livable, functional and complementary to the surrounding public and private realm. Those policies most critical to the development concept at the rezoning stage are reviewed below.

Massing Strategy: The massing of the proposed development is arranged to reflect the allocation of uses on the site and is consistent with the general objectives of the CCAP. Double height retail spaces line both street frontages at the ground level. The office uses are primarily located in a 46.9 m (GSC) high "tower" building that overlooks both No. 3 Road and the interior podium level courtyard. The residential uses are primarily located in a 33.6 m (GSC) high "midrise" building that overlooks Anderson Road and the interior podium-level courtyard. The tower and midrise are set in a lower scale podium base, which is sized, in the case of No. 3 Road, to establish a strong and continuous streetwall on the block face, and, in the case of Anderson Road, to have a more residential scale that will step back in sync with the existing mixed use development to the east. Loading and five levels of parking are located within the podium, along with the north-south lane SRW.

Adjacencies: The relationship of new development to adjacent public and private properties is assessed with the intent that negative impacts are reduced and positive ones enhanced.

- Public Adjacencies: The overall massing arrangement, which pushes the bulk of the building floor area toward the street edges, helps establish comfortable street cross-section proportions on No.3 Road and Anderson Road, both of which are "wider-than-typical" streets. Street animating uses, with large window areas and opportunities for sunny outdoor patios, are located along both streets and weather protection is provided.
- Private Adjacencies: The proposed development is massed to locate the densest and highest forms away from adjacent sites. For future development to the north, this reduces shadowing and overlook impacts and increases tower location options. For existing development to the east (8111 Anderson Road), this optimizes light access and outlook for most of the residential units in the development.

- Common Property Line Interfaces: Because the design of the proposed development anticipates a similar podium and tower style development on the site to the north, there is a long wall on the shared property line. The applicant proposes to embellish this wall with a combination of architectural concrete, painted concrete and metal mesh panels to provide “interim” visual interest. The property line interface with the property to the east is not visible as the podium of the subject development steps along with the podium of the adjacent development.

DP Guidelines: Additional review of the following building features will occur through the Development Permit Application process.

- Parking and Loading: A draft functional plan showing internal truck manoeuvring has been provided and will be finalized through the DP process.
- Waste Management: A draft waste management plan has been submitted and will be finalized through the DP process.
- Rooftop Equipment: Rooftop mechanical equipment and building mounted telecom equipment can be unsightly when viewed from the ground and from surrounding buildings. To prevent diminishment of both the architectural character and the skyline, a more detailed design strategy for rooftop equipment/enclosures is required.
- Common Amenity Spaces: The proposed indoor and outdoor common amenity space areas slightly exceed the OCP and CCAP DP Guidelines expectations, as tabulated in the Development Application Data and Floor Area Summary (Attachment 4). A legal agreement stipulating that all amenity spaces be available to all tenants is a requirement of rezoning. Review of the proposed amenity space programming and landscaping will occur with the DP process.
- Private Amenity Spaces: The City has adopted guidelines for the provision of private outdoor space for residential uses. Assessment of the proposed private amenity areas will be undertaken within the DP process.
- Crime Prevention through Environmental Design (CPTED): The City has adopted policies intended to minimize opportunities for crime and promote a sense of security. A CPTED checklist and plans demonstrating natural access, natural surveillance, defensible space and maintenance measures will be reviewed within the development permit process.
- Accessibility: In addition to providing a variety of accessible units (per Analysis, Section C.1 – Households and Housing), the proposed development will be required to provide good site and building accessibility and visitability. Provision of a checklist along with design implementation will occur within the development permit process.

Form and Character: Within the Development Permit Application process, the form and character of the proposed development is assessed against the expectations of the development Permit Guidelines. As a DP Application was submitted shortly after the Rezoning Application, form and character comments have been provided to the applicant by both staff and the Advisory Design Panel. Additional modifications resulting from Council recommendations or further Advisory Design Panel comments will be addressed within the Development Permit approval process.

## **D. City-wide Policies**

### **1. Tree Retention, Protection and Replacement**

Off-site Trees: Three existing street trees located on No. 3 Road are proposed to be retained and a fourth to be removed to accommodate intersection visibility and bike lane integration. The other two trees are located on adjacent frontages and will be protected. A contribution of \$1,300 to the City's Tree Compensation Fund for the removed tree is a consideration of rezoning.

Tree Management Plan: The applicant has submitted a tree management plan which identifies the six off-site trees and related tree protection measures. Further, the applicant has submitted a Certified Arborist Memo concerning the No. 3 Road street trees that includes recommendations for management of upheaval due to the root system.

Tree Protection: Due to concerns about sidewalk buckling, the No. 3 Road sidewalk was recently repaved on the instructions of Engineering staff. This work, which included pruning of the tree roots, may ultimately compromise the viability of the trees. Should the trees require replacement, appropriate contributions will be managed through the Servicing Agreement process. In the meantime, staff recommend proceeding as though the trees will remain viable.

## **E. Land and Legal Interests**

The proposed rezoning will alter the current property boundaries and legal encumbrances as well as create new ones, as summarized below.

Existing Encumbrances: The applicant has provided a Charge Summary and Opinion prepared by a lawyer. The lawyer advises that encumbrances related to various existing Statutory Rights of Way may be removed and that the proposed rezoning does not create other adverse circumstances. There are six SRWs that may be discharged or, where relevant, modified to accommodate new "public right of passage" SRWs to be provided on properties to the north of the subject site (per east-west lane). The SRWs are described in the Rezoning Considerations (Attachment 6).


Subdivision and New Encumbrances: Sketch survey plans showing the preliminary consolidated site dimensions and site area after required dedications, as well as the location, preliminary dimensions and areas of on-site statutory rights of way, easements and encroachments have been provided (Attachment 9).

## **F. Financial Impact**

The rezoning application results in an insignificant Operational Budget Impact (OBI) for off-site City infrastructure (such as road works, waterworks, storm sewers, sanitary sewers, street lights, street trees and traffic signals).

## Conclusion

The application by 1004732 BC Ltd to rezone the properties at 6840 & 6860 No. 3 Road and 8051 Anderson Road in order to develop a high-density, mixed commercial and residential use high rise building is consistent with City objectives as set out in the OCP, CCAP and other City policies, strategies and bylaws. The public realm and built form designs will set a high standard for redevelopment of the Brighthouse Village No. 3 Road “art walk” corridor and the engineering, transportation and parks improvements, along with the in-kind and in-lieu density bonusing contributions provided by the developer, will help to address a variety of community needs. On this basis, it is recommended that Zoning Bylaw 8500, Amendment Bylaw 9510 be introduced and given first reading.





Janet Digby, Architect AIBC  
Planner 3

JD:rg

- Attachment 1: Rezoning Map
- Attachment 2: Location Map (Aerial)
- Attachment 3: City Centre Brighthouse Village Specific Land Use Map
- Attachment 4: Development Application Data (per applicant)
- Attachment 5: Rezoning Proposal Conceptual Plans (per applicant)
- Attachment 6: Rezoning Considerations
- Attachment 7: Advisory Design Panel Minutes (per ADP)
- Attachment 8: Subject Site Public Realm Concept Plan (per applicant)
- Attachment 9: Sketch Survey Plans (Subdivision)  
Sketch Survey Plans (SRWs)

Enclosure



RZ 14-678448

Original Date: 01/12/15

Revision Date:

Note: Dimensions are in METRES




RZ 14-678448

Original Date: 01/12/15

Revision Date

Note: Dimensions are in METRES

**Specific Land Use Map: Brighthouse Village (2031)**







**Development Application (RZ)  
Data and Floor Area Summary**

<b>RZ 14-678448</b>	
Address:	6840 and 6860 No 3 Road and 8051 Anderson Road
Owner/Applicant:	1004732 BC Ltd / 1004732 BC Ltd
Planning Area(s):	City Centre Area Plan – Brighthouse Village – T6 (45m) – VCB Overlay – Sub-Area B.4
Other Area(s):	Aircraft Noise Sensitive Use Area 4 – Flood Construction Level Area A

<b>RZ 14-678448</b>	<b>Existing</b>	<b>Proposed</b>
OCP Designation:	Downtown Mixed Use	Downtown Mixed Use
Land Uses:	Commercial	Commercial & Residential
Zoning:	CDT1	ZMU31
Site Area (before and after dedications):	5,219.39 m <sup>2</sup>	4,778.50 m <sup>2</sup>
Net Development Site Area (for floor area calculation):	N/A	4,881.26 m <sup>2</sup>
Number of Residential Units:	0	75

<b>RZ 14-678448</b>	<b>Proposed Site Specific Zone</b>	<b>Proposed Development</b>	<b>Variance</b>
Base FAR (max):	3.00	3.00	
Village Centre Bonus (VCB) (max):	0.85	0.83	
Commercial FAR (max):	2.25	2.24	
Residential FAR (max.):	1.60	1.59	
Total FAR (max):	3.85	3.83	
Indoor Amenity Space FAR Increase (max):	0.1	0.03	
Floor Area Gross (not including parking):	n/a	19,037.00 m <sup>2</sup>	
Floor Area FAR (max):	19,525.04 m <sup>2</sup>	18,700.64 m <sup>2</sup>	
Lot Coverage (max.):	90%	64%	
Setback – Front Yard (min):	3.8 m/0.8 m	3.89 m/0.84 m	
Setback – Exterior Side Yard (min):	3.8 m/1.5 m	4.01 m/1.52 m	
Setback – Interior Side Yard (min):	0.0 m	0.0 m	
Setback – Rear Yard (min):	0.0 m	0.0 m	
Height Dimensional (geodetic) (max):	47 m	46.94 m	
Height Accessory (max):	n/a	n/a	
Subdivision/Lot Size (minimum):	4780 m <sup>2</sup>	4,778.5 m <sup>2</sup>	
Off-street Parking – Commercial (incl. Accessible, EV, CS) (min):	141	155	
Off-street Parking – Residential (incl. Accessible, EV,CS) (min):	75	82	
Off-Street Parking – Visitor Parking (shared) (min):	15	15	
Off-Street Parking – Disabled (Commerc'I + Resident'I) (min):	4	5	
Off-street Parking – Total (incl. Accessible, EV, CS) (min):	216	237	
TDM Reduction (max):	10%	10% (commercial only)	
Tandem Parking Spaces (max):	n/a	n/a	
Class 1 Bicycle Parking – Commercial (min):	24	24	
Class 2 Bicycle Parking – Commercial (min):	35	35	
Class 1 Bicycle Parking – Residential (min):	94	94	
Class 2 Bicycle Parking – Residential (min):	15	15	
Loading – Medium (min):	3	3	
Loading – Large (min):	2	2	
Amenity Space – Common Outdoor (min):	938 m <sup>2</sup>	1115 m <sup>2</sup>	
Amenity Space – Common Child Play (min):	225 m <sup>2</sup>	225 m <sup>2</sup>	
Amenity Space – Common Indoor (min):	100 m <sup>2</sup>	135 m <sup>2</sup>	

# gbl

800-445-6787  
 1000 WEST 10TH AVENUE  
 SUITE 1000  
 VANCOUVER, BRITISH COLUMBIA V6H 3G9  
 TEL: 604-681-2222  
 FAX: 604-681-2223  
 WWW.GBLARCHITECTURE.COM

PROJECT NO. 15-0000000000  
 DATE: 15-00-0000  
 SHEET NO. 15-00-0000

**REVISIONS**  
 NO. DATE DESCRIPTION  
 1 15-00-0000 15-00-0000  
 2 15-00-0000 15-00-0000  
 3 15-00-0000 15-00-0000  
 4 15-00-0000 15-00-0000



Nb 3 ROAD PERSPECTIVE



CORNER VIEW



INTERIOR LANE ENTRANCE AT ANDERSON RD.

**IFORTUNE Centre Anderson Roa**  
 8051 Anderson Road  
 Richmond, BC  
 RZ 14-078448 / DP 15-708092  
 MIXED USE DEVELOPMENT

**3D IMAGES**  
 DATE: 15-00-0000  
 DRAWN BY: [Name]  
 CHECKED BY: [Name]  
 SCALE: 1:441  
 JOB NUMBER: 15-00-0000

**A-6.01**

ATTACHMENT 5

VIEW FROM ANDERSON STREET



**gbl**

1000 AVENUE 10  
VANCOUVER, CANADA V6P 6E9  
TEL: 604.278.1234  
WWW.GBLINC.COM

NOTES  
1. 1/18/2018

REVISIONS  
NO. DATE BY  
1 1/18/2018 JLM  
2 2/1/2018 JLM  
3 2/1/2018 JLM  
4 2/1/2018 JLM

PROPOSED DEVELOPMENT



3D VIEW OF BUILDING ADJACENCIES TO THE EAST

IPORTUNE Centre Anderson Row  
8051 Anderson Road  
Richmond, BC  
RZ 14-478448 / DP 15-708892  
MIXED USE DEVELOPMENT

3D IMAGES

DATE 1/18/2018  
DRAWN BY JLM  
SCALE 1:441  
JOB NUMBER 1441

A-6.02



PWL Partnership  
 10000 North Central Expressway, Suite 100  
 Dallas, TX 75243  
 (214) 416-1000  
 www.pwlpartnership.com

gbl

- LEGEND
- 1. EXISTING
  - 2. PROPOSED
  - 3. EXISTING
  - 4. PROPOSED
  - 5. EXISTING
  - 6. PROPOSED


FORTUNE CENTRE  
 ANDERSON ROAD

RENDER PLAN

SCALE  
 3/32" = 1'


DATE  
 11/18/2010  
 TIME  
 10:00 AM  
 DRAWN BY  
 J. J. JONES  
 CHECKED BY  
 J. J. JONES

L1.00



ATTACHMENT 5

1	CONCRETE	CONCRETE
2	ASPHALT	ASPHALT
3	PAVING	PAVING
4	GRASS	GRASS
5	LANDSCAPE	LANDSCAPE



PROPERTY LINE

LIGHTING LEGEND

KEY	DESCRIPTION
1	IN ROAD LIGHTING

SITE FURNISHING LEGEND

KEY	DESCRIPTION
1	BENCH - TYPE 1
2	BENCH - TYPE 2
3	BENCH - TYPE 3
4	OUTDOOR FURNITURE
5	INVEST TABLE AND CHAIR
6	CONCRETE PLANTER
7	URBAN AGRICULTURE PLANTER
8	PLANTER POT
9	OUTDOOR BIRD AND COUNTRY
10	PLAY EQUIPMENT - METAL TUBE
11	STORAGE AND COMPOST
12	BIKE RACK
13	TREE GRATE
14	PLAY EQUIPMENT - RESILIENT MALL
15	PLAY EQUIPMENT - BLOOD
16	BIKE CHECK SET

PAVING LEGEND

KEY	DESCRIPTION
1	CP CONCRETE PAVING
2	STONE PAVING
3	COLOR CONCRETE PAVING - TYPE 1
4	COLOR CONCRETE PAVING - TYPE 2
5	UNIT PAVES - TYPE 1
6	UNIT PAVES - TYPE 2
7	HYDROCOMPRESSED SLAB
8	BEARING
9	RESILIENCE SURFACE
10	ARTIFICIAL TURF (PUTTING GREEN)
11	ASPHALT
12	REFER TO CIVIL DRAWINGS

HARDSCAPE LEGEND

KEY	DESCRIPTION
1	METAL DATE
2	PRIVACY SCREEN
3	METAL TRELLIS

LAYOUT AND MATERIALS GENERAL NOTES

1. LAYOUT AND MATERIALS DRAWINGS ARE TO BE READ IN CONJUNCTION WITH LANDSCAPE SPECIFICATIONS.
2. REPORT ANY DISCREPANCIES TO CONSULTANT FOR REVIEW AND RESPONSE.
3. LAYOUT AND MATERIALS DRAWINGS ARE TO BE READ IN CONJUNCTION WITH LANDSCAPE SPECIFICATIONS.
4. REPORT ANY DISCREPANCIES TO CONSULTANT FOR REVIEW AND RESPONSE.

DRAIN LEGEND

KEY	DESCRIPTION
1	AREA DRAIN
2	SLAB DRAIN
3	PLANTER DRAIN
4	RESIDENTIAL BIKE PARKING STALLS
5	COMMERCIAL BIKE PARKING STALLS

GRADING LEGEND

KEY	DESCRIPTION
1	Building Elevation
2	Proposed Elevation
3	Finished Floor Elevation
4	Proposed Top of Wall Elevation
5	Proposed Bottom of Wall Elevation
6	Area Drain
7	Slab Drain
8	Planter Drain

NOTE: CONFIRM DRAIN LOCATIONS WITH MECHANICAL, CIVIL AND ARCH DRAWINGS. REPORT ANY DISCREPANCIES.

FORTUNE CENTRE  
 ANDERSON ROAD

LAYOUT, MATERIAL AND GRADING LEVEL 1

DATE	3/22/20
SCALE	AS SHOWN
PROJECT	14104 FORTUNE
DATE	10-20-18 AT 11:00:00 PM
DESIGNER	ELI AVNY
CHECKER	DEB

L1.01

**gbl**


**GENERAL NOTES:**  
1. ALL WORK SHALL BE IN ACCORDANCE WITH THE BC BUILDING ACT AND THE BC BUILDING REGULATIONS.  
2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.  
3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY UTILITIES INFORMATION AND SHALL BE RESPONSIBLE FOR PROTECTING ALL UTILITIES.  
4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY ACCESS AND EGRESS INFORMATION AND SHALL BE RESPONSIBLE FOR MAINTAINING ALL ACCESS AND EGRESS.  
5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY SURVEY INFORMATION AND SHALL BE RESPONSIBLE FOR MAINTAINING ALL SURVEY MARKERS.

**NOTES:**  
1. ALL WORK SHALL BE IN ACCORDANCE WITH THE BC BUILDING ACT AND THE BC BUILDING REGULATIONS.  
2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS.  
3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY UTILITIES INFORMATION AND SHALL BE RESPONSIBLE FOR PROTECTING ALL UTILITIES.  
4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY ACCESS AND EGRESS INFORMATION AND SHALL BE RESPONSIBLE FOR MAINTAINING ALL ACCESS AND EGRESS.  
5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY SURVEY INFORMATION AND SHALL BE RESPONSIBLE FOR MAINTAINING ALL SURVEY MARKERS.

**REVISIONS:**  
NO. DATE DESCRIPTION  
1 01/15/2018 INITIAL DESIGN  
2 02/15/2018 REVISED PER COMMENTS  
3 03/15/2018 REVISED PER COMMENTS  
4 04/15/2018 REVISED PER COMMENTS  
5 05/15/2018 REVISED PER COMMENTS  
6 06/15/2018 REVISED PER COMMENTS  
7 07/15/2018 REVISED PER COMMENTS  
8 08/15/2018 REVISED PER COMMENTS  
9 09/15/2018 REVISED PER COMMENTS  
10 10/15/2018 REVISED PER COMMENTS

**FORTUNE Centre Anderson Road**  
8051 Anderson Road  
Richmond, BC  
R2 14-578/048 / DP 15-108092  
MIXED USE DEVELOPMENT

**L1 SITE PLAN**  
DATE: 10/15/2018  
DRAWN BY: [Name]  
CHECKED BY: [Name]  
SCALE: 1/8" = 1'-0"  
JOB NUMBER: 1441



**A-1.06**

**ATTACHMENT 5**

177 WEST 10TH AVENUE  
VANCOUVER, BC V6P 2T9  
TEL: 604.681.1111  
WWW.GBLINC.COM


NO. 1015  
REV. 01/20/2018

REVISIONS  
NO. DATE  
1 01/20/2018  
2 02/01/2018  
3 02/01/2018  
4 02/01/2018  
5 02/01/2018  
6 02/01/2018  
7 02/01/2018  
8 02/01/2018  
9 02/01/2018  
10 02/01/2018


**FORTUNE Centre Anderson Road**  
8057 Anderson Road  
Richmond, BC  
RZ 14-5784/8 / DP 15-7881/2  
MIXED USE DEVELOPMENT

**NORTH & SOUTH ELEVATIONS**


DATE: 01/20/2018  
DRAWN BY: AB  
SCALE: 1/8" = 1'-0"  
JOB NUMBER: 1441



NORTH ELEVATION



SOUTH ELEVATION



## WEST ELEVATION

**FORTUNE Centre Anderson Road**  
 8051 Anderson Road  
 Richmond, BC  
 RZ 14-678448 / DP 15-708092  
 MIXED USE DEVELOPMENT

**WEST ELEVATION**

DATE: 10/10/14  
 DRAWN BY: JG  
 CHECKED BY: JG  
 SCALE: 1/8" = 1'-0"  
 JOB NUMBER: 1441




**gbl**

510 EAST BIRCH AVE  
 VANCOUVER, BC V6C 2G8  
 TEL: 604.278.1111  
 FAX: 604.278.1112  
 WWW.GBLARCHITECTURE.COM


PROJECT NO. 1444  
 DATE: 11/11/11  
 DRAWN BY: [Name]  
 CHECKED BY: [Name]  
 APPROVED BY: [Name]

REMARKS:  
 1. ALL DIMENSIONS ARE IN METERS UNLESS OTHERWISE NOTED.  
 2. ALL FINISHES ARE TO BE DETERMINED BY THE CLIENT.  
 3. ALL MATERIALS ARE TO BE APPROVED BY THE ARCHITECT.  
 4. ALL WORK IS TO BE IN ACCORDANCE WITH THE BC BUILDING CODE.  
 5. ALL UTILITIES ARE TO BE MAINTAINED AND PROTECTED.  
 6. ALL EXISTING STRUCTURES ARE TO BE DEMOLISHED AND REBUILT.  
 7. ALL NEW STRUCTURES ARE TO BE BUILT TO THE SPECIFICATIONS.  
 8. ALL WORK IS TO BE COMPLETED WITHIN THE SPECIFIED TIME FRAME.  
 9. ALL COSTS ARE TO BE INCLUDED IN THE BUDGET.  
 10. ALL RISKS ARE TO BE MITIGATED.




SOUTH ELEVATION

SOUTH STREETScape (ANDERSON ROAD)



WEST ELEVATION

WEST STREETScape (No 3 ROAD)




NORTH STREETScape

ATTACHMENT 5


**FORTUNE Centre Anderson Rca**  
 8051 Anderson Road  
 Richmond, BC  
 RZ 14-07848 / DP 15-70892  
 MIXED USE DEVELOPMENT

**STREETScape ELEVATIONS**  
 DATE: 11/11/11  
 DRAWN BY: [Name]  
 CHECKED BY: [Name]  
 SCALE: 1/4" = 1'-0"  
 APP NUMBER: 1444

**A-4.03**



SECTION A-A



SECTION B-B











PROJECT NO. 15-00092  
 DATE 12/15/15  
 DRAWN BY J. HARRIS  
 CHECKED BY M. BROWN  
 APPROVED BY S. HARRIS

REMARKS:  
 1. ALL WORK SHALL BE IN ACCORDANCE WITH THE BC BUILDING ACT AND THE BC BUILDING REGULATIONS.  
 2. ALL WORK SHALL BE IN ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE (NEC) AND THE NATIONAL FIRE ALARM AND SIGNALING CODE (NFPA 72).  
 3. ALL WORK SHALL BE IN ACCORDANCE WITH THE NATIONAL MECHANICAL CODE (NMC) AND THE NATIONAL PLUMBING AND HEATING CODE (NPHC).  
 4. ALL WORK SHALL BE IN ACCORDANCE WITH THE NATIONAL SANITARY ENGINEERING CODE (NSPE) AND THE NATIONAL GAS CODE (NCG).  
 5. ALL WORK SHALL BE IN ACCORDANCE WITH THE NATIONAL CONSTRUCTION CODE (NCC) AND THE NATIONAL CONSTRUCTION REGULATIONS.

ABBREVIATIONS:  
 S.U.T. - Shared Universal Trenching Features

NOTES:  
 1. A minimum of 20% of parking stalls to be electric vehicle charging stalls.  
 2. 20% of parking stalls to be constructed to accommodate electric vehicle charging equipment.  
 3. 20% of parking stalls to be constructed to accommodate electric vehicle charging equipment.

REVISIONS:  
 NO. DATE DESCRIPTION  
 1 12/15/15 ISSUE FOR PERMITTING  
 2 12/15/15 ISSUE FOR PERMITTING  
 3 12/15/15 ISSUE FOR PERMITTING  
 4 12/15/15 ISSUE FOR PERMITTING  
 5 12/15/15 ISSUE FOR PERMITTING

PROJECT NO. 15-00092  
 DATE 12/15/15  
 DRAWN BY J. HARRIS  
 CHECKED BY M. BROWN  
 APPROVED BY S. HARRIS

PROJECT NO. 15-00092  
 DATE 12/15/15  
 DRAWN BY J. HARRIS  
 CHECKED BY M. BROWN  
 APPROVED BY S. HARRIS


PROJECT NO. 15-00092  
 DATE 12/15/15  
 DRAWN BY J. HARRIS  
 CHECKED BY M. BROWN  
 APPROVED BY S. HARRIS

PROJECT NO. 15-00092  
 DATE 12/15/15  
 DRAWN BY J. HARRIS  
 CHECKED BY M. BROWN  
 APPROVED BY S. HARRIS

PROJECT NO. 15-00092  
 DATE 12/15/15  
 DRAWN BY J. HARRIS  
 CHECKED BY M. BROWN  
 APPROVED BY S. HARRIS

PROJECT NO. 15-00092  
 DATE 12/15/15  
 DRAWN BY J. HARRIS  
 CHECKED BY M. BROWN  
 APPROVED BY S. HARRIS

PROJECT NO. 15-00092  
 DATE 12/15/15  
 DRAWN BY J. HARRIS  
 CHECKED BY M. BROWN  
 APPROVED BY S. HARRIS



Anderson Road  
 8051 Anderson Road  
 Richmond, BC  
 RZ 14-678448 / DP 15-708092  
 MIXED USE DEVELOPMENT

FLOOR PLAN  
 DATE 12/15/15  
 DRAWN BY J. HARRIS  
 CHECKED BY M. BROWN  
 SCALE 1/4" = 1'-0"  
 APP. NUMBER 1441

A-3.03  
 ATTACHMENT 5

GBL ARCHITECTS  
 1000 WEST 10TH AVENUE  
 VANCOUVER, BC V6H 2Y6  
 TEL: 604-681-1111  
 WWW.GBLARCHITECTS.COM

**NOTES**  
 1. A minimum of 20% of parking stalls to accommodate electric vehicle (EV) charging equipment.  
 2. 25% of parking stalls to be constructed to accommodate electric vehicle charging equipment, e.g. pre-installed for future EV charging.

**REVISIONS**  
 NO. DATE  
 1 10/10/14  
 2 11/10/14  
 3 12/10/14  
 4 01/10/15  
 5 02/10/15  
 6 03/10/15  
 7 04/10/15  
 8 05/10/15  
 9 06/10/15  
 10 07/10/15  
 11 08/10/15  
 12 09/10/15  
 13 10/10/15  
 14 11/10/15  
 15 12/10/15  
 16 01/10/16  
 17 02/10/16  
 18 03/10/16  
 19 04/10/16  
 20 05/10/16  
 21 06/10/16  
 22 07/10/16  
 23 08/10/16  
 24 09/10/16  
 25 10/10/16  
 26 11/10/16  
 27 12/10/16  
 28 01/10/17  
 29 02/10/17  
 30 03/10/17  
 31 04/10/17  
 32 05/10/17  
 33 06/10/17  
 34 07/10/17  
 35 08/10/17  
 36 09/10/17  
 37 10/10/17  
 38 11/10/17  
 39 12/10/17  
 40 01/10/18  
 41 02/10/18  
 42 03/10/18  
 43 04/10/18  
 44 05/10/18  
 45 06/10/18  
 46 07/10/18  
 47 08/10/18  
 48 09/10/18  
 49 10/10/18  
 50 11/10/18  
 51 12/10/18  
 52 01/10/19  
 53 02/10/19  
 54 03/10/19  
 55 04/10/19  
 56 05/10/19  
 57 06/10/19  
 58 07/10/19  
 59 08/10/19  
 60 09/10/19  
 61 10/10/19  
 62 11/10/19  
 63 12/10/19  
 64 01/10/20  
 65 02/10/20  
 66 03/10/20  
 67 04/10/20  
 68 05/10/20  
 69 06/10/20  
 70 07/10/20  
 71 08/10/20  
 72 09/10/20  
 73 10/10/20  
 74 11/10/20  
 75 12/10/20  
 76 01/10/21  
 77 02/10/21  
 78 03/10/21  
 79 04/10/21  
 80 05/10/21  
 81 06/10/21  
 82 07/10/21  
 83 08/10/21  
 84 09/10/21  
 85 10/10/21  
 86 11/10/21  
 87 12/10/21  
 88 01/10/22  
 89 02/10/22  
 90 03/10/22  
 91 04/10/22  
 92 05/10/22  
 93 06/10/22  
 94 07/10/22  
 95 08/10/22  
 96 09/10/22  
 97 10/10/22  
 98 11/10/22  
 99 12/10/22  
 100 01/10/23  
 101 02/10/23  
 102 03/10/23  
 103 04/10/23  
 104 05/10/23  
 105 06/10/23  
 106 07/10/23  
 107 08/10/23  
 108 09/10/23  
 109 10/10/23  
 110 11/10/23  
 111 12/10/23  
 112 01/10/24  
 113 02/10/24  
 114 03/10/24  
 115 04/10/24  
 116 05/10/24  
 117 06/10/24  
 118 07/10/24  
 119 08/10/24  
 120 09/10/24  
 121 10/10/24  
 122 11/10/24  
 123 12/10/24  
 124 01/10/25  
 125 02/10/25  
 126 03/10/25  
 127 04/10/25  
 128 05/10/25  
 129 06/10/25  
 130 07/10/25  
 131 08/10/25  
 132 09/10/25  
 133 10/10/25  
 134 11/10/25  
 135 12/10/25  
 136 01/10/26  
 137 02/10/26  
 138 03/10/26  
 139 04/10/26  
 140 05/10/26  
 141 06/10/26  
 142 07/10/26  
 143 08/10/26  
 144 09/10/26  
 145 10/10/26  
 146 11/10/26  
 147 12/10/26  
 148 01/10/27  
 149 02/10/27  
 150 03/10/27  
 151 04/10/27  
 152 05/10/27  
 153 06/10/27  
 154 07/10/27  
 155 08/10/27  
 156 09/10/27  
 157 10/10/27  
 158 11/10/27  
 159 12/10/27  
 160 01/10/28  
 161 02/10/28  
 162 03/10/28  
 163 04/10/28  
 164 05/10/28  
 165 06/10/28  
 166 07/10/28  
 167 08/10/28  
 168 09/10/28  
 169 10/10/28  
 170 11/10/28  
 171 12/10/28  
 172 01/10/29  
 173 02/10/29  
 174 03/10/29  
 175 04/10/29  
 176 05/10/29  
 177 06/10/29  
 178 07/10/29  
 179 08/10/29  
 180 09/10/29  
 181 10/10/29  
 182 11/10/29  
 183 12/10/29  
 184 01/10/30  
 185 02/10/30  
 186 03/10/30  
 187 04/10/30  
 188 05/10/30  
 189 06/10/30  
 190 07/10/30  
 191 08/10/30  
 192 09/10/30  
 193 10/10/30  
 194 11/10/30  
 195 12/10/30  
 196 01/10/31  
 197 02/10/31  
 198 03/10/31  
 199 04/10/31  
 200 05/10/31  
 201 06/10/31  
 202 07/10/31  
 203 08/10/31  
 204 09/10/31  
 205 10/10/31  
 206 11/10/31  
 207 12/10/31  
 208 01/10/32  
 209 02/10/32  
 210 03/10/32  
 211 04/10/32  
 212 05/10/32  
 213 06/10/32  
 214 07/10/32  
 215 08/10/32  
 216 09/10/32  
 217 10/10/32  
 218 11/10/32  
 219 12/10/32  
 220 01/10/33  
 221 02/10/33  
 222 03/10/33  
 223 04/10/33  
 224 05/10/33  
 225 06/10/33  
 226 07/10/33  
 227 08/10/33  
 228 09/10/33  
 229 10/10/33  
 230 11/10/33  
 231 12/10/33  
 232 01/10/34  
 233 02/10/34  
 234 03/10/34  
 235 04/10/34  
 236 05/10/34  
 237 06/10/34  
 238 07/10/34  
 239 08/10/34  
 240 09/10/34  
 241 10/10/34  
 242 11/10/34  
 243 12/10/34  
 244 01/10/35  
 245 02/10/35  
 246 03/10/35  
 247 04/10/35  
 248 05/10/35  
 249 06/10/35  
 250 07/10/35  
 251 08/10/35  
 252 09/10/35  
 253 10/10/35  
 254 11/10/35  
 255 12/10/35  
 256 01/10/36  
 257 02/10/36  
 258 03/10/36  
 259 04/10/36  
 260 05/10/36  
 261 06/10/36  
 262 07/10/36  
 263 08/10/36  
 264 09/10/36  
 265 10/10/36  
 266 11/10/36  
 267 12/10/36  
 268 01/10/37  
 269 02/10/37  
 270 03/10/37  
 271 04/10/37  
 272 05/10/37  
 273 06/10/37  
 274 07/10/37  
 275 08/10/37  
 276 09/10/37  
 277 10/10/37  
 278 11/10/37  
 279 12/10/37  
 280 01/10/38  
 281 02/10/38  
 282 03/10/38  
 283 04/10/38  
 284 05/10/38  
 285 06/10/38  
 286 07/10/38  
 287 08/10/38  
 288 09/10/38  
 289 10/10/38  
 290 11/10/38  
 291 12/10/38  
 292 01/10/39  
 293 02/10/39  
 294 03/10/39  
 295 04/10/39  
 296 05/10/39  
 297 06/10/39  
 298 07/10/39  
 299 08/10/39  
 300 09/10/39  
 301 10/10/39  
 302 11/10/39  
 303 12/10/39  
 304 01/10/40  
 305 02/10/40  
 306 03/10/40  
 307 04/10/40  
 308 05/10/40  
 309 06/10/40  
 310 07/10/40  
 311 08/10/40  
 312 09/10/40  
 313 10/10/40  
 314 11/10/40  
 315 12/10/40  
 316 01/10/41  
 317 02/10/41  
 318 03/10/41  
 319 04/10/41  
 320 05/10/41  
 321 06/10/41  
 322 07/10/41  
 323 08/10/41  
 324 09/10/41  
 325 10/10/41  
 326 11/10/41  
 327 12/10/41  
 328 01/10/42  
 329 02/10/42  
 330 03/10/42  
 331 04/10/42  
 332 05/10/42  
 333 06/10/42  
 334 07/10/42  
 335 08/10/42  
 336 09/10/42  
 337 10/10/42  
 338 11/10/42  
 339 12/10/42  
 340 01/10/43  
 341 02/10/43  
 342 03/10/43  
 343 04/10/43  
 344 05/10/43  
 345 06/10/43  
 346 07/10/43  
 347 08/10/43  
 348 09/10/43  
 349 10/10/43  
 350 11/10/43  
 351 12/10/43  
 352 01/10/44  
 353 02/10/44  
 354 03/10/44  
 355 04/10/44  
 356 05/10/44  
 357 06/10/44  
 358 07/10/44  
 359 08/10/44  
 360 09/10/44  
 361 10/10/44  
 362 11/10/44  
 363 12/10/44  
 364 01/10/45  
 365 02/10/45  
 366 03/10/45  
 367 04/10/45  
 368 05/10/45  
 369 06/10/45  
 370 07/10/45  
 371 08/10/45  
 372 09/10/45  
 373 10/10/45  
 374 11/10/45  
 375 12/10/45  
 376 01/10/46  
 377 02/10/46  
 378 03/10/46  
 379 04/10/46  
 380 05/10/46  
 381 06/10/46  
 382 07/10/46  
 383 08/10/46  
 384 09/10/46  
 385 10/10/46  
 386 11/10/46  
 387 12/10/46  
 388 01/10/47  
 389 02/10/47  
 390 03/10/47  
 391 04/10/47  
 392 05/10/47  
 393 06/10/47  
 394 07/10/47  
 395 08/10/47  
 396 09/10/47  
 397 10/10/47  
 398 11/10/47  
 399 12/10/47  
 400 01/10/48  
 401 02/10/48  
 402 03/10/48  
 403 04/10/48  
 404 05/10/48  
 405 06/10/48  
 406 07/10/48  
 407 08/10/48  
 408 09/10/48  
 409 10/10/48  
 410 11/10/48  
 411 12/10/48  
 412 01/10/49  
 413 02/10/49  
 414 03/10/49  
 415 04/10/49  
 416 05/10/49  
 417 06/10/49  
 418 07/10/49  
 419 08/10/49  
 420 09/10/49  
 421 10/10/49  
 422 11/10/49  
 423 12/10/49  
 424 01/10/50  
 425 02/10/50  
 426 03/10/50  
 427 04/10/50  
 428 05/10/50  
 429 06/10/50  
 430 07/10/50  
 431 08/10/50  
 432 09/10/50  
 433 10/10/50  
 434 11/10/50  
 435 12/10/50  
 436 01/10/51  
 437 02/10/51  
 438 03/10/51  
 439 04/10/51  
 440 05/10/51  
 441 06/10/51  
 442 07/10/51  
 443 08/10/51  
 444 09/10/51  
 445 10/10/51  
 446 11/10/51  
 447 12/10/51  
 448 01/10/52  
 449 02/10/52  
 450 03/10/52  
 451 04/10/52  
 452 05/10/52  
 453 06/10/52  
 454 07/10/52  
 455 08/10/52  
 456 09/10/52  
 457 10/10/52  
 458 11/10/52  
 459 12/10/52  
 460 01/10/53  
 461 02/10/53  
 462 03/10/53  
 463 04/10/53  
 464 05/10/53  
 465 06/10/53  
 466 07/10/53  
 467 08/10/53  
 468 09/10/53  
 469 10/10/53  
 470 11/10/53  
 471 12/10/53  
 472 01/10/54  
 473 02/10/54  
 474 03/10/54  
 475 04/10/54  
 476 05/10/54  
 477 06/10/54  
 478 07/10/54  
 479 08/10/54  
 480 09/10/54  
 481 10/10/54  
 482 11/10/54  
 483 12/10/54  
 484 01/10/55  
 485 02/10/55  
 486 03/10/55  
 487 04/10/55  
 488 05/10/55  
 489 06/10/55  
 490 07/10/55  
 491 08/10/55  
 492 09/10/55  
 493 10/10/55  
 494 11/10/55  
 495 12/10/55  
 496 01/10/56  
 497 02/10/56  
 498 03/10/56  
 499 04/10/56  
 500 05/10/56  
 501 06/10/56  
 502 07/10/56  
 503 08/10/56  
 504 09/10/56  
 505 10/10/56  
 506 11/10/56  
 507 12/10/56  
 508 01/10/57  
 509 02/10/57  
 510 03/10/57  
 511 04/10/57  
 512 05/10/57  
 513 06/10/57  
 514 07/10/57  
 515 08/10/57  
 516 09/10/57  
 517 10/10/57  
 518 11/10/57  
 519 12/10/57  
 520 01/10/58  
 521 02/10/58  
 522 03/10/58  
 523 04/10/58  
 524 05/10/58  
 525 06/10/58  
 526 07/10/58  
 527 08/10/58  
 528 09/10/58  
 529 10/10/58  
 530 11/10/58  
 531 12/10/58  
 532 01/10/59  
 533 02/10/59  
 534 03/10/59  
 535 04/10/59  
 536 05/10/59  
 537 06/10/59  
 538 07/10/59  
 539 08/10/59  
 540 09/10/59  
 541 10/10/59  
 542 11/10/59  
 543 12/10/59  
 544 01/10/60  
 545 02/10/60  
 546 03/10/60  
 547 04/10/60  
 548 05/10/60  
 549 06/10/60  
 550 07/10/60  
 551 08/10/60  
 552 09/10/60  
 553 10/10/60  
 554 11/10/60  
 555 12/10/60  
 556 01/10/61  
 557 02/10/61  
 558 03/10/61  
 559 04/10/61  
 560 05/10/61  
 561 06/10/61  
 562 07/10/61  
 563 08/10/61  
 564 09/10/61  
 565 10/10/61  
 566 11/10/61  
 567 12/10/61  
 568 01/10/62  
 569 02/10/62  
 570 03/10/62  
 571 04/10/62  
 572 05/10/62  
 573 06/10/62  
 574 07/10/62  
 575 08/10/62  
 576 09/10/62  
 577 10/10/62  
 578 11/10/62  
 579 12/10/62  
 580 01/10/63  
 581 02/10/63  
 582 03/10/63  
 583 04/10/63  
 584 05/10/63  
 585 06/10/63  
 586 07/10/63  
 587 08/10/63  
 588 09/10/63  
 589 10/10/63  
 590 11/10/63  
 591 12/10/63  
 592 01/10/64  
 593 02/10/64  
 594 03/10/64  
 595 04/10/64  
 596 05/10/64  
 597 06/10/64  
 598 07/10/64  
 599 08/10/64  
 600 09/10/64  
 601 10/10/64  
 602 11/10/64  
 603 12/10/64  
 604 01/10/65  
 605 02/10/65  
 606 03/10/65  
 607 04/10/65  
 608 05/10/65  
 609 06/10/65  
 610 07/10/65  
 611 08/10/65  
 612 09/10/65  
 613 10/10/65  
 614 11/10/65  
 615 12/10/65  
 616 01/10/66  
 617 02/10/66  
 618 03/10/66  
 619 04/10/66  
 620 05/10/66  
 621 06/10/66  
 622 07/10/66  
 623 08/10/66  
 624 09/10/66  
 625 10/10/66  
 626 11/10/66  
 627 12/10/66  
 628 01/10/67  
 629 02/10/67  
 630 03/10/67  
 631 04/10/67  
 632 05/10/67  
 633 06/10/67  
 634 07/10/67  
 635 08/10/67  
 636 09/10/67  
 637 10/10/67  
 638 11/10/67  
 639 12/10/67  
 640 01/10/68  
 641 02/10/68  
 642 03/10/68  
 643 04/10/68  
 644 05/10/68  
 645 06/10/68  
 646 07/10/68  
 647 08/10/68  
 648 09/10/68  
 649 10/10/68  
 650 11/10/68  
 651 12/10/68  
 652 01/10/69  
 653 02/10/69  
 654 03/10/69  
 655 04/10/69  
 656 05/10/69  
 657 06/10/69  
 658 07/10/69  
 659 08/10/69  
 660 09/10/69  
 661 10/10/69  
 662 11/10/69  
 663 12/10/69  
 664 01/10/70  
 665 02/10/70  
 666 03/10/70  
 667 04/10/70  
 668 05/10/70  
 669 06/10/70  
 670 07/10/70  
 671 08/10/70  
 672 09/10/70  
 673 10/10/70  
 674 11/10/70  
 675 12/10/70  
 676 01/10/71  
 677 02/10/71  
 678 03/10/71  
 679 04/10/71  
 680 05/10/71  
 681 06/10/71  
 682 07/10/71  
 683 08/10/71  
 684 09/10/71  
 685 10/10/71  
 686 11/10/71  
 687 12/10/71  
 688 01/10/72  
 689 02/10/72  
 690 03/10/72  
 691 04/10/72  
 692 05/10/72  
 693 06/10/72  
 694 07/10/72  
 695 08/10/72  
 696 09/10/72  
 697 10/10/72  
 698 11/10/72  
 699 12/10/72  
 700 01/10/73  
 701 02/10/73  
 702 03/10/73  
 703 04/10/73  
 704 05/10/73  
 705 06/10/73  
 706 07/10/73  
 707 08/10/73  
 708 09/10/73  
 709 10/10/73  
 710 11/10/73  
 711 12/10/73  
 712 01/10/74  
 713 02/10/74  
 714 03/10/74  
 715 04/10/74  
 716 05/10/74  
 717 06



DE ARCHITECTS  
1000 WEST 10TH AVENUE  
VANCOUVER, CANADA V6H 3G9  
VANCOUVER OFFICE  
VANCOUVER TEL: 604-681-1111  
VANCOUVER FAX: 604-681-1112  
WWW.GBLARCHITECTS.COM  
PROJECT NO. 1441


NOTES  
NO. 10000000

REMARKS  
NO. 10000000  
DATE: 11/11/11  
DRAWN BY: J. BROWN  
CHECKED BY: J. BROWN  
DATE: 11/11/11  
SCALE: AS SHOWN  
PROJECT NO.: 1441  
PROJECT NAME: FORTUNE CENTRE ANDERSON ROAD  
PROJECT ADDRESS: 8051 ANDERSON ROAD, RICHMOND, BC  
PROJECT TYPE: MIXED USE DEVELOPMENT



**FORTUNE Centre Anderson Road**  
8051 Anderson Road  
Richmond, BC  
RZ 14-078448 / DP 15-708092  
MIXED USE DEVELOPMENT

**FLOOR PLAN**  
DATE: 11/11/11  
DRAWN BY: J. BROWN  
CHECKED BY: J. BROWN  
SCALE: AS SHOWN  
PROJECT NO.: 1441  
PROJECT NAME: FORTUNE CENTRE ANDERSON ROAD  
PROJECT ADDRESS: 8051 ANDERSON ROAD, RICHMOND, BC  
PROJECT TYPE: MIXED USE DEVELOPMENT



STANDARD CONTRACT DOCUMENTS  
 2012 EDITION  
 1.01 GENERAL CONDITIONS  
 1.02 SPECIFICATIONS  
 1.03 SCHEDULE OF VALUES  
 1.04 ADDENDUMS

NOTES  
 1. REFER TO DRAWING NO. A-3.06 FOR FLOOR PLAN  
 2. REFER TO DRAWING NO. A-3.07 FOR FLOOR PLAN  
 3. REFER TO DRAWING NO. A-3.08 FOR FLOOR PLAN  
 4. REFER TO DRAWING NO. A-3.09 FOR FLOOR PLAN  
 5. REFER TO DRAWING NO. A-3.10 FOR FLOOR PLAN  
 6. REFER TO DRAWING NO. A-3.11 FOR FLOOR PLAN  
 7. REFER TO DRAWING NO. A-3.12 FOR FLOOR PLAN  
 8. REFER TO DRAWING NO. A-3.13 FOR FLOOR PLAN  
 9. REFER TO DRAWING NO. A-3.14 FOR FLOOR PLAN  
 10. REFER TO DRAWING NO. A-3.15 FOR FLOOR PLAN  
 11. REFER TO DRAWING NO. A-3.16 FOR FLOOR PLAN  
 12. REFER TO DRAWING NO. A-3.17 FOR FLOOR PLAN  
 13. REFER TO DRAWING NO. A-3.18 FOR FLOOR PLAN  
 14. REFER TO DRAWING NO. A-3.19 FOR FLOOR PLAN  
 15. REFER TO DRAWING NO. A-3.20 FOR FLOOR PLAN  
 16. REFER TO DRAWING NO. A-3.21 FOR FLOOR PLAN  
 17. REFER TO DRAWING NO. A-3.22 FOR FLOOR PLAN  
 18. REFER TO DRAWING NO. A-3.23 FOR FLOOR PLAN  
 19. REFER TO DRAWING NO. A-3.24 FOR FLOOR PLAN  
 20. REFER TO DRAWING NO. A-3.25 FOR FLOOR PLAN  
 21. REFER TO DRAWING NO. A-3.26 FOR FLOOR PLAN  
 22. REFER TO DRAWING NO. A-3.27 FOR FLOOR PLAN  
 23. REFER TO DRAWING NO. A-3.28 FOR FLOOR PLAN  
 24. REFER TO DRAWING NO. A-3.29 FOR FLOOR PLAN  
 25. REFER TO DRAWING NO. A-3.30 FOR FLOOR PLAN  
 26. REFER TO DRAWING NO. A-3.31 FOR FLOOR PLAN  
 27. REFER TO DRAWING NO. A-3.32 FOR FLOOR PLAN  
 28. REFER TO DRAWING NO. A-3.33 FOR FLOOR PLAN  
 29. REFER TO DRAWING NO. A-3.34 FOR FLOOR PLAN  
 30. REFER TO DRAWING NO. A-3.35 FOR FLOOR PLAN  
 31. REFER TO DRAWING NO. A-3.36 FOR FLOOR PLAN  
 32. REFER TO DRAWING NO. A-3.37 FOR FLOOR PLAN  
 33. REFER TO DRAWING NO. A-3.38 FOR FLOOR PLAN  
 34. REFER TO DRAWING NO. A-3.39 FOR FLOOR PLAN  
 35. REFER TO DRAWING NO. A-3.40 FOR FLOOR PLAN  
 36. REFER TO DRAWING NO. A-3.41 FOR FLOOR PLAN  
 37. REFER TO DRAWING NO. A-3.42 FOR FLOOR PLAN  
 38. REFER TO DRAWING NO. A-3.43 FOR FLOOR PLAN  
 39. REFER TO DRAWING NO. A-3.44 FOR FLOOR PLAN  
 40. REFER TO DRAWING NO. A-3.45 FOR FLOOR PLAN  
 41. REFER TO DRAWING NO. A-3.46 FOR FLOOR PLAN  
 42. REFER TO DRAWING NO. A-3.47 FOR FLOOR PLAN  
 43. REFER TO DRAWING NO. A-3.48 FOR FLOOR PLAN  
 44. REFER TO DRAWING NO. A-3.49 FOR FLOOR PLAN  
 45. REFER TO DRAWING NO. A-3.50 FOR FLOOR PLAN  
 46. REFER TO DRAWING NO. A-3.51 FOR FLOOR PLAN  
 47. REFER TO DRAWING NO. A-3.52 FOR FLOOR PLAN  
 48. REFER TO DRAWING NO. A-3.53 FOR FLOOR PLAN  
 49. REFER TO DRAWING NO. A-3.54 FOR FLOOR PLAN  
 50. REFER TO DRAWING NO. A-3.55 FOR FLOOR PLAN  
 51. REFER TO DRAWING NO. A-3.56 FOR FLOOR PLAN  
 52. REFER TO DRAWING NO. A-3.57 FOR FLOOR PLAN  
 53. REFER TO DRAWING NO. A-3.58 FOR FLOOR PLAN  
 54. REFER TO DRAWING NO. A-3.59 FOR FLOOR PLAN  
 55. REFER TO DRAWING NO. A-3.60 FOR FLOOR PLAN  
 56. REFER TO DRAWING NO. A-3.61 FOR FLOOR PLAN  
 57. REFER TO DRAWING NO. A-3.62 FOR FLOOR PLAN  
 58. REFER TO DRAWING NO. A-3.63 FOR FLOOR PLAN  
 59. REFER TO DRAWING NO. A-3.64 FOR FLOOR PLAN  
 60. REFER TO DRAWING NO. A-3.65 FOR FLOOR PLAN  
 61. REFER TO DRAWING NO. A-3.66 FOR FLOOR PLAN  
 62. REFER TO DRAWING NO. A-3.67 FOR FLOOR PLAN  
 63. REFER TO DRAWING NO. A-3.68 FOR FLOOR PLAN  
 64. REFER TO DRAWING NO. A-3.69 FOR FLOOR PLAN  
 65. REFER TO DRAWING NO. A-3.70 FOR FLOOR PLAN  
 66. REFER TO DRAWING NO. A-3.71 FOR FLOOR PLAN  
 67. REFER TO DRAWING NO. A-3.72 FOR FLOOR PLAN  
 68. REFER TO DRAWING NO. A-3.73 FOR FLOOR PLAN  
 69. REFER TO DRAWING NO. A-3.74 FOR FLOOR PLAN  
 70. REFER TO DRAWING NO. A-3.75 FOR FLOOR PLAN  
 71. REFER TO DRAWING NO. A-3.76 FOR FLOOR PLAN  
 72. REFER TO DRAWING NO. A-3.77 FOR FLOOR PLAN  
 73. REFER TO DRAWING NO. A-3.78 FOR FLOOR PLAN  
 74. REFER TO DRAWING NO. A-3.79 FOR FLOOR PLAN  
 75. REFER TO DRAWING NO. A-3.80 FOR FLOOR PLAN  
 76. REFER TO DRAWING NO. A-3.81 FOR FLOOR PLAN  
 77. REFER TO DRAWING NO. A-3.82 FOR FLOOR PLAN  
 78. REFER TO DRAWING NO. A-3.83 FOR FLOOR PLAN  
 79. REFER TO DRAWING NO. A-3.84 FOR FLOOR PLAN  
 80. REFER TO DRAWING NO. A-3.85 FOR FLOOR PLAN  
 81. REFER TO DRAWING NO. A-3.86 FOR FLOOR PLAN  
 82. REFER TO DRAWING NO. A-3.87 FOR FLOOR PLAN  
 83. REFER TO DRAWING NO. A-3.88 FOR FLOOR PLAN  
 84. REFER TO DRAWING NO. A-3.89 FOR FLOOR PLAN  
 85. REFER TO DRAWING NO. A-3.90 FOR FLOOR PLAN  
 86. REFER TO DRAWING NO. A-3.91 FOR FLOOR PLAN  
 87. REFER TO DRAWING NO. A-3.92 FOR FLOOR PLAN  
 88. REFER TO DRAWING NO. A-3.93 FOR FLOOR PLAN  
 89. REFER TO DRAWING NO. A-3.94 FOR FLOOR PLAN  
 90. REFER TO DRAWING NO. A-3.95 FOR FLOOR PLAN  
 91. REFER TO DRAWING NO. A-3.96 FOR FLOOR PLAN  
 92. REFER TO DRAWING NO. A-3.97 FOR FLOOR PLAN  
 93. REFER TO DRAWING NO. A-3.98 FOR FLOOR PLAN  
 94. REFER TO DRAWING NO. A-3.99 FOR FLOOR PLAN  
 95. REFER TO DRAWING NO. A-3.100 FOR FLOOR PLAN


REVISIONS  
 NO. DATE  
 1. 15/10/15  
 2. 15/10/15  
 3. 15/10/15  
 4. 15/10/15  
 5. 15/10/15  
 6. 15/10/15  
 7. 15/10/15  
 8. 15/10/15  
 9. 15/10/15  
 10. 15/10/15  
 11. 15/10/15  
 12. 15/10/15  
 13. 15/10/15  
 14. 15/10/15  
 15. 15/10/15  
 16. 15/10/15  
 17. 15/10/15  
 18. 15/10/15  
 19. 15/10/15  
 20. 15/10/15  
 21. 15/10/15  
 22. 15/10/15  
 23. 15/10/15  
 24. 15/10/15  
 25. 15/10/15  
 26. 15/10/15  
 27. 15/10/15  
 28. 15/10/15  
 29. 15/10/15  
 30. 15/10/15  
 31. 15/10/15  
 32. 15/10/15  
 33. 15/10/15  
 34. 15/10/15  
 35. 15/10/15  
 36. 15/10/15  
 37. 15/10/15  
 38. 15/10/15  
 39. 15/10/15  
 40. 15/10/15  
 41. 15/10/15  
 42. 15/10/15  
 43. 15/10/15  
 44. 15/10/15  
 45. 15/10/15  
 46. 15/10/15  
 47. 15/10/15  
 48. 15/10/15  
 49. 15/10/15  
 50. 15/10/15  
 51. 15/10/15  
 52. 15/10/15  
 53. 15/10/15  
 54. 15/10/15  
 55. 15/10/15  
 56. 15/10/15  
 57. 15/10/15  
 58. 15/10/15  
 59. 15/10/15  
 60. 15/10/15  
 61. 15/10/15  
 62. 15/10/15  
 63. 15/10/15  
 64. 15/10/15  
 65. 15/10/15  
 66. 15/10/15  
 67. 15/10/15  
 68. 15/10/15  
 69. 15/10/15  
 70. 15/10/15  
 71. 15/10/15  
 72. 15/10/15  
 73. 15/10/15  
 74. 15/10/15  
 75. 15/10/15  
 76. 15/10/15  
 77. 15/10/15  
 78. 15/10/15  
 79. 15/10/15  
 80. 15/10/15  
 81. 15/10/15  
 82. 15/10/15  
 83. 15/10/15  
 84. 15/10/15  
 85. 15/10/15  
 86. 15/10/15  
 87. 15/10/15  
 88. 15/10/15  
 89. 15/10/15  
 90. 15/10/15  
 91. 15/10/15  
 92. 15/10/15  
 93. 15/10/15  
 94. 15/10/15  
 95. 15/10/15  
 96. 15/10/15  
 97. 15/10/15  
 98. 15/10/15  
 99. 15/10/15  
 100. 15/10/15

FORTUNE Centre Anderson Rd  
 8051 Anderson Road  
 Richmond, BC  
 RZ 14-07848 / JP 15-70892  
 MIXED USE DEVELOPMENT

L6 FLOOR PLAN  
 OFFICE L5

DATE: 15/10/15  
 BY: [Signature]  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 APPR NUMBER: 1441

A-3.06



ANDERSON ROAD  
 ATTACHMENT 5




DESIGNED BY: GBL  
 DRAWN BY: [Name]  
 CHECKED BY: [Name]  
 DATE: [Date]

NOTES:  
 1. SEE [Reference]  
 2. SEE [Reference]

REVISIONS:  
 NO. DATE  
 1. [Date]  
 2. [Date]

**PORTLINE Centre Anderson Road**  
 8051 Anderson Road  
 Richmond, BC  
 20-0-0-0000 / 0-0-0-0000  
 MIXED USE DEVELOPMENT

**L9 FLOOR PLAN**  
 DATE: [Date]  
 DRAWN BY: [Name]  
 CHECKED BY: [Name]  
 SCALE: 1/4" = 1'-0"  
 APP NUMBER: 1441



ATTACHMENT 5

ANDERSON ROAD

No 3 ROAD

DESIGNED BY: GBL ARCHITECTS  
 DRAWN BY: GBL ARCHITECTS  
 CHECKED BY: GBL ARCHITECTS  
 DATE: 15-08-2018  
 PROJECT: FORTUNE CENTRE ANDERSON ROAD  
 SHEET: A-3.10

REVISIONS  
 NO. DATE DESCRIPTION  
 1 15-08-2018 ISSUE FOR PERMITTING  
 2 15-08-2018 ISSUE FOR PERMITTING  
 3 15-08-2018 ISSUE FOR PERMITTING  
 4 15-08-2018 ISSUE FOR PERMITTING  
 5 15-08-2018 ISSUE FOR PERMITTING

SCALE: 1/8" = 1'-0"  
 SHEET NUMBER: 1441

DATE: 15-08-2018  
 DRAWN BY: GBL ARCHITECTS  
 CHECKED BY: GBL ARCHITECTS  
 SHEET NUMBER: 1441

PROJECT: FORTUNE CENTRE ANDERSON ROAD  
 SHEET: A-3.10

DATE: 15-08-2018  
 DRAWN BY: GBL ARCHITECTS  
 CHECKED BY: GBL ARCHITECTS  
 SHEET NUMBER: 1441

PROJECT: FORTUNE CENTRE ANDERSON ROAD  
 SHEET: A-3.10

DATE: 15-08-2018  
 DRAWN BY: GBL ARCHITECTS  
 CHECKED BY: GBL ARCHITECTS  
 SHEET NUMBER: 1441

PROJECT: FORTUNE CENTRE ANDERSON ROAD  
 SHEET: A-3.10

DATE: 15-08-2018  
 DRAWN BY: GBL ARCHITECTS  
 CHECKED BY: GBL ARCHITECTS  
 SHEET NUMBER: 1441

PROJECT: FORTUNE CENTRE ANDERSON ROAD  
 SHEET: A-3.10

DATE: 15-08-2018  
 DRAWN BY: GBL ARCHITECTS  
 CHECKED BY: GBL ARCHITECTS  
 SHEET NUMBER: 1441

PROJECT: FORTUNE CENTRE ANDERSON ROAD  
 SHEET: A-3.10

DATE: 15-08-2018  
 DRAWN BY: GBL ARCHITECTS  
 CHECKED BY: GBL ARCHITECTS  
 SHEET NUMBER: 1441

PROJECT: FORTUNE CENTRE ANDERSON ROAD  
 SHEET: A-3.10

DATE: 15-08-2018  
 DRAWN BY: GBL ARCHITECTS  
 CHECKED BY: GBL ARCHITECTS  
 SHEET NUMBER: 1441

PROJECT: FORTUNE CENTRE ANDERSON ROAD  
 SHEET: A-3.10

DATE: 15-08-2018  
 DRAWN BY: GBL ARCHITECTS  
 CHECKED BY: GBL ARCHITECTS  
 SHEET NUMBER: 1441

PROJECT: FORTUNE CENTRE ANDERSON ROAD  
 SHEET: A-3.10

DATE: 15-08-2018  
 DRAWN BY: GBL ARCHITECTS  
 CHECKED BY: GBL ARCHITECTS  
 SHEET NUMBER: 1441

PROJECT: FORTUNE CENTRE ANDERSON ROAD  
 SHEET: A-3.10

DATE: 15-08-2018  
 DRAWN BY: GBL ARCHITECTS  
 CHECKED BY: GBL ARCHITECTS  
 SHEET NUMBER: 1441


PROJECT: FORTUNE CENTRE ANDERSON ROAD  
 SHEET: A-3.10

DATE: 15-08-2018  
 DRAWN BY: GBL ARCHITECTS  
 CHECKED BY: GBL ARCHITECTS  
 SHEET NUMBER: 1441

PROJECT: FORTUNE CENTRE ANDERSON ROAD  
 SHEET: A-3.10

DATE: 15-08-2018  
 DRAWN BY: GBL ARCHITECTS  
 CHECKED BY: GBL ARCHITECTS  
 SHEET NUMBER: 1441

PROJECT: FORTUNE CENTRE ANDERSON ROAD  
 SHEET: A-3.10



ATTACHMENT 5

500 LAKE STREET  
 RICHMOND, BC V6V 1A6  
 TEL: 604-273-8888  
 FAX: 604-273-8889  
 WWW.GBLARCHITECTS.COM  
 GBLARCHITECTS@GMAIL.COM

PROJECT NO. 14441  
 DATE: 15-07-2009  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

NOTES:  
 1. SEE GENERAL NOTES ON DRAWING  
 2. ALL DIMENSIONS UNLESS OTHERWISE NOTED

REVISIONS:  
 NO. DATE DESCRIPTION  
 1 15-07-09 1. ISSUE FOR PERMIT  
 2 15-07-09 2. REVISED PERMIT REQUIREMENTS  
 3 15-07-09 3. REVISED PERMIT REQUIREMENTS  
 4 15-07-09 4. REVISED PERMIT REQUIREMENTS  
 5 15-07-09 5. REVISED PERMIT REQUIREMENTS  
 6 15-07-09 6. REVISED PERMIT REQUIREMENTS  
 7 15-07-09 7. REVISED PERMIT REQUIREMENTS  
 8 15-07-09 8. REVISED PERMIT REQUIREMENTS  
 9 15-07-09 9. REVISED PERMIT REQUIREMENTS  
 10 15-07-09 10. REVISED PERMIT REQUIREMENTS

FORTUNE Centre Anderson Roa  
 80ST Anderson Road  
 Richmond, BC  
 RZ 14-678/08 / DP 15-708892  
 MIXED USE DEVELOPMENT  
 OFFICE LEVEL-9

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441


DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441

DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441


DATE: 15-07-09  
 CHECKED BY: [Signature]  
 SCALE: 1/4" = 1'-0"  
 JOB NUMBER: 14441











# igs

1000 PINEBLAKE DRIVE  
RICHMOND, BC V6X 4E1  
TEL: 604.270.1334 FAX: 604.270.1078  
GMAIL: IGS@IGSBUSINESS.COM  
WWW.IGSBUSINESS.COM

**REVISIONS**

NO.	DATE	DESCRIPTION
1	10/15/13	FINAL PLAN
2	10/15/13	REVISIONS FOR PERMITS


**PROJECT**  
**FOOTLINE Centre Anderson Road**  
 8051 Anderson Road  
 Richmond, BC  
 RZ 14-678448 / DP 15-701892  
 MIXED USE DEVELOPMENT

**UPPER FLOOR**


DATE	BY	SCALE	JOB NUMBER
10/15/13	AM	1/8"=1'-0"	1441

**A-3.14**

ANDERSON ROAD  
ATTACHMENT 5



SECTION 1-1



SECTION 2-2



GUY HARRISON & ASSOCIATES  
 120 EAST BENTLEY AVENUE  
 VANICUO, BC V8N 2M5  
 TEL: 779.751.1511 FAX: 779.751.1779  
 EMAIL: INFO@GUYHARRISON.COM

DATE: 11/20/19

BY: JHR

SCALE: 1/8" = 1'-0"

JOB NUMBER: 1441

REVISIONS  
 NO. DATE REVISIONS  
 1 08/15/19 SUBMITTAL  
 2 09/11/19 REVISED PER  
 3 10/22/19 REVISED PER  
 4 11/15/19 REVISED PER  
 5 11/20/19 REVISED PER




**IFORTUNE Centre Anderson Rsa**  
 801 Anderson Road  
 Richmond, BC  
 R2 14-078448 / Dp 15-708692  
 MIXED USE DEVELOPMENT


SECTION 3-3

DATE: 11/20/19  
 BY: JHR  
 SCALE: 1/8" = 1'-0"  
 JOB NUMBER: 1441

**A-5.04**



**SECTION 3-3 w/ REFLECTED ELEVATION**



**SECTION 3-3**

**ATTACHMENT 5**





**Address:** 6840 and 6860 No. 3 Road and 8051 Anderson Road

**File No.:** RZ 14-678448

**Prior to final adoption of Richmond Zoning Bylaw 8500, Amendment Bylaw 9510, the owner is required to complete the following.**

*(Subdivision, Dedications, SRWs and Encroachments)*

1. Discharge\* of the following Statutory Rights of Way:

- a) with respect to 6840 No. 3 Road,
  - SRW – Township of Richmond – 287391C;
- b) with respect to 6860 No. 3 Road,
  - SRW – Township of Richmond – 285751C;
  - SRW – Township of Richmond – 285759C;
- c) with respect to 8051 Anderson Road,
  - SRW – Township of Richmond – 284721C;
  - SRW – Township of Richmond – 285746C; and
  - SRW – Township of Richmond – 285752C.

\* Existing SRWs may be amended where relevant to implementing new SRW requirements, with the agreement of the City Solicitor.

2. Submission of interim and ultimate road functional drawings, showing all dedicated land and statutory rights of way areas pertaining to the subject property and adjacent properties, to the satisfaction of the City.
3. Consolidation of all parcels and registration of a subdivision plan for the subject site that satisfies the following conditions, generally as shown in the sketch survey plan(s) (RTC Attachment 9):
  - a) dedication of approximately 5.8 m along the No. 3 Road frontage for street widening, subject to final dimensions established by the surveyor on the basis of functional plans completed to the satisfaction of the Director of Transportation; and
  - b) dedication of an area approximately 33.7 m x 3.0 m in the northeast corner of the site for lane purposes, subject to final dimensions established by the surveyor on the basis of functional plans completed to the satisfaction of the Director of Transportation.

*(Note: Refer to Servicing Agreement section for information regarding frontage improvements on fronting City and dedicated lands.)*

4. Granting of a volumetric public right of passage and utilities statutory right-of-way for an internal lane composed of a minimum of:
  - an approximately 10.3 m wide x 31.7 m long x 5.0 m high south portion (to accommodate vehicular traffic);
  - an approximately 9.0 m wide x 22.1 m long x 7.5 m high north portion (to accommodate vehicular traffic and overflow waste loading);

- a 3.0 m x 3.0 m corner cut on either side of the intersection of the SRW with the Anderson Road property line; and
- a 3.0 x 3.0 m corner cut on the east side of the intersection of the SRW with the east-west lane,

generally as shown in the related sketch survey plan (RTC Attachment 9) and subject to final dimensions established by the surveyor on the basis of functional plans completed to the satisfaction of the Director of Transportation, providing for:

- a) universal accessibility;
  - b) design and construction requirements, including decorative finishing and lighting for the ground, wall and ceiling surfaces in the south portion, as determined through the Development Permit and Servicing Agreement processes;
  - c) design and construction at owner's cost; and
  - d) maintenance and repair at owner's cost.
5. Granting of an approximately 90 m<sup>2</sup> public right of passage and utilities statutory right of way to accommodate car share stalls and drive aisle access, generally as shown in the related sketch survey plan (RTC Attachment 9) and subject to final dimensions established by the surveyor on the basis of functional plans completed to the satisfaction of the Director of Transportation, providing for:
- a) universal accessibility;
  - b) design and construction, including decorative finishing and lighting for the ground, wall and ceiling surfaces to match the decorative finishing in the volumetric SRW (south portion), as determined through the Development Permit and Servicing Agreement processes;
  - c) design and construction, at owner's cost; and
  - d) maintenance and repair, at owner's cost.
6. Granting of a volumetric public right of passage and utilities statutory right of way at the corner of No. 3 Road and Anderson Road to satisfy the 4.0 m x 4.0 m transportation corner cut requirement, generally as shown in the related sketch survey plan (RTC Attachment 9). The statutory right-of-way shall provide for:
- a) a clear height of 5.0 m;
  - b) universal accessibility;
  - c) decorative finishing consistent with the finishing on surrounding city and private land, as determined through the Development Permit and Servicing Agreement processes;
  - d) design and construction at owner's cost; and
  - e) maintenance and repair at owner's cost.
7. Granting of a public right of passage and utilities statutory rights of way in favour of the City on the properties at 6820 No. 3 Road, 8080 Park Road, and 8108 Park Road for the purposes of supplementing the existing secured portions of the east-west lane that runs to Buswell Street and composed of:
- for 6820 No. 3 Road, approximately 5.348 m x 5.00 m in the south east corner of the site;
  - for 8080 Park Road, approximately 5.348 m x 24.387 m along the south PL; and
  - for 8108 Park Road, approximately 5.348 m x 24.387 m along the south PL,

generally as shown in the sketch survey plan(s) (RTC Attachment 9), subject to final dimensions established by the surveyor on the basis of functional plans completed to the satisfaction of the Director of Transportation and to provide for:

- a) each SRW to be free and clear of obstructions except that, in the case of 8080 and 8108 Park Road, loading may occur in the north 3.0 m of the statutory right of way subject to the provisions of the Traffic Regulation By law;
- b) universal accessibility;
- c) interim improvements at the developer’s cost, as determined by the Servicing Agreement process; and
- d) maintenance and repair at owner’s cost.

*Note: Refer also to the District Energy Utility conditions regarding statutory rights of way related to district energy facilities.*

*Note: Refer also to Servicing Agreement conditions regarding statutory rights of way related to private utility connections.*

**(Covenants and Agreements)**

- 8. **(Flood Construction Level)** Registration of a flood covenant on title identifying the basic minimum flood construction level of 2.9 m GSC for Area A.
- 9. **(Aircraft Noise)** Registration of an aircraft noise restrictive covenant on title suitable for residential uses and a SRW in favour of the Airport Authority.
- 10. **(Mixed Use Noise)** Registration of a mixed use noise restrictive covenant on title that identifies the development as being of mixed use (residential and commercial).
- 11. **(Ambient Noise)** Registration of an ambient noise restrictive covenant on title noting that the development is located in a densifying urban area and may be subject to impacts that affect the use and enjoyment of the property including, but not limited to, ambient noise, ambient light, shading, light access, privacy, outlook, vibration, dust and odours from development or redevelopment of public and private land in the surrounding area.
- 12. **(Affordable Housing)** Registration of a Housing Agreement securing the owner's commitment to:
  - a) provide 5% of the residential floor area to affordable housing dwelling units, in perpetuity;
  - b) provide for affordable housing units, of numbers, types, sizes and associated rent and income levels in accordance with the table below:

Unit Type	Affordable Housing Strategy Requirements			Project Targets (2)	
	Minimum Unit Area	Maximum Monthly Unit Rent (1)	Total Maximum Household Income (1)	Unit Mix	# of Units
Bachelor	37 m <sup>2</sup> (400 ft <sup>2</sup> )	\$850	\$34,000 or less	0%	0
1-Bedroom	50 m <sup>2</sup> (535 ft <sup>2</sup> )	\$950	\$38,000 or less	40%	2
2- Bedroom	80 m <sup>2</sup> (860 ft <sup>2</sup> )	\$1,162	\$46,500 or less	60%	3
3-Bedroom	91 m <sup>2</sup> (980 ft <sup>2</sup> )	\$1,437	\$57,500 or less	0%	0
TOTAL		N/A	N/A	100%	5

(1) May be adjusted periodically, as provided for under adopted City policy.  
 (2) 100% of affordable housing units shall meet Richmond Basic Universal Housing (BUH) standards or better.

- c) provide for private outdoor amenity area for each unit consistent with the minimum requirements of the CCAP and OCP Development Permit Guidelines;
  - d) provide for full and unlimited access to, and use of, all on-site indoor and outdoor amenity spaces, at no additional charge;
  - e) provide 5 parking stalls for exclusive use of the occupiers of the Affordable Housing Units at no cost in perpetuity;
  - f) provide for full and unlimited access to, and use of, other building facilities including, but not limited to, casual, shared or assigned bicycle storage, visitor parking, electric vehicle charging and related facilities, at no additional charge;
  - g) provide for all affordable housing units and related uses (e.g. parking) and amenities (e.g. common outdoor amenity space) to be completed to a turnkey level of finish at the sole cost of the developer and to the satisfaction of Director of Development and Manager, Community Services;
  - a) incorporate and identify the affordable housing dwelling units and associated facilities in the Development Permit plans, subject to the advice (e.g. changes to unit circumstances and/or confirmation of unit locations) of the Housing Co-ordinator; and
  - b) incorporate and identify the affordable housing dwelling units and associated facilities in the Building Permit plans, subject to the advice (e.g. changes to unit circumstances and/or confirmation of unit locations) of the Housing Co-ordinator.
13. ***(Shared Commercial and Residential Visitor Parking)*** Registration of a restrictive covenant on title securing the owner's commitment to:
- a) provide a pool of forty-one (41) shared commercial/residential visitor parking stalls;
  - b) locate the shared stalls on the ground level of the parkade, on either side of the north-south lane, using all of the available commercial stalls, and locate any remainder on the next parkade level, subject to the approval of the Director of Transportation;
  - c) ensure the shared stalls will remain unassigned;
  - d) ensure the shared stalls will be fully accessible (e.g. entry gate open) during standard business operating hours;
  - e) ensure the visitor use of the shared stalls will be accessible (e.g. buzz entry) during non-standard business hours;
  - f) identify the shared commercial/visitor parking stalls in the Development Permit plans;
  - g) identify the shared commercial/visitor parking stalls in the Building Permit plans; and
  - h) prior to Building Permit issuance granting occupancy, provide wayfinding and stall identification signage for the shared commercial/residential visitor stalls, to the satisfaction of the Director of Transportation.
14. ***(Shared Commercial and Residential Truck Loading)*** Registration of a restrictive covenant on title securing the owner's commitment to:
- a) provide a pool of three (3) shared commercial/residential medium size truck loading spaces;
  - b) ensure the shared spaces will remain unassigned;
  - c) identify the shared commercial/visitor medium size truck loading spaces in the Development Permit plans;
  - d) identify the shared commercial/visitor medium size truck loading spaces in the Building Permit plans; and



- e) prior to Building Permit issuance granting occupancy, provide wayfinding and space identification signage for the shared commercial/residential large size truck loading space, to the satisfaction of the Director of Transportation.

*Note: Two adjoining medium size truck spaces are also intended to be used for provision of one of the required large size truck loading spaces.*

15. **(Electric Vehicle Provisions)** Registration of a restrictive covenant on title securing the owner's commitment to:
- a) provide a minimum of 20% of residential parking stalls with a 120 volt receptacle to accommodate electric vehicle charging equipment;
  - b) provide an additional minimum of 25% of residential parking stalls with pre-ducting to support future installation of electric vehicle charging equipment;
  - c) provide a minimum of one 120 volt receptacle is provided to accommodate electric charging equipment for every 10 Class 1 bike parking stalls;
  - d) identify the electric vehicle stalls in the Development Permit plans;
  - e) identify the electric vehicle stalls in the Building Permit plans; and
  - f) prior to Building Permit issuance granting occupancy, provide wayfinding and stall identification signage for the electric vehicle stalls, to the satisfaction of the Director of Transportation.
16. **(End of Trip Facilities)** Registration of a restrictive covenant on title securing the owner's commitment to:
- a) provide cycling end of trip facilities for the shared use of all commercial uses (e.g. retail and office) generally as follows:
    - i. one male facility and one female facility, each with a minimum of two showers; and
    - ii. located such that the facilities are easily accessible from bicycle parking areas and all intended users.
  - b) identify the cycling end of trip facilities in the Development Permit plans;
  - c) identify the cycling end of trip facilities in the Building Permit plans; and
  - d) prior to Building Permit issuance granting occupancy, provide wayfinding signage for the end of trip facilities, to the satisfaction of the Director of Transportation.
- (Note: Facilities shall be a handicapped-accessible suite of rooms containing a change room, toilet, wash basin, shower, lockers, and grooming station (i.e. mirror, counter, and electrical outlets) designed to accommodate use by two or more people at one time.)*
17. **(Car Share Provisions)** Registration of a restrictive covenant on title or alternative legal agreement(s), subject to the final approval of the Director of Transportation, securing the owner's commitment to:
- a) provide two car-share stalls with drive aisle access, secured with a SRW in favour of the City, on the ground level of the parkade adjacent to the north-south lane SRW;
  - b) provide the forgoing stalls with 24 hour a day public access;
  - c) provide each car-share stall with an EV quick-charge (240 volt) charging station for its convenient and exclusive use;
  - d) identify the location, size, access, EV and CPTED characteristics of the car share stalls on the Development Permit plans;
  - e) identify the location, size, access, EV and CPTED characteristics of the car share stalls on the Building Permit plans;

- f) prior to Building Permit issuance granting occupancy, provide wayfinding signage for the car share stalls, to the satisfaction of the Director of Transportation;
  - g) provide the car share stalls and associated access at no cost to the car share operator;
  - h) provide the car share stalls and associated access at no cost to individual users of the car share service, except as otherwise determined by the City;
  - i) provide two car share cars, of which at least one is an electric vehicle, at no cost to the car share operator;
  - j) submit a draft contract of the agreement between the Developer and the car share provider for City's review;
  - k) submit a Letter of Credit prior to Development Permit for the sum of \$45,000 to secure the developer's commitment to provide the car share cars;
  - l) should the car share cars not be provided at the time of Building Permit issuance granting occupancy, voluntarily contribute the \$45,000 secured by LOC towards alternate transportation demand management modes of transportation;
  - m) prior to Building Permit issuance granting occupancy, enter into a contract with a car share operator for a minimum of three years from the first date of building occupancy, a copy of which shall be provided to the City; and
  - n) in the event that the car-share facilities are not operated for car-share purposes as intended via the subject rezoning application (e.g., operator's contract is terminated or expires), control of the car-share facilities shall be transferred to the City, at no cost to the City, and the City at its sole discretion, without penalty or cost, shall determine how the facilities shall be used going forward.
18. (***Common Amenity Space***) Registration of a restrictive covenant on title or alternative legal agreement(s), to the satisfaction of the City, securing the owner's commitment to:
- a) provide for full and unlimited access to and use of all common residential indoor and outdoor recreational and/or social amenity spaces/facilities for all residents including, but not limited to, the podium level deck, the Level 7 urban agriculture deck and the roof level deck, except in the case that individual facilities are reserved for private use by residents on a managed, time-limited and specified purpose basis.
19. (***District Energy Utility***) Registration of a restrictive covenant and/or alternative legal agreement(s), to the satisfaction of the City, securing the owner's commitment to connect to District Energy Utility (DEU), which covenant and/or legal agreement(s) will include, at minimum, the following terms and conditions:
- a) no Building Permit will be issued for a building on the subject site unless the building is designed with the capability to connect to and be serviced by a DEU and the owner has provided an energy modelling report satisfactory to the Director of Engineering;
  - b) if a DEU is available for connection, no final building inspection permitting occupancy of a building will be granted until: the Owner has executed and delivered to the City a Section 219 Covenant for the installation, operation and maintenance of all necessary facilities for supplying the services to the Lands; the Owner has entered into a Service Provider Agreement as required by the City; and the Owner has granted or acquired the Statutory Right-of-Way(s) and/or easements necessary for supplying the DEU services to the Lands; and
  - c) if a DEU is not available for connection, then the following is required prior to the earlier of subdivision (stratification) or final building inspection permitting occupancy of a building:
    - i. the City receives a professional engineer's certificate stating that the building has the capability to connect to and be serviced by a DEU;

- ii. the owner enters into a covenant and/or other legal agreement to require that the building connect to a DEU when a DEU is in operation;
- iii. the owner grants or acquires the Statutory Right-of-Way(s) and/or easements necessary for supplying DEU services to the building; and
- iv. if required by the Director of Engineering, the owner provides to the City with security for costs associated with acquiring any further Statutory Right of Way(s) and/or easement(s) and preparing and registering legal agreements and other documents required to facilitate the building connecting to a DEU when it is in operation.

**(Contributions)**

- 20. **(Child Care)** City acceptance of an offer to voluntarily contribute at least \$515,105.15 (one percent of the residential floor area, excluding affordable housing floor area, calculated using the proposed floor area e.g.  $0.01 \times 7,361.8 \text{ m}^2 \times \$6,997/\text{m}^2$ ) towards the development and operation of child care (90% to Childcare Development Reserve Fund - Account # 7600-80-000-90157-0000 and 10% to Childcare Operating Contributions Account # 7600-80-000-90159-0000).
- 21. **(Community Facilities)** City acceptance of an offer to voluntarily contribute at least \$1,417,398.31 (five percent of the Village Centre Bonus floor area calculated using the proposed floor area e.g.  $0.05 \times .83 \times 4,881.26 \text{ m}^2 \times \$6,997/\text{m}^2$ ) towards the development of community facilities (City Centre Facility Development Fund - Account # 7600-80-000-90170-0000).
- 22. **(Community Planning)** City acceptance of an offer to voluntarily contribute at least \$50,304.72 (100% of the total floor area calculated using the proposed floor area e.g.  $18,700.64 \text{ m}^2 \times \$2.69/\text{m}^2$ ) towards City Centre community planning (CC-Community Planning and Engineering Account # 3132-10-520-00000-0000).
- 23. **(Public Art)** City acceptance of an offer to voluntarily contribute at least \$114,861.64 (100% commercial floor area @ \$4.63 per square meter and 100% residential floor area, excluding affordable housing floor area, @ \$8.72 per square meter calculated using the proposed floor area e.g.  $10,943.14 \text{ m}^2 \times \$4.63/\text{m}^2 + 7,361.8 \text{ m}^2 \times \$8.72/\text{m}^2$ ) towards public art (15% to Public Art Provision Account # 7500-10-000-90337-0000 and 85% to ma # 7600-80-000-90173-0000).
- 24. **(Transportation Demand Management)** City acceptance of an offer to voluntarily contribute \$50,000 to upgrading the traffic signal at Park Road/Buswell Street (General Account (Transportation) Account # 5132-10-550-55005-0000) for pedestrian environment enhancement in support of a reduction in parking.
- 25. **(Trees – City Property)** City acceptance of an offer to voluntarily contribute \$1300 (calculated as \$1300 per tree) to the City’s Tree Compensation Fund (Account # 2336-10-000-00000-0000) for the planting of replacement trees within the City.

Per Current Floor Area Estimates:

Total Floor Area m <sup>2</sup>	Commercial Floor Area m <sup>2</sup>	Residential Floor Area m <sup>2</sup>	Calculable Residential Floor Area m <sup>2</sup>	Affordable Housing Floor Area m <sup>2</sup>
18,700.64	10,943.14	7,757.50	7361.8	395.7

**(Miscellaneous Considerations)**

- 26. **(LEED)** Design and construction of the development to LEED Silver Equivalent based on advice provided by a LEED AP BD+C.

27. (**Accessibility**) Design and construction of the development to include accessible housing units consistent with the following table:

<i>Type</i>	<i>Affordable</i>	<i>Market</i>	<i>Intent</i>	<i>Standard</i>
<i>Aging in Place</i>	0	66	- support mobility and usability	Per OCP
<i>Adaptable + Basic Universal Housing</i>	4	4	- reno potential for wheelchair plus added floor area for manoeuvring	Per BCBC and RZB
<i>Barrier Free</i>	1	0	- move in with wheelchair	Per BCDH
<i>Total Units</i>	5	70		

28. (**Common Amenity Area**) Design and construction of the development to include common indoor and outdoor amenity area consistent with the common amenity area provisions of the OCP/CCAP.

**(Servicing Agreement)**

29. Submission and processing of a Servicing Agreement\* application, completed to a level deemed acceptable by the Director of Engineering, for the design and construction of works associated with the proposed rezoning, subject to the following conditions:

**(Water Works)**

- a) Using the OCP Model, there is 683.6 L/s of water available at a 20 psi residual at the No 3 Rd frontage and 145.3 L/s at the Anderson Rd frontage. Based on your proposed Development your site requires a minimum fire flow of 220 L/s.
- b) The Developer is required to:
  - i. Submit Fire Underwriter Survey (FUS) or International Organization for Standardization (ISO) fire flow calculations to confirm the development has adequate fire flow for onsite fire protection. Calculations must be signed and sealed by a Professional Engineer and be based on Building Permit Stage and Building designs.
  - ii. Upgrade the existing 150mm AC water main along Anderson Road frontage to a 200mm watermain and install additional hydrants as required to achieve minimum 75m spacing along Anderson Road frontage.
  - iii. Install a new water service connection. Water meter to be located on-site (e.g. in a mechanical room).
  - iv. Confirm the actual settlement of the water main located along the No 3 Road frontage via the settlement test points indicated in the Preload Induced Utility Settlement report prepared by Geopacific dated November 5th, 2015, and report the final results to the City. If unacceptable settlement has occurred, the replacement of the water main along the effected length shall be added into the Servicing Agreement scope of works at the Developer's cost.
- c) At Developers cost, the City is to:
  - i. Cut and cap the existing water service connection at the watermain along the No 3 Road frontage.
  - ii. Complete all tie-ins to existing water mains.

**(Storm Sewer Works)**

- d) The Developer is required to:

- i. Install a new storm sewer within the center of Anderson Road from the existing 600 mm storm sewer to No 3 Road complete with manholes as required. Sizing shall be via the servicing agreement design review.
  - ii. Remove the adjacent existing storm sewers along both sides of the Anderson Road frontage, and tie-in the upstream portions and all existing service connections and catch basins to the proposed storm sewer along the centreline of Anderson Road. Removal of the existing storm sewer on the south side of Anderson Road will require curb, gutter, and sidewalk restoration.
  - iii. Note that the existing lane drainage to the south of Anderson Road will require extension to tie in to the proposed storm sewer via a new manhole.
  - iv. Tie-in existing storm mains, service connections and catch basin leads to the new storm sewer as required.
  - v. Install a new storm service connection complete with an inspection chamber located on-site within a proposed 1.5 m-deep, 3.0 m-wide SRW along the Anderson Rd frontage. Exact dimensions to be determined during the servicing agreement design review.
  - vi. Cut and cap the existing service connections and remove existing inspection chambers along the No 3 Road and Anderson Road frontages.
  - vii. Upgrade and install lane drainage along the east-west lane from 8051 Anderson Road to the east property line of 8111 Anderson Road to City specifications, complete with catch basins and manholes. The pipes shall be sized via a capacity analysis, minimum 200 mm diameter. The design of the lane drainage must be coordinated with the City-funded sanitary sewer to be placed within the east-west lane. Note: no service connections are permitted to connect to lane drainage.
  - viii. Remove the existing diagonally-aligned drainage line within the east-west lane along the frontage of 8111 Anderson Road.
  - ix. Confirm the actual settlement of the storm sewer located along the No 3 Road frontage via a CCTV inspection and submit to the City. If unacceptable settlement has occurred, the replacement of the storm sewer along the effected length shall be added into the Servicing Agreement scope of works at the Developer's cost.
- e) At Developers cost, the City is to:
- i. Complete all tie-ins of the proposed works to existing City infrastructure.

***(Sanitary Sewer Works)***

- f) The Developer is required to:
- i. As the site pre-load and other ground improvements, which will impact the existing sanitary main within the development site, has commenced prior to the City's construction of the sanitary main along Buswell Street, the developer was required to construct a temporary sanitary pump station and forcemain diversion. Following this, the Developer, at his sole costs, is required to:
  - ii. Design and construct a 200mm diameter sanitary main along Anderson Road by the completion date set out within the related servicing SA 16-731504 and connect to the future City-funded Buswell Street sanitary sewer when it becomes available. Tie-in to the west shall be to the existing sanitary sewer within the north-south aligned lane south of Anderson Road.
  - iii. Prior to start of on-site excavation and foundation works, construct the 200 mm diameter sanitary sewer along Anderson Road, decommission and remove the on-site forcemain and temporary pump station, and connect to the City-funded Buswell Street sanitary sewer.

- iv. Coordinate the construction of the sanitary main along Anderson Road with the construction schedule of the City-funded sanitary main along Buswell Street. The Developer is required to connect to the new sanitary sewer within Buswell Street, as soon as it becomes available.
  - v. Maintain, monitor and repair, to the satisfaction of the City, the temporary sanitary pump station and the piping system, until such time that the new 200mm diameter sanitary main to be built by the developer along Anderson Road and the City funded sanitary main along Buswell Street are constructed and operational.
  - vi. Remove the temporary sanitary pump station and the piping system and restore to original condition or better the affected areas after the connection to the new sanitary sewer within Buswell Street.
  - vii. Perform all other tasks required by the related servicing agreement SA 16-731504.
- g) At Developers cost, the City is to:
- i. Complete all tie-ins of the proposed works to existing City infrastructure.

***(Frontage Improvements – Engineering)***

- h) The Developer is required to:
- i. Review street lighting levels and street light type along No. 3 Rd and Anderson Rd frontages and upgrade lighting as required to meet City standards.
  - ii. Provide street lighting along the proposed east-west lane along the north property line of 8051 Anderson Road.
  - iii. Design the ultimate road cross-section of Anderson Road to accommodate for future District Energy Utility corridor within the roadway.
  - iv. Coordinate with BC Hydro, Telus and other private communication service providers
    - To underground proposed Hydro service lines.
    - When relocating/modifying any of the existing power poles and/or guy wires within the property frontages.
    - To determine if above ground structures are required and coordinate their locations (e.g. Vista, PMT, LPT, Shaw cabinets, Telus Kiosks, etc.). All such structures are to be located within the subject site's property line.
  - v. Complete other frontage improvements as per Transportation's requirements.

***(General Items – Engineering)***

- i) The Developer is required to:
- i. Grant utilities statutory rights of way for required connections between City utilities and the development as determined within the Servicing Agreement process.
  - ii. Locate/relocate all above ground utility cabinets and kiosks required to service the proposed development within the developments site (see list below for examples). A functional plan showing conceptual locations for such infrastructure shall be included in the development process design review. Please coordinate with the respective private utility companies and the project's lighting and traffic signal consultants to confirm the requirements (e.g., statutory right-of-way dimensions) and the locations for the aboveground structures. If a private utility company does not require an aboveground structure, that company shall confirm this via a letter to be submitted to the City. The following are examples of statutory right-of-ways that shall be shown in the functional plan and registered prior to SA design approval:

- BC Hydro PMT – 4mW X 5m (deep)
- BC Hydro LPT – 3.5mW X 3.5m (deep)
- Street light kiosk – 1.5mW X 1.5m (deep)
- Traffic signal kiosk – 1mW X 1m (deep)
- Traffic signal UPS – 2mW X 1.5m (deep)
- Shaw cable kiosk – 1mW X 1m (deep) – show possible location in functional plan
- Telus FDH cabinet-1.1 m W X 1 m (deep – show possible location in functional plan

***(Frontage Improvements – Transportation)***

*(General Note: Servicing Agreement for design and construction to City Centre standards. All requirements subject to final functional design including, but not limited to, the items outlined in this section and any associated required technical changes.)*

- j) The Developer is required to:
- i. For No. 3 Rd.:
    - a. Maintain existing curb.
    - b. From existing curb line provide:
      - 0.15m curb;
      - 2.50m boulevard;
      - 2.00m bike lane;
      - 1.50m lighting/street furniture buffer strip; and
      - 3.00m sidewalk.
  - ii. For Anderson Rd.:
    - a. Maintain existing curb.
    - b. From the existing north curb line provide:
      - 0.15 curb;
      - 1.5m hardscaped treed boulevard; and
      - 2.0m scored concrete sidewalk.
  - iii. For the internal north-south lane SRW PROP:
    - a. From east side:
      - 1.50m sidewalk free and clear of all obstructions;
      - 7.50m min. pavement width; and
      - 0.60 m buffer.

*Note: Rollover curbs both sides consistent with CC lane design standard.*
  - iv. For the east-west lane upgrade - subject site portions:
 

*(Note: Works are required to make the E-W lane operational to the greatest extent possible for two way traffic to and from Buswell Rd, to the satisfaction of the City.)*

    - a. From the new subject site north PL *(after lane dedication)*:
      - per forgoing note;
      - 1.50 m concrete sidewalk including rollover curb; and
      - 1.50 m pavement width; and
      - grading, drainage, gutter, lighting and traffic marking, as determined through the Servicing Agreement process.
  - v. For the east-west lane upgrade – off-site portions:
 

*(Note: Works are required to make the E-W lane operational to the greatest extent possible for two way traffic to and from Buswell Rd, to the satisfaction of the City.)*

    - a. For 6820 No. 3 Road:

- per forgoing note; and
- grading, drainage, curb and gutter, paving, lighting and traffic marking, as determined through the Servicing Agreement process.
- b. For 8080 and 8108 Park Road:
  - per forgoing note; and
  - grading, drainage, curb and gutter, paving, lighting and traffic marking, as determined through the Servicing Agreement process.
- c. For 8120 Park Road:
  - per forgoing note; and
  - grading, drainage, curb and gutter, paving, lighting and traffic marking, as determined through the Servicing Agreement process.
- d. For 8111 Anderson Road:
  - per forgoing note;
  - 1.50 m concrete sidewalk including lighting and rollover curb along north PL; and
  - grading, drainage, curb and gutter, paving, lighting and traffic marking, as determined through the Servicing Agreement process.

***(TIA Improvements – Transportation)***

- k) The Developer is required to:
  - i. For the No. 3 Rd./Anderson Rd. intersection:
    - a. upgrade the crosswalks at the intersection with decorative stamped asphalt treatment and tactile warning pavers at the curb ramps to improve visibility of crosswalks.
  - ii. For the Anderson Rd./Buswell Rd intersection:
    - a. to install two special crosswalk signals (side-mounted) with APS and service panel; pedestrian detection and communications conduit, cable and junction boxes; and
    - b. add new curb ramps on east side per City Engineering Design Specification standards with tactile warning strips.
  - iii. For the Granville Ave./Buswell St. intersection:
    - a. upgrade intersection with illuminated street name signs.

***(Parks - City Trees)***

- l) The developer is required to provide for the retention of three existing trees on City property along No. 3 Road, unless otherwise determined by the SA process, in which case replacement terms shall be determined within the SA process. Retention shall be supported with:
  - i. installation of appropriate tree protection fencing around all trees to be retained on the No. 3 Road frontage, as well as trees located in adjacent frontages that may be affected by the construction of the proposed development and associated frontage improvements; and
  - ii. submission of a contract entered into by the applicant and a Certified Arborist for the supervision of all works conducted in close proximity to the aforesaid tree protection zones. The contract must include the scope of work to be undertaken, including the proposed number of monitoring inspections at specified stages of construction, any special measures required to ensure tree protection, and a provision for the arborist to submit a post-construction impact assessment to the City for review.



*(Servicing Agreement – Letter of Credit)*

- m) Provision of a Letter of Credit to secure the completion of the works in an amount determined by the Director of Development.

*(Servicing Agreement – LTO Registration)*

- n) Registration of the Servicing Agreement on title.

*(Development Permit)*

30. Submission and processing of a Development Permit\* application, completed to a level deemed acceptable by the Director of Development, demonstrating:
- a) design development of the rezoning concept to address:
    - i. Council directions arising out of Public Hearing;
    - ii. form and character objectives noted in the associated Report to Planning Committee;
    - iii. form and character objectives described in the OCP and CCAP Development Permit Guidelines;
    - iv. technical resolution, as necessary, of building services, private utilities, public utilities, parking and loading and waste management including provision of final utility, loading, waste management and signage and wayfinding plans; and
    - v. technical resolution, as necessary, of the landscape plans related to:
      - a. the protection, installation and/or maintenance (including automatic irrigation) of retained and/or new ecological network landscape;
      - b. the protection, installation and/or maintenance (including automatic irrigation) of retained and/or new trees; and
      - c. the installation and/or maintenance (including automatic irrigation) of additional landscape; and
  - b) the owner's commitment to design and construct the development in accordance with rezoning policy, the rezoning considerations and the draft site-specific zoning bylaw, by incorporating information into the Development Permit plans (inclusive of architectural, landscape and other plans, sections, elevations, details, specifications, checklists and supporting consultant work) including, but not limited to:
    - i. statutory rights of way, easements, encroachments, no build areas, agreements and other legal restrictions;
    - ii. flood construction level(s);
    - iii. use, density, height, siting, building form, landscaping, parking and loading and other zoning provisions;
    - iv. site access and vehicular crossings;
    - v. the required shared commercial/visitor parking stalls;
    - vi. the required EV-charging and EV-ready vehicle parking stalls;
    - vii. the required EV-charging and EV-ready bicycle parking stalls;
    - viii. the required car-share parking stalls;
    - ix. the required end of trip facilities, including their location, number, size, type and use;
    - x. the location of areas reserved for DEU connection facilities and a notation regarding the need for DEU pre-ducting;
    - xi. the required affordable housing units, including their size and location;
    - xii. the required aging in place, basic universal, accessible, adaptable and/or convertible dwelling units, including their associated design features;

- xiii. a site and building Accessibility checklist and identification of specific recommended measures on the plans, where relevant;
- xiv. a CPTED checklist and identification of specific recommended measures on the plans, where relevant;
- xv. a LEED Checklist with measures recommended by a LEED AP BD+C to achieve LEED Silver equivalent and identification of specific measures to be incorporated into the Building Permit plans;
- xvi. an acoustic and mechanical report with recommendations prepared by an appropriate registered professional regarding measures to be incorporated into the Building Permit drawings to achieve the exterior and interior noise levels and other noise mitigation standards articulated in the aircraft and mixed use noise covenants;
- xvii. the required common indoor, common outdoor and private outdoor amenity areas including their location, size, use and finishing;
- xviii. the location and specifications for ecological network landscaping; and
- xix. the dimensions of any tree protection fencing illustrated on the Tree Retention/Management Plan provided with the application.

***(Letter of Credit – Trees, Ecological Network and Landscape)***

- c) Submission of a letter of credit for landscaping based on 100% of the cost estimate provided by the Landscape Architect, including installation costs, plus a 10% contingency cost.

***(Building Permit)***

*Note: Prior to Building Permit issuance the approved Development Permit and associated conditions, as well as any additional items referenced in “Schedule B: Assurance of Professional Design and Commitment for Field Review”, shall be incorporated into the Building Permit plans (drawings and documents) prior to Building Permit issuance.*

*Note: Prior to Building Permit issuance the developer must submit a “Construction Parking and Traffic Management Plan” to the Transportation Department. The Management Plan shall include location for parking for services, deliveries, workers, loading, application for any lane closures, and proper construction traffic controls as per Traffic Control Manual for works on Roadways (by Ministry of Transportation) and MMCD Traffic Regulation Section 01570.*

*Note: Prior to Building Permit issuance the developer must obtain a Building Permit for any construction hoarding. If construction hoarding is required to temporarily occupy a public street, the air space above a public street, or any part thereof, additional City approvals and associated fees may be required as part of the Building Permit. For additional information, contact the Building Approvals Department at 604-276-4285.*

**General Notes:**

1. Some of the foregoing items (\*) may require a separate application.
2. Where the Director of Development deems it appropriate, legal agreements are to be drawn not only as personal covenants of the property owner but also as covenants pursuant to Section 219 of the Land Title Act.

All agreements to be registered in the Land Title Office shall have priority over all such liens, charges and encumbrances as is considered advisable by the Director of Development. All agreements to be

registered in the Land Title Office shall, unless the Director of Development determines otherwise, be fully registered in the Land Title Office prior to enactment of the appropriate bylaw.

The legal agreements shall provide security to the City including indemnities, warranties, equitable/rent charges, letters of credit and withholding Permits, as deemed necessary or advisable by the Director of Development. All agreements shall be in a form and content satisfactory to the Director of Development.

3. Enter into, if required, additional legal agreements, as determined via the subject development's Servicing Agreement(s) and/or Development Permit(s), and/or Building Permit(s) to the satisfaction of the Director of Engineering, including, but not limited to, site investigation, testing, monitoring, site preparation, de-watering, drilling, underpinning, anchoring, shoring, piling, pre-loading, ground densification or other activities that may result in settlement, displacement, subsidence, damage or nuisance to City and private utility infrastructure.
4. Applicants for all City Permits are required to comply at all times with the conditions of the Provincial Wildlife Act and Federal Migratory Birds Convention Act, which contain prohibitions on the removal or disturbance of both birds and their nests. Issuance of Municipal Permits does not give an individual authority to contravene these legislations. The City of Richmond recommends that where significant trees or vegetation exists on-site, the services of a Qualified Environmental

---

Signed

---

Date

## COPY ADP MINUTES

**3. RZ 14-678448/DP 15-708092 – PROPOSED REZONING OF 6840-6860 NO.3 ROAD AND 8051 ANDERSON ROAD TO PROVIDE FOR THE DEVELOPMENT OF A MIXED COMMERCIAL AND MULTI-FAMILY RESIDENTIAL USE DEVELOPMENT WITH A TOTAL FAR OF 3.84 AND A HEIGHT OF 47 M GSC.**

APPLICANT: Ifortune Homes

PROPERTY LOCATION: 8051 Anderson Road

**Applicant's Presentation**

Daniel Eisenberg and Amela Brudar, GBL Architects, and Landscape Architect Grant Brumpton, PWL Partnerships, presented the project on behalf of the applicant and answered queries from the Panel.

**Panel Discussion**

*Comments from the Panel were as follows:*

- the design of the proposed building is unique in Richmond but suitable for its location;
- the building design is new and interesting; however, the south-facing balconies of the residential midrise need further articulation to achieve its architectural objective;
- consider introducing architectural elements and/or lighting in the proposed north-south lane to make it more friendly;
- would like to see the application back to the Panel if substantial changes will be made to the proposed development;
- the west façade of the building almost opposite Richmond City Hall is interesting; appreciate the inversion of the “podium streetwall with tower” and the pedestrian use of the space under the cantilevered rectangular volumes;
- applicant should ensure that the proposed commercial balconies are kept tidy and free from unsightly objects (e.g. barbeque grills, potted plants, etc.) as they are an important piece on the south façade;
- consider continuing the concrete paving treatment on the covered southern portion of the north-south lane up to the exposed northern portion to improve the experience of pedestrians and motorists coming from the north of the subject site;
- consider eliminating the sidewalk on the proposed north-south lane to enable pedestrians and motorists to share the use of the lane;
- lanes should be well lit to ensure pedestrian safety;
- commend the applicant for a clear and thorough presentation on the architecture and landscaping of the proposed development;
- the planting palette is well considered; appreciate the animation and landscaping on the various levels of the building; appreciate the round garden plots and the tables in between;

- appreciate the applicant's intent to contrast the landscaping of the different building levels with the rectilinear architecture of the building; overall geometry works in the plan drawings but may not be experienced by the residents at the different floor levels; up close, curves may look fuzzy and accidental; some curves, lines and diagonal trellises create too much geometry; consider design development and refinement of geometry on the landscaped areas in the building;
- curved planting beds fronting Anderson Road is not consistent with the overall architecture of the building and landscaping on the ground level; consider a rectilinear form for the planting beds;
- would like to see the proposal back to the Panel if there will be changes to the proposed landscaping;
- appreciate the proposed building form and massing which is unique in Richmond; appreciate the landscaped rooftop of the office tower;
- overall landscaping is cohesive and works well in aerial view; however, the landscaped areas work independently at each level and will not be experienced as a whole by the residents;
- the common outdoor space at the end of the hallway on level 9 is excessive and may not be used by residents; consider utilizing a portion of the space to create an extended private balcony for the two adjacent residential units;
- consider a more extended overhang to provide 4-5 meters of covered space on the ground level of the office tower along No. 3 Road; will provide better weather protection to future occupants of the office tower; also consider more seating opportunities (e.g. partially covered and partially exposed bench areas) along No. 3 Road and Anderson Road and at the corners to provide meeting places for people; application of Canada Line setback guidelines in this location is not necessary as there is no intention to extend the Canada Line southward;
- attention given to the north-south lane is excessive; should be used only as a vehicle service lane and not for pedestrian circulation; pedestrians should utilize the public realm fronting the streets; an east-west lane is not supported, unless the lane is designed to incorporate commercial and active use at ground level (ex. Fan Tan Alley in Victoria), it will not be well-used by pedestrians; provided service access can be accommodated by the north-south lane, removal of the east-west lane is supported; consider covering the entire lane to screen the exposed parkade and introduce a green roof to provide more visual interest from above;
- applicant can look at appropriate precedents if it wants to animate the lane, e.g. Fan Tan Alley in Victoria, Maiden Lane in San Francisco, and other pedestrian lanes in Europe;
- will support the project if the applicant will incorporate the suggested design changes to the proposed north-south and east-west lanes;
- support the previous comment regarding the needed design changes for the proposed east-west lane especially with regard to eliminating the pedestrian sidewalk;

- the applicant needs to provide adequate setback along No. 3 Road for the possible extension of Canada Line in the future;
- appreciate the provision of affordable units and the incorporation of universal access features in residential units; also appreciate the provision of pocket doors in some residential units;
- project may not return to the Panel unless substantial changes are made to the Canada Line setback and the building overhang;
- the applicant is encouraged to identify public art opportunities for the proposed development;
- appreciate the elevation along No. 3 Road and the overhanging tower; agree with comments that it could be further extended;
- the proposed development is sited in a prominent location; design development is needed to emphasize the importance of the project;
- the proposed north-south lane is highlighted by the applicant; however, it lacks appropriate treatments and amenities which would enhance the pedestrian and motorist experience;
- review the relationship of the subject development with the adjacent development along Anderson Road; the stepping down of the residential mid-rise is a weak move; consider a stronger transition;
- consider a stronger interaction of the north side of the proposed development, e.g. more “eyes on the street”, with the east-west pedestrian mews; and
- would like to see the application again in the Panel.

**Panel Decision**

It was moved and seconded

*That DP 15-708092 return to the Panel with the applicant giving consideration to the comments of the Panel.*

**CARRIED**

1	PROPERTY	FOR REVIEW
2	PROPERTY	FOR REVIEW
3	PROPERTY	FOR REVIEW
4	PROPERTY	FOR REVIEW
5	PROPERTY	FOR REVIEW
6	PROPERTY	FOR REVIEW


ATTACHMENT 8

FORTUNE CENTRE  
 ANDERSON ROAD

LAYOUT, MATERIAL  
 AND GRADING  
 LEVEL 1 - INTERIM

PROJECT	DATE	SCALE
NO.	DATE	SCALE
DATE	SCALE	DATE
DATE	SCALE	DATE
DATE	SCALE	DATE

L1.01



**LIGHTING LEGEND**

KEY	DESCRIPTION
1	IN-GROUND LIGHTING

**SITE FURNISHING LEGEND**

KEY	DESCRIPTION
1	BENCH-TYPE 1
2	BENCH-TYPE 2
3	BENCH-TYPE 3
4	OUTDOOR FURNITURE
5	HARVEST TABLE AND CHAIR
6	CONCRETE PLANTER
7	URBAN AGRICULTURE PLANTER
8	PLANTED POT
9	OUTDOOR BENCH AND COUNTERTOP
10	PLAY EQUIPMENT-METAL TUBE
11	STORAGE AND CABINET
12	BIKE RACK
13	TRICE GRATE
14	PLAY EQUIPMENT-RECURRENT BALL
15	PLAY EQUIPMENT-BLOCK
16	SHANTY CHESS SET

**PAVING LEGEND**

KEY	DESCRIPTION
1	CP CONCRETE PAVING
2	STONE PAVING
3	COLOR CONCRETE PAVING-TYPE 1
4	COLOR CONCRETE PAVING-TYPE 2
5	UNIT PAVER-TYPE 1
6	UNIT PAVER-TYPE 2
7	HYDRO-PRESSED SLAB
8	ZECCINO
9	REFERENCE SURFACE
10	ARTIFICIAL TURF PUTTING GREEN
11	ASPHALT

**HARDSCAPE LEGEND**

KEY	DESCRIPTION
1	METAL BALE
2	FRINGE SCREEN
3	METAL TRELLIS

**DRAIN LEGEND**

KEY	DESCRIPTION
1	AREA DRAIN
2	SLAB DRAIN
3	PLANTED DRAIN
4	RESIDENTIAL BIKE PARKING IS STALLS
5	COMMERCIAL BIKE PARKING IS STALLS

**LAYOUT AND MATERIALS GENERAL NOTES**

- ON-SITE SCALE DRAWINGS, LAYOUTS AND DIMENSIONS, REFER TO LANDSCAPE PLANS. REPORT ANY DISCREPANCIES TO CONSULTANT FOR REVIEW AND RESPONSE.
- LAYOUT AND MATERIALS DRAWINGS ARE TO BE READ IN CONJUNCTION WITH LANDSCAPE PLANS AND MATERIALS DRAWINGS. REPORT ANY DISCREPANCIES TO CONSULTANT FOR REVIEW AND RESPONSE.
- LANDSCAPE DRAWINGS ARE TO BE READ IN CONJUNCTION WITH ARCHITECTURAL AND ENGINEERING DRAWINGS. REPORT ANY DISCREPANCIES TO CONSULTANT FOR REVIEW AND RESPONSE.
- VERIFY ALL DIMENSIONS WITH FIELD CONDITIONS. REPORT ANY DISCREPANCIES TO CONSULTANT FOR REVIEW AND RESPONSE.

REFER TO CIVIL DRAWING

REFER TO CIVIL DRAWING

REFER TO CIVIL DRAWING

REFER TO CIVIL DRAWING

REFER TO CIVIL DRAWING

REFER TO CIVIL DRAWING

REFER TO CIVIL DRAWING

REFER TO CIVIL DRAWING

REFER TO CIVIL DRAWING

REFER TO CIVIL DRAWING

REFER TO CIVIL DRAWING

REFER TO CIVIL DRAWING


REFER TO CIVIL DRAWING

REFER TO CIVIL DRAWING

REFER TO CIVIL DRAWING

PLAN EPPXXXXX

SUBDIVISION PLAN OF LOT "B" PLAN 8552 (RD58458E),  
 LOT 3 PLAN 8552 EXCEPT: PARCEL "A" (EXPLANATORY PLAN 12388) AND  
 LOT 169 PLAN 39107 ALL OF  
 BLOCK 4 NORTH RANGE 6 WEST NEW WESTMINSTER DISTRICT  
 PURSUANT TO SECTION 67 OF THE LAND TITLE ACT. BCCS 92G.015



INTEGRATED SURVEY AREA No. 18  
 (CITY OF RICHMOND) NAD83 (CSRS)

GRID BEARINGS ARE DERIVED FROM OBSERVATIONS BETWEEN GEODETIC CONTROL MONUMENTS 77H4623 and 91H9837 AND ARE REFERRED TO THE CENTRAL MERIDIAN OF UTM ZONE 10.

THIS PLAN SHOWS HORIZONTAL GROUND-LEVEL DISTANCES UNLESS OTHERWISE SPECIFIED. TO COMPUTE GRID DISTANCES, MULTIPLY GROUND-LEVEL DISTANCES BY THE AVERAGE CORRECTION FACTOR OF 0.9996040 WHICH HAS BEEN DERIVED FROM 77H4623 AND 91H9837.

THE UTM COORDINATES AND ESTIMATED HORIZONTAL POSITIONAL ACCURACY ACHIEVED ARE DERIVED FROM THE MASCOIT PUBLISHED COORDINATES AND STANDARD DEVIATIONS FOR GEODETIC CONTROL MONUMENTS 77H4623 AND 91H9837.

UTM ZONE TO COORDINATES: 77H4623  
 DATUM: NAD83(CSRS) 4.0 B.C. L.C.A.R.D.  
 UTM NORTHING: 5445786.070  
 UTM EASTING: 490043.484  
 POINT COMBINED FACTOR: 0.9996040  
 ESTIMATED HORIZONTAL POSITIONAL ACCURACY: 0.004

UTM ZONE TO COORDINATES: 91H9837  
 DATUM: NAD83(CSRS) 4.0 B.C. L.C.A.R.D.  
 UTM NORTHING: 5445786.070  
 UTM EASTING: 490043.484  
 POINT COMBINED FACTOR: 0.9996041  
 ESTIMATED HORIZONTAL POSITIONAL ACCURACY: 0.010

LEGEND


- FOUND PLACED
- DENOTES CONTROL MONUMENT
  - DENOTES LEAD PLUG
  - DENOTES IRON POST
  - DENOTES WITNESS
  - m<sup>2</sup> DENOTES SQUARE METRES
  - ha DENOTES HECTARES
  - NF DENOTES NOTHING FOUND
  - Fd. DENOTES FOUND, NO RECORDS

NOTE: THIS PLAN SHOWS ONE OR MORE POSTS WHICH ARE SET ALONG THE PRODUCTION OF THE PROPERTY BOUNDARY LINE UNLESS OTHERWISE NOTED.



THIS PLAN LIES WITHIN THE JURISDICTION OF THE APPROVING OFFICER FOR THE CITY OF RICHMOND

THIS FIELD SURVEY REPRESENTED BY THIS PLAN WAS COMPLETED ON 11/11/2016 BY SURVEYORS GRANT BUTLER, BELS (BS), ECP & GRANT



7 DEC 2016



THIS PLAN LIES WITHIN THE GREATER VANCOUVER REGIONAL DISTRICT



PLAN EPPXXXXX

EXPLANATORY PLAN OF VOLUMETRIC STATUTORY RIGHT OF WAY  
 OF PART OF LOT 1 BLOCK 4 NORTH RANGE 6 WEST  
 NEW WESTMINSTER DISTRICT PLAN EPP-----  
 PURSUANT TO SECTION (99)(1)(e) OF THE LAND TITLE ACT.

BCCS 92G.015 CITY OF RICHMOND

\*FOR PUBLIC PASSAGE PURPOSES\*




SCALE 1 : 500 DISTANCES ARE IN METRES  
 THE INTENDED PLOT SCALE OF THIS PLAN IS 500 mm  
 IN WIDTH BY 432 mm IN HEIGHT (C SIZE) WHEN  
 PLOTTED AT A SCALE OF 1:500.

INTEGRATED SURVEY AREA No. 18  
 (CITY OF RICHMOND) NADB3 (CSRS)


GRID BEARINGS ARE DERIVED FROM PLAN EPP-----

LEGEND

m<sup>2</sup> DENOTES SQUARE METRES  
 m<sup>3</sup> DENOTES CUBIC METRES




ISOMETRIC VIEW



SCALE 1 : 250 DISTANCES ARE IN METRES

TABLE OF COORDINATES

Pt.No.	Northing	Easting	Elevation
1	10000.000	10000.000	0.660
2	10002.966	10003.013	0.660
3	10053.672	10003.239	0.660
4	10063.575	10015.345	0.660
5	10060.367	10012.225	0.660
6	10002.901	10012.013	0.660
7	9999.876	10015.000	0.660
8	10000.000	10003.013	6.000
9	10002.966	10003.013	6.000
10	10031.612	10003.141	6.000
11	10031.612	10003.141	8.500
12	10053.672	10001.239	8.500
13	10053.575	10015.345	8.500
14	10050.367	10012.225	8.500
15	10031.540	10012.141	8.500
16	10031.540	10012.141	6.000
17	10002.901	10012.013	6.000
18	9999.876	10015.000	6.000




ANDERSON ROAD

BUSWELL STREET

PLAN VIEW

THIS PLAN LIES WITHIN THE GREATER VANCOUVER REGIONAL DISTRICT



7 DEC 2016



PROFESSIONAL LAND SURVEYORS  
 200-1378 Macdon Drive  
 Vancouver, BC V5L 3K7  
 Tel: 604-872-7211  
 www.butlersundwick.ca

Dwg: 4534-SRW 1


THIS PLAN IS BASED ON THE FOLLOWING LAND TITLE AND  
 SURVEY AUTHORITY OF BC RECORDS: PLAN EPP-----  
 GRANT BUTLER, BCLS ECP #----- DRAFT

PLAN EPPXXXXXX

EXPLANATORY PLAN OF STATUTORY RIGHT OF WAY OF  
 PART OF LOT 1 BLOCK 4 NORTH RANGE 6 WEST  
 NEW WESTMINSTER DISTRICT PLAN EPP \_\_\_\_\_  
 PURSUANT TO SECTION (99)(1)(e) OF THE LAND TITLE ACT.

BCGS 92G.015 CITY OF RICHMOND

"FOR PUBLIC PASSAGE PURPOSES"



SCALE 1 : 500


THE INTENDED PLOT SCALE OF THIS PLAN IS 432 mm  
 IN WIDTH BY 280 mm IN HEIGHT (B SIZE) WHEN  
 PLOTTED AT A SCALE OF 1:500.

INTEGRATED SURVEY AREA No. 18  
 (CITY OF RICHMOND) NADB3 (CSRS)

GRID BEARINGS ARE DERIVED FROM PLAN EPP \_\_\_\_\_

LEGEND

m<sup>2</sup> DENOTES SQUARE METRES



THIS PLAN IS BASED ON THE FOLLOWING LAND TITLE AND  
 SURVEY AUTHORITY OF BC RECORDS; PLAN EPP \_\_\_\_\_  
 GRANT BUTLER, BCLS ECP # \_\_\_\_\_ DRAFT

7 DEC 2016  
**BUTLER  
 SUNDEVICK**  
 PROFESSIONAL LAND SURVEYORS  
 201 - 1375 McLean Drive  
 Vancouver, BC V5L 3N7  
 Tel. 604-872-7211  
 www.butlersundevick.ca  
 File: 4554-SRW 3  
 Dwg: 4554-SRW 3


THIS PLAN LIES WITHIN THE GREATER VANCOUVER REGIONAL DISTRICT

PLAN EPPXXXXX

EXPLANATORY PLAN OF STATUTORY RIGHT OF WAY OF PARTS OF LOTS 12, 13 AND 14 BLOCK 4 NORTH RANGE 6 WEST NEW WESTMINSTER DISTRICT PLAN 7312 PURSUANT TO SECTION (99)(1)(e) OF THE LAND TITLE ACT.

BOGS 926.015 CITY OF RICHMOND

"FOR PUBLIC PASSAGE PURPOSES"



SCALE 1 : 500 DISTANCES ARE IN METRES THE INTENDED PLOT SCALE OF THIS PLAN IS 560 mm IN WIDTH BY 432 mm IN HEIGHT (C SIZE) WHEN PLOTTED AT A SCALE OF 1:500.

INTEGRATED SURVEY AREA No. 18 (CITY OF RICHMOND) NAD83 (CSRS)


GRID BEARINGS ARE DERIVED FROM PLAN EPP\_

LEGEND

m2 DENOTES SQUARE METRES



PARK ROAD AND ANDERSON ROAD



ANDERSON ROAD

ROAD

BUSWELL STREET

7 DEC 2016

BUTLER SUNDWICK PROFESSIONAL LAND SURVEYORS 201-3375-1444 201-3375-1445 Vancouver, BC V6L 3A7 Tel: 604-872-7211 www.butlerandsundwick.ca

THIS PLAN LIES WITHIN THE GREATER VANCOUVER REGIONAL DISTRICT

THIS PLAN IS BASED ON THE FOLLOWING LAND TITLE AND SURVEY AUTHORITY OF BC RECORDS: PLAN EPP\_ GRANIT BUTLER, BCLS ECP # DRAFT


PLAN EPPXXXXX

**DRAFT**

**EXPLANATORY PLAN OF VOLUMETRIC STATUTORY RIGHT OF WAY  
OF PART OF LOT 1 BLOCK 4 NORTH RANGE 6 WEST  
NEW WESTMINSTER DISTRICT PLAN EPP**  
PURSUANT TO SECTION (99)(1)(e) OF THE LAND TITLE ACT.

BCGS 92G.015 CITY OF RICHMOND

"FOR SHARED PARKING PURPOSES"



**SCALE 1 : 500** DISTANCES ARE IN METRES  
THE INTENDED PLOT SCALE OF THIS PLAN IS 560 mm  
IN WIDTH BY 432 mm IN HEIGHT (C SIZE) WHEN  
PLOTTED AT A SCALE OF 1:500.




**INTEGRATED SURVEY AREA No. 18  
(CITY OF RICHMOND) NAD83 (CSRS)**

GRID BEARINGS ARE DERIVED FROM PLAN EPP.

**LEGEND**

m<sup>2</sup> DENOTES SQUARE METRES

m<sup>3</sup> DENOTES CUBIC METERS




**ISOMETRIC VIEW**



**SCALE 1 : 250** DISTANCES ARE IN METRES

**TABLE OF COORDINATES**

Pt.No.	Northing	Easting	Elevation
20	10017.061	9995.326	0.800
21	10030.061	9995.384	0.800
22	10030.026	10003.134	0.800
23	10022.533	10003.100	0.800
24	10022.535	10001.150	0.800
25	10017.035	10001.126	0.800
26	10017.061	9995.326	3.350
27	10030.061	9995.384	3.350
28	10030.026	10003.134	3.350
29	10022.533	10003.100	3.350
30	10022.535	10001.150	3.350
31	10017.035	10001.126	3.350



**DRAFT**

THIS PLAN IS BASED ON THE FOLLOWING LAND TITLE AND SURVEY AUTHORITY OF BC RECORDS: PLAN EPP. ---  
GRANT BUTLER, BCLS ECP --- DRAFT

19 DEC 2016  
PROFESSIONAL LAND SURVEYORS  
**BUTLER  
SUNDBICK**  
201 - 1375 McLean Drive  
Vancouver, BC V5L 3N7  
Tel: 604-681-7771  
Fax: 455-4  
www.butlersunswick.ca  
Dwg: 4554-SRW 4

THIS PLAN LIES WITHIN THE GREATER VANCOUVER REGIONAL DISTRICT



**Richmond Zoning Bylaw 8500  
Amendment Bylaw 9510 (RZ 14-678448)  
6840 & 6860 No. 3 Road and 8051 Anderson Road**

The Council of the City of Richmond, in open meeting assembled, enacts as follows:

1. Richmond Zoning Bylaw 8500 is amended by inserting the following into Section 20 (Site Specific Mixed Use Zones), in numerical order:

**20.31 City Centre High Density Mixed Use with Office (ZMU31) – Brighthouse Village**

**20.31.1 Purpose**

The **zone** provides for a broad range of commercial, service, business, entertainment and residential uses typical of the **City Centre**. Additional **density** is provided to achieve **City** objectives related to the development of **affordable housing units, child care, community amenity space and commercial uses**, including a significant component of **office**.

**20.31.2 Permitted Uses**

- animal grooming
- broadcasting studio
- child care
- education
- education, commercial
- education, university
- entertainment, spectator
- government service
- health service, minor
- housing, apartment
- housing, town
- library and exhibit
- liquor primary establishment
- manufacturing, custom indoor
- microbrewery, winery and distillery
- neighbourhood public house
- office
- parking, non-accessory
- private club
- recreation, indoor
- religious assembly
- restaurant
- retail, convenience
- retail, general
- retail, second hand
- service, business support
- service, financial
- service, household repair
- service, personal
- studio
- vehicle rental, convenience
- veterinary service

### 20.31.3 Secondary Uses

- amenity space, community
- boarding and lodging
- community care facility minor
- home-based business

### 20.31.4 Permitted Density

1. For the purposes of this **zone**, the calculation of **floor area ratio** is based on a **site** area of 4,882 sq. m.
2. The maximum **floor area ratio** is:
  - a) for residential uses, 1.00; and
  - b) for non-residential uses, 1.40.

together with an additional 0.1 **floor area ratio** provided that the additional **floor area** is used entirely to accommodate indoor **amenity space**.

3. Notwithstanding Section 20.31.4.2(a), the reference to “1.00” is increased to a higher **floor area ratio** of “1.60” if, at the time **Council** adopts a zoning amendment bylaw to create the ZMU31 **zone** and include the **lot** in the **zone**, the **owner**:
  - a) has agreed to provide **affordable housing units** on site and the combined **habitable space** of the **affordable housing units** is not less than 5% of the total residential **floor area**;
  - b) has entered into a **housing agreement** with respect to the **affordable housing units** and registers the **housing agreement** against title to the **lot** and files a notice in the Land Title Office; and
  - c) pays a sum into the **child care reserve fund** based on 1% of the value of the total residential **floor area ratio** less the value of the **affordable housing unit floor area ratio**, calculated using the “equivalent to construction value” rate determined by **Council** during the rezoning process.
4. Notwithstanding Section 20.31.4.2(b), the reference to “1.40” is increased to a higher **floor area ratio** of “2.25” provided that:
  - a) the **owner** uses the additional 0.85 **floor area ratio** for **office uses** only; and
  - b) if, at the time **Council** adopts a zoning amendment bylaw to create the ZMU31 **zone** and include the **lot** in the **zone**, the **owner** pays a sum into the City Centre Facility Development Fund based on 5% of the 0.85 **floor area ratio** “Village Centre Bonus”, calculated using the “equivalent to construction value” rate determined by **Council** during the rezoning process.

### 20.31.5 Permitted Lot Coverage

1. The maximum **lot coverage** is 90% for **buildings**.

### 20.31.6 Yards & Setbacks

1. The minimum **front yard** is:
  - a) 3.80 m but the minimum **front yard** may be reduced to 0.80 m for a maximum of 80% of the width of the **front yard** in the case of portions of the **building** located 5.0 m or more above **grade**; and,
  - b) weather protection associated with ground level uses may project into the **front yard** a maximum of 1.8 m.
2. The minimum **exterior side yard** is:
  - a) 3.80 m but the minimum **exterior side yard** may be reduced to 1.50 m for a maximum of 25% of the width of the **exterior side yard** in the case of portions of the building located 5.0 m or more above grade; and,
  - b) weather protection associated with ground level uses may project into the **exterior side yard** a maximum of 1.8 m.
3. The minimum **interior side yard** is 0.0 m.
4. The minimum **rear yard** is 0.0 m.
5. In addition to any **front, exterior side, interior side** and **rear yard** requirements, a minimum **building setback** of 1.5 m is required in any area where a **building** door provides direct **access** to or from **City** land or a secured, publicly-accessible exterior space.

### 20.31.7 Permitted Heights

1. The maximum **building height** for **principal buildings** is 47.0 m geodetic.
2. The maximum **building height** for **accessory buildings** is 12.0 m.

### 20.31.8 Subdivision Provisions/Minimum Lot Size

1. The minimum **lot area** is 4780 sq. m.
2. The minimum **lot width** is 45.0 m.
3. The minimum **lot depth** is 40.0 m.

### 20.31.9 Landscaping & Screening

1. **Landscaping** and **screening** shall be provided according to the provisions of Section 6.0.

**20.31.10 On-Site Parking and Loading**

1. On-site **vehicle** and bicycle parking and loading shall be provided according to the standards set out in Section 7.0.

**20.31.11 Other Regulations**

1. **Telecommunication antenna** must be located a minimum 20.0 m above the ground (i.e., on a roof of a **building**).
  2. In addition to the regulations listed above, the General Development Regulations in Section 4.0 and the Specific Use Regulations in Section 5.0 apply.
2. The Zoning Map of the City of Richmond, which accompanies and forms part of Richmond Zoning Bylaw 8500, is amended by repealing the existing zoning designation of the following parcels and by designating them **CITY CENTRE HIGH DENSITY MIXED USE WITH OFFICE (ZMU31) – BRIGHOUSE VILLAGE**:

- P.I.D. 011-325-666  
LOT 3 EXCEPT: PARCEL "A" (EXPLANATORY PLAN 12388); SECTION 9 BLOCK  
4 NORTH RANGE 6 WEST NEW WESTMINSTER DISTRICT PLAN 8552
- P.I.D. 003-609-944  
LOT "B" (RD58458E) SECTION 9 BLOCK 4 NORTH RANGE 6 WEST  
NEW WESTMINSTER DISTRICT PLAN 8552
- P.I.D. 002-850-702  
LOT 169 SECTION 9 BLOCK 4 NORTH RANGE 6 WEST NEW WESTMINSTER  
DISTRICT PLAN 39107



3. This Bylaw may be cited as "Richmond Zoning Bylaw 8500, Amendment Bylaw 9510".

FIRST READING

JAN 23 2017

PUBLIC HEARING

SECOND READING

THIRD READING

OTHER CONDITIONS SATISFIED

ADOPTED

CITY OF RICHMOND
APPROVED by 
APPROVED by Director or Solicitor 

\_\_\_\_\_  
MAYOR

\_\_\_\_\_  
CORPORATE OFFICE