



**To:** Planning Committee

**Date:** July 18, 2006

**From:** Jean Lamontagne  
Director of Development

**File:** RZ 04-286813


Terry Crowe  
Manager, Policy Planning


**Re:** **Application by Oris Development (London Landing Corp.) for A Steveston Area Plan Amendment and Rezoning at 13251 Princess Street and 6211 Dyke Road**

**Staff Recommendation**


1. That Official Community Plan Amendment Bylaw No. 8107, which amends Official Community Plan Bylaw No. 7100, by substituting a revised Steveston Area Plan Sub-Area for the existing Steveston Area Plan Sub-Area Plan as Schedule A thereof to amend the London/Princess Land Use Map to designate 13251 Princess Street and 6211 Dyke Road from "Mixed-Use" to "Residential", be introduced and given first reading;
2. That Bylaw No. 8107, having been considered in conjunction with:
  - the City's Financial Plan and Capital Program;
  - the Greater Vancouver Regional District Solid Waste and Liquid Waste Management Plans;is hereby deemed to be consistent with said program and plans, in accordance with Section 882(3)(a) of the Local Government Act;
3. That Bylaw No. 8107, having been considered in accordance with the City Policy on Consultation during OCP Development, is hereby deemed not to require further consultation.
4. That Bylaw No. 8078 for the rezoning of 13251 Princess Street and 6211 Dyke Road from "Industrial District (I2)" to "Comprehensive Development District (CD/174)" for multi-family residential development, to facilitate the construction of a 16-unit over-parkade multi-family residential development, be referred to Public Hearing on September 6, 2006;

5. That Bylaw 8077, which was given first reading by Council on June 12, 2006, be abandoned.

  
Jean Lamontagne  
*Director of Development*  
CA blg  
Att 9

~~TOP~~   
Terry Crowe  
*Manager, Policy Planning*

FOR ORIGINATING DIVISION USE ONLY

ROUTED TO:	CONCURRENCE	CONCURRENCE OF GENERAL MANAGER
Law .....	Y <input checked="" type="checkbox"/> N <input type="checkbox"/>	

## Staff Report

### Origin

Oris Development (London Landing) Corp. has applied, for 13251 Princess Street and 6211 Dyke Road, to the City of Richmond:

1. to amend the Steveston Area Plan from "Mixed Use [industrial, commercial, residential] to Residential"; (**Attachment 1**) and
2. for permission to rezone, from "Light Industrial District" (I2) to a "Comprehensive Development District" (CD/174) [residential], (**Attachment 1 and Attachment 2**) to permit the development of a four-storey residential building containing approximately 16 dwelling units over a one-storey parkade (**Attachment 3**).

This application was originally reviewed by Planning Committee on June 6, 2006 and referred to Public Hearing on July 17, 2006. The original proposed Official Community Plan Bylaw No. 8077 included land use amendment of the London/Princess Land Use Map to designate 6240 London Road, approximately the east 40 m portion of 13191 Princess Street, 13251 Princess Street and 6211 Dyke Road from "Mixed-Use" to "Residential", be introduced and given first reading.

At the Public Hearing on July 17, 2006, Council:

- referred the application by Oris Development (London Landing Corp.) for Area Plan amendment and rezoning at 13251 and 6211 Road for review and submission to the July 18, 2006 meeting of the Planning Committee; and
- Council did not support the staff's recommendation to amend the OCP land use designation for the Steveston Sub-Area to designate 6240 London Road and the east 40 m portion of 13191 Princess from "Mixed-Use" to "Residential".

This report deals with the proposed Official Community Plan Amendment Bylaw No. 8107 and rezoning for 13251 Princess Street and 6211 Dyke Road only.

## AREA PLAN AMENDMENT and REZONING APPLICATION (RZ 04-286813)

### Findings of Fact

Item	Existing	Proposed
Owner	Oris Development (Nakade) Corp.	Oris Development (Nakade) Corp.
Applicant	Oris Development (London Landing) Corp.	Oris Development (London Landing) Corp.
Site Size	1,943 m <sup>2</sup> (20,915 ft <sup>2</sup> )	1,943 m <sup>2</sup> (20,915 ft <sup>2</sup> )
Land Uses	Light Industrial	Residential
OCP Designation	Schedule 2.4 Steveston Area Plan	Schedule 2.4 Steveston Area Plan
Area Plan Designation	Mixed-Use	Residential
Sub-Area Plan Designation	2.4	2.4
Zoning	Light Industrial (I2)	Comprehensive Development District (CD/174) [Residential]

### **Project Description**

The London/Princess Area is an area in transition. A Development Application Technical Data Sheet (**Attachment 4**) provides the details regarding the proposed multi-family development on 13251 Princess Street and 6211 Dyke Road.

### **Surrounding Development**

The adjacent land uses are:

- To the North: Existing industrial uses and London Road beyond. Recently a Development Permit (DP 04-279174) was approved for a mixed-used commercial/residential development at 6111 London Road zoned Comprehensive Development (CD/83);
- To the East: Princess Street and existing multiple family residential development in a “heritage residential area” zone Comprehensive Development (CD/112 and CD/115). 13333 Princess Street (Abercrombie House) located at the south end of Princess Street at Dyke Road is a restored single-family home of recognized heritage significance;
- To the South: Dyke Road and foreshore public open space along the dyke zoned School and Public Use District (SPU); and
- To the West: Existing light industrial developments zoned Light Industrial District (I2).

### **Related Policies & Studies**

#### Official Community Plan

- The Steveston Area Plan, London/Princess Sub-Area:
  - describes the London/Princess node as “a mix of land uses providing both residential and job/business opportunities” to encourage a community that provides opportunities to live, work and play,
  - allows for Mixed-Uses: commercial, light industrial, residential and office;
  - requires that residential uses cannot be on the ground floor;
  - requires that office uses cannot be on the ground floor;
  - for example, building could have commercial and /or industrial uses throughout, or on the ground floor with all residential and/or offices uses above the ground floor.

#### Council Policy 5043 – OCP Bylaw Preparation Consultation Policy

This Policy provides direction regarding the consultation requirements for an Official Community Plan (OCP) amendment. Consultation with external agencies, organizations and authorities was not deemed to be required. The statutory Public Hearing will provide area residents, businesses and property owners an opportunity to comment on the application.

The Richmond School Board – School District #38 has recently indicated to City staff that OCP amendments should be directed to the Board of Trustees for review when they would result in the introduction of 50 new students, with the assumption that 100 new units would result in 17 new students. Therefore, applications for less than 294 new units should not be forwarded to the Board for review. The School Board has therefore not been consulted regarding the subject application which is for less than 14 dwelling units.

### Environmental Review

A copy of the Site Profile completed by the applicant on December 1, 2004 indicating that there is no known environmental contamination on site has been forwarded to the Province for record purposes.

### **Staff Comments**

#### **Proposed Rezoning to Comprehensive Development District (CD/174)**

The Development Data Sheet (**Attachment 4**) is enclosed for Reference. Staff Technical Review comments for the proposed rezoning to Comprehensive Development District (CD/174) are attached (**Attachment 5**).

### **Analysis**

- General
  - This area has been in transition, generally away from light industrial uses to residential and commercial uses.
  - East of Princess Street, the London/Princess area has been redeveloped into "heritage" residential with single-family and townhouses.
  - West of Princess Street, Council has recently indicated that the Area Plan mixed use designation is to continue.
- Land Uses
  - Of the approximately 113,500 ft<sup>2</sup> existing light industrial/marine commercial uses in the London/Princess area, there has been a demonstrable shift from predominately light industrial uses to a variety of businesses that are more compatible with residential uses above the ground floor.
  - Current uses include light industrial, maritime support uses, arts and culture uses (artisan, musician and dance studios), and other commercial/retail uses which serve the daily needs of area residents.
  - At full built out under the current Area Plan London/Princess Land Use designation, there may be up to 23,000 ft<sup>2</sup> of light industrial/commercial floor area created on the ground floor of future developments.
- Challenges
  - In Mixed land use areas, land use incompatibility problems can arise particularly between residential and certain types of light industrial uses.
  - Here, the introduction of mixed-use development with residential uses above the first floor to densify and introduce residential use the neighbourhood have created certain challenges. For example:
    - the Building Code requirements for industrial uses are stringent and do not facilitate an easy co-existence between industrial and residential uses within the same building without some significant increase of the construction costs; and
    - some industrial related noise and smells may be considered to be nuisance uses by some residents.

- To avoid the higher property costs and interference with residential uses, some of the industrial uses have opted to relocate elsewhere in the City where the rents are more reasonable and where there are fewer residents who may complain regarding their industrial uses.

The proposed amendment to the London/Princess Land Use Map to designate 13251 Princess Street and 6211 Dyke Road from “Mixed-Use” to “Residential” is supportable because it

- provides a land use buffer which minimizes direct land use conflicts and provides a gradual transition, from the lower density pure residential neighbourhood (single-family to three-storey townhouses) east of Princess Street, to the mixed-use development permitted west of Princess Street.
- The proposed development at 13251 Princess Street and 6211 Dyke Road maintains the residential “heritage” character along Dyke Road, and
- There is no negative impact to the existing industrial development to the north of the site.

#### Urban Design and Site Planning

- Proposed Rezoning Site - The intent of the developer is to create a “*Heritage Precinct*” to provide a signature landmark development that complements the heritage development to the east.
- The proposed multi-family residential development mimics the form of three (3) large “heritage” homes that are connected with a central circulation and service core.
- This built form reduces the mass of the building and complements the Abercrombie House at 13333 Princess Street, east of this site.
- The Dyke Road facade has been designed to have frontage character of heritage homes with doors and porches from individual units on the first floor leading to grade. Further design development to enhance the frontage character will be required as part of the Development Permit submission.
- North of the Proposed Rezoning Site - There are existing industrial buildings to the north and the west of the site. It is anticipated that these sites will be redeveloped as per the “Mixed-Use” Area Plan designation to mixed-use and requiring parkade structures with a minimum habitable floor elevation at 2.6 m to address flood plain requirements similar to the proposed development.
- There is minimal setback proposed on the north side for the parkade. It is anticipated that if the property to the north is completely redeveloped, its parkade will be set close to the common property line to eliminate any exposed walls.
- A 3 m setback is proposed on the west side to allow for some perimeter planting to provide landscape buffering and to provide visual screening of the existing industrial buildings further west.
- A 6 m setback with minor permitted projections such as porches and balconies, is provided along Dyke Road and Princess Street into the setback to provide articulated facades to animate the street frontages.
- It is intended that future development north of the site along the west side of Princess Street will be no more than three (3) storeys [15-18 m. high max. with pitched roofs] to create a better interface with the single-family dwellings along the north side of Princess Street.

### Architectural Form and Character:

- The proposed height and massing of the residential blocks steps down from the highest building height 17.7 m (58 ft.) at the southeast corner to approximately 15.3 m (50 ft) to the north and to the west of the site.
- The building is approximately 58 ft. high with portions of the building stepping down to provide gradual transition of height along Princess Street. The proposed height steps down from four (4) storeys to three (3) storeys over parking on the west side of Princess Street and 2½ storeys over parking for the town houses on the east side of Princess Street.
- The fourth storey of the building is designed to be wholly within the sloping roof to minimize its impact on the Abercrombie House.
- Further design development is required as part of the Development Permit submission to visually “lighten” up the core (common lobby entrance) to deemphasize the visual prominence. Consideration to be given to re-working the circulation to the fourth floor unit to enable the stepping back the fourth storey circulation core from Princess Street.

### Parks, Open Space & Landscaping

- The Parks Department advises that Steveston now has enough parkland until at least 2021, with the inclusion of the proposed public park in London/Princess when viewed from a park standard perspective of 6.5 acres per 1,000 people. This includes large tracts of parkland such as Garry Point as well as neighbourhood parks.
- As well, at the neighbourhood level, the following standard for accessibility to park/open space is to be achieved:
  - “Park/open space is to be located within a 600 meter walking distance of residents.
- Adequate building setbacks have been provided along Princess Street and Dyke Road to accommodate landscaping to create a good street interface.
- The landscape concept plan indicates a landscaped common open space in the northwest quadrant of the site above the parkade roof. A detailed landscape plan will be required as part of the Development Permit for the design of the open space.

### Trees

- There are two (2) existing Spruce trees along the south property line on Dyke Road exceeding 10 cm diameter dbh identified on the subject site. An accompanying arborist report prepared by Ken Bell, Certified Arborist, dated May 16, 2006, indicated that the two (2) existing trees cannot be retained because of the proximity to the proposed parkade and the grade alterations required to facilitate compliance with flood plain elevation.
- The proposed replacement trees in the landscape concept plan exceed the replacement ratio of 2: 1. The preliminary landscape concept plan proposes four (4) replacement trees that are 7 cm - 10 cm calliper in size. A minimum of seven (7) additional trees will be incorporated into the detailed landscape plan as part of the Development Permit submission.
- Common landscaped outdoor space is provided on the parkade roof accessible from the first floor common lobby corridor. Details of the landscaping and outdoor amenities will be provided as part of the Development Permit submission.

### Amenity Space

The proposed development includes an indoor amenity space off the lobby on the second floor.

### Affordable Housing

The applicant is to contribute \$18,266 (based on \$.60/ft<sup>2</sup> for permissible floor area) towards affordable housing to be constructed within the Steveston Area (e.g. at the "Branscombe House" site at 4900 Steveston Highway). This is acceptable as the affordable housing was introduced late in City-developer discussions.

### Flood Proofing

Natural grades in the London/Princess Area vary, depending on whether a site was filled at the time of development. The required habitable floor elevation in the London/Princess Area for flood proofing is 2.6 m (8.5 ft.) geodetic. Therefore, any residential development will have to be raised to conform to this requirement. The proposed first floor elevation (habitable floor) is approximately 3.9 m which exceeds the minimum required flood plain elevation to accommodate a parkade structure.

### Utilities and Site Servicing

- Engineering Department concurred with the Engineering Consultant's Analysis, that no storm or sanitary upgrades are required. This site can be serviced with all the relevant utilities and there is adequate capacity.
- A Restrictive Covenant prohibiting vehicular access onto Dyke Road is required.

### Site Phasing

The site will be consolidated and developed in its entirety. No phasing is proposed.

### Rezoning Conditions

A list of rezoning conditions is included as **Attachment 6**.

The applicant has agreed to all conditions. A signed acceptance of the conditions is on file.


### **Financial Impact**

None.

### **Conclusion**

Staff propose:

- (1) That the proposed OCP amendment to designate 13251 Princess Street and 6211 Dyke Road from "Mixed-Use" to "Residential" be approved as it provides a better transition of land use from the residential neighbourhood east of Princess Street westward towards a mixed-use area; and
- (2) That the rezoning of 13251 Street and 6211 Dyke Road be approved.




Cecilia Achiam, MCIP, BCSLA,  
Senior Planner, Urban Design, (Local 4122)

CA:blg



**ATTACHMENTS**

- Attachment 1: Location Map Proposed Area Plan Amendment and and Rezoning
- Attachment 2: Aerial Map
- Attachment 3: Conceptual Development Plans (RZ 04-286813)
- Attachment 4: Development Data Sheet (RZ 04-286813)
- Attachment 5: Staff Technical Review Comments (RZ 04-286813)
- Attachment 6: Conditional Rezoning Requirements Concurrence



**SUBJECT SITE**

*South Arm Fraser River*




# OCP Amendment Area

Original Date: 05/23/06

Amended Date: 07/18/06

Note: Dimensions are in METRES

# City of Richmond



20.11

40.28

PRINCESS ST

13251

46.23

16.09

22.00  
13333  
11.00

54.92

25.57

19.61

DYKE RD

20.12  
6160

20.12  
6180

20.12  
140

PROPOSED AREA  
PLAN AMENDMENT

SPU

PRINCESS ST

LONDON RD

12

NO. 2 RD


PROPOSED  
REZONING

South Arm Fraser River

CD/115

CD/112

CD/122




## RZ 04-286813

Original Date: 05/23/06

Revision Date:

Note: Dimensions are in METRES



**SUBJECT  
PROPERTY**

*South Arm Fraser River*




RZ 04-286813

Date: 05/04/06

Amended Date:

Note: Dimensions are in METRES

NOTES



NO.	REVISION
1	ISSUED FOR PERMITTING
2	ISSUED FOR PERMITTING
3	ISSUED FOR PERMITTING
4	ISSUED FOR PERMITTING
5	ISSUED FOR PERMITTING
6	ISSUED FOR PERMITTING
7	ISSUED FOR PERMITTING
8	ISSUED FOR PERMITTING
9	ISSUED FOR PERMITTING
10	ISSUED FOR PERMITTING
11	ISSUED FOR PERMITTING
12	ISSUED FOR PERMITTING
13	ISSUED FOR PERMITTING
14	ISSUED FOR PERMITTING
15	ISSUED FOR PERMITTING
16	ISSUED FOR PERMITTING
17	ISSUED FOR PERMITTING
18	ISSUED FOR PERMITTING
19	ISSUED FOR PERMITTING
20	ISSUED FOR PERMITTING

**Palco Group**  
 1000 West 10th Street  
 Vancouver, BC V6H 1A5  
 Tel: (604) 681-1111  
 Fax: (604) 681-1112  
 Email: info@palco.com



6211 DYKE ROAD  
 MOULTON FAMILY DEVELOPMENT  
 RICHMOND, B.C.  
 Site Development  
 London (Landscape) Corp

NO.	REVISION
1	ISSUED FOR PERMITTING
2	ISSUED FOR PERMITTING
3	ISSUED FOR PERMITTING
4	ISSUED FOR PERMITTING
5	ISSUED FOR PERMITTING
6	ISSUED FOR PERMITTING
7	ISSUED FOR PERMITTING
8	ISSUED FOR PERMITTING
9	ISSUED FOR PERMITTING
10	ISSUED FOR PERMITTING
11	ISSUED FOR PERMITTING
12	ISSUED FOR PERMITTING
13	ISSUED FOR PERMITTING
14	ISSUED FOR PERMITTING
15	ISSUED FOR PERMITTING
16	ISSUED FOR PERMITTING
17	ISSUED FOR PERMITTING
18	ISSUED FOR PERMITTING
19	ISSUED FOR PERMITTING
20	ISSUED FOR PERMITTING

**SITE PLAN / GROUND FLOOR PLAN**  
 A-202  
 B

SITE PLAN / GROUND FLOOR PLAN  
 A-202  
 1/8" = 1'-0"





NOTES

Sheet No.	A.351
Rev.	B


**Patrick Gilling**  
 ARCHITECT  
 1000 WEST 10TH AVENUE  
 SUITE 100  
 DENVER, CO 80202  
 TEL: (303) 733-1111  
 FAX: (303) 733-1112  
 WWW: WWW.PATRICKGILLING.COM

**Dyke Road Development**  
 627 DYKE ROAD  
 RICHMOND, BC

Chris Debernardi  
 (Urban Landings) Corp.

DYKE ROAD  
 STREETSCAPE  
 (LOOKING NORTH)

NOTES






ITO  
 LANDSCAPE ARCHITECTS  
 6311 DYKE ROAD  
 RICHMOND, BC V6X 2E4  
 TEL: 604-273-2812  
 FAX: 604-273-1818  
 WWW.ITO.VAN.CA

6311 DYKE ROAD  
 RICHMOND

LANDSCAPE PLAN

NO.	DATE	DESCRIPTION
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		
22		
23		
24		
25		
26		
27		
28		
29		
30		
31		
32		
33		
34		
35		
36		
37		
38		
39		
40		
41		
42		
43		
44		
45		
46		
47		
48		
49		
50		
51		
52		
53		
54		
55		
56		
57		
58		
59		
60		
61		
62		
63		
64		
65		
66		
67		
68		
69		
70		
71		
72		
73		
74		
75		
76		
77		
78		
79		
80		
81		
82		
83		
84		
85		
86		
87		
88		
89		
90		
91		
92		
93		
94		
95		
96		
97		
98		
99		
100		

L1 of 1





**City of Richmond**

6911 No. 3 Road  
Richmond, BC V6Y 2C1

**Development  
Data Sheet**  
Development Applications Department

**RZ 04-286813**

**Attachment 4**

Address:	<b>13251 Princess Street and 6211 Dyke Road</b>	
Applicant:	Oris Development (London Landing) Corp.	Owner: Oris Development (London Landing) Corp.
Planning Area(s):	2.4 Steveston Area Plan	
Floor Area	Gross: 1,943 m <sup>2</sup>	Net: 1,943 m <sup>2</sup>

	Existing	Proposed
Site Area	1,943 m <sup>2</sup>	1,943 m <sup>2</sup>
Land Uses	Vacant	Residential
OCP Designation	Mixed-Use	Residential
Zoning:	I2	CD/174
Number of Units	0	16

	Bylaw Requirement	Proposed	Variance
Floor Area Ratio:	1.45	1.45	complies
Lot Coverage:	Max. 50%	46 %	complies
Setback – Dyke Road (S):	Min. 6 m	6 m	complies
Setback – Princess Street (E):	Min. 3 m	3 m	complies
Setback – Side Yard (W):	Min. 3 m	3 m	complies
Setback – Rear Yard (N):	Min. 3 m	3 m	complies
Height (m):	Max. 20 m	19.05 m	complies
Lot Size:	1,900 m <sup>2</sup>	1,943 m <sup>2</sup>	complies
Off-street Parking Spaces – Resident/Visitors:	24 and 4	32 and 4	complies
Off-street Parking Spaces – Accessible:	1	2	complies
Off-street Parking Spaces – Total:	28	36	complies
Tandem Parking Spaces:	permitted	none proposed	complies
Indoor Amenity Space:	Min. 70 m <sup>2</sup>	approx. 70 m <sup>2</sup>	complies
Outdoor Amenity Space:	Min. 96 m <sup>2</sup>	> 96 m <sup>2</sup>	complies

**SUMMARY OF STAFF COMMENTS****Engineering Comments:**

This site can be serviced with all the relevant utilities and there is adequate capacity. No access to Dyke Road, a covenant restricting access will be required.

March 28, 2006: Engineering concurred with HY Engineering's analysis from March 3, 2006- no storm or sanitary upgrades required, but calculations are to be shown on Servicing Agreement design.

**Transportation Comments**

May 1, 2006 Comments on latest revised plans-

1. Frontage improvements (including S/W and grass treed boulevard along the entire Princess Street frontage.
2. Conform to City's Parking Bylaw Requirements on the number and dimensions of parking spaces. Indicate dimensions (including lengths) of the parking spaces on the plan. Require 1 handicapped parking space for visitors for this 14-unit townhouse development. No overlapping of parking spaces (Stall #12 & 13 and #21 & 22 overlap on the plan). Also demonstrate how a car would manoeuvre in and out of the visitor parking stalls without backing onto public road (i.e., Princess Street), particularly as the proposed security gate limits the access to the drive aisle of the resident's parking area.
3. Driveway and internal drive aisle to be a minimum of 6 m wide, clear of any obstructions or overhangs.
4. Frontage improvements (including S/W and grass treed boulevard) along the entire Princess Street frontage.
5. Demonstrate how a loading truck (i.e., SU 9) would manoeuvre into and out of the proposed loading area without backing onto Princess Street.
6. Contact Parks Department for their requirements (e.g., greenlink requirements, continuation of the existing walkway south of the site).
7. Prior to issuance of the Building Permit, a construction parking and traffic management plan to be provided to the Transportation Department.

## Conditional Rezoning Requirements

6211 Dyke Road and 13251 Princess Street RZ 04-286813

Prior to final adoption of OCP Amendment Bylaw No. 8077, and Zoning Amendment Bylaws 8078, the developer is required to complete the following requirements:

Legal Requirement, specifically:

- A Restrictive Covenant prohibiting vehicular access onto Dyke Road

Voluntary Contribution, specifically:

- The applicant to contribute \$18,266 (based on \$.06/sq. ft. for permissible floor area) towards affordable housing to be constructed in the Steveston Area (E.g. at the “Branscombe House” site at 4900 Steveston Highway)

Development Permit Conditions, specifically:

- The submission and processing of a Development Permit\* completed to a level deemed acceptable by the Director of Development.

The following conditions are required to be met prior to forwarding the Development Permit application to the Development Permit Panel:

- Further design development to enhance the frontage character along Dyke Road (i.e. with porches, entry doors and stairs of individual units leading to grade).
- Further design development is required to visually “lighten” up the core (common lobby entrance) to deemphasize the visual prominence. Consideration to be given to reworking the circulation to the fourth floor unit to enable the stepping back the fourth storey circulation core from Princess Street.
- Submission of grading information, based on legal survey grades to illustrate compatibility with adjacent existing development and how flood proofing is addressed
- Submission of a detail landscape plan to illustrate the open space, children’s play area and planting and landscaping design.
- Design development to incorporate Crime Prevention Through Environmental Design (CPTED) measures particularly in the parkade and open space treatment.
- Design development to incorporate universal accessibility measures including wheelchair accessible units in the development.
- Compliance with Parking Bylaw standards

The following conditions are required to be met prior to forwarding this application to Council for approval of the Development Permit:

- Submission of Letter of Credit landscaping will be required.

The following conditions are required to be met prior to the issuance of a Building Permit:

- The developer shall enter into the City’s standard Servicing Agreement document for design and construction including but not limited to the works, as described below:

- (i) Frontage improvements (including S/W and grass treed Blvd) along the entire Princess St frontage
- (ii) Continuation of the existing walkway along the south of the site fronting Dyke Road. Design to be to the satisfaction of Parks and Recreation Department.
- A construction parking and traffic management plan to be provided to the Transportation Department to include: location for parking for services, deliveries and workers and loading, application for request for any lane closures (including dates, times, and duration), and proper construction traffic controls as per Traffic Control Manual for Works on Roadways (by Ministry of Transportation) and MMCD Traffic Regulation Section 01570.

(Signed copy on file)

Signed \_\_\_\_\_

\_\_\_\_\_ Date

\* A separate application is required



**Richmond Official Community Plan Bylaw 7100  
Amendment Bylaw 8107 (RZ 04-286813)  
13251 Princess Street and 6211 Dyke Road**

The Council of the City of Richmond, in open meeting assembled, enacts as follows:

1. The Land Use Map of Schedule 2.4 (Steveston Area Plan) of Richmond Official Community Plan Bylaw 7100 is amended by repealing the existing land use designation from "Mixed Use" and re-designate it to "Residential", as shown on the cross-hatched on Schedule A, which is attached to and forms part of this Bylaw.
  
2. This Bylaw may be cited as "**Richmond Official Community Plan Bylaw 7100, Amendment Bylaw 8107**".

FIRST READING

PUBLIC HEARING

SECOND READING

THIRD READING

ADOPTED

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_



\_\_\_\_\_

\_\_\_\_\_

CITY OF RICHMOND
APPROVED by <i>[Signature]</i>
APPROVED by Manager or Solicitor <i>[Signature]</i>

\_\_\_\_\_  
MAYOR

\_\_\_\_\_  
CORPORATE OFFICER



# OCP Amendment Area

Original Date: 05/23/06

Amended Date: 07/18/06

Note: Dimensions are in METRES



**Richmond Zoning and Development Bylaw 5300  
Amendment Bylaw 8078 (RZ 04-286813)  
13251 Princess Street and 6211 Dyke Road**

The Council of the City of Richmond, in open meeting assembled, enacts as follows:

**“ 291.174 COMPREHENSIVE DEVELOPMENT DISTRICT (CD/174)**

The intent of this zoning district is to accommodate **multiple-family dwellings**.

**291.174.1 PERMITTED USES**

**RESIDENTIAL**, limited to **Multiple-Family Dwellings**;  
**BOARDING & LODGING**, limited to two persons per **dwelling unit**;  
**HOME OCCUPATION**;  
**COMMUNITY USE**;  
**ACCESSORY USES, BUILDINGS & STRUCTURES**;  
**RESIDENTIAL PARKING, ACCESS AND STORAGE** within a parking garage.

**291.174.2 PERMITTED DENSITY**

.01 Maximum **Floor Area Ratio**: 1.45

(a) an additional 0.1 **floor area ratio** provided that it is entirely **used** to accommodate common indoor **amenity space**.

.02 For the purpose of this subsection, **Floor Area Ratio** shall be deemed to exclude the following:

(a) portions of a **building** that are **used** for off-street parking and bicycle storage purposes located in the parkade;

(b) unenclosed balconies;

(c) elevator shafts and common stairwells; and

(d) common mechanical and electrical storage rooms, **PROVIDED THAT** the total floor area of these facilities does not exceed 30 m<sup>2</sup> (323 ft<sup>2</sup>).

**291.174.3 MINIMUM LOT SIZE**

.01 A **building** shall not be constructed on a **lot** which is less than 1,900 m<sup>2</sup> (20,450ft<sup>2</sup>) in area.



291.174.4 **MAXIMUM LOT COVERAGE:** 50%

291.174.5 **MINIMUM SETBACKS FROM PROPERTY LINES**

.01 **Public Road Setback**

- (a) Dyke Road: 6 m (19.7 ft.);
- (b) Princess Street: 3 m (9.8 ft.);
- (c) Notwithstanding the limitations imposed above:
  - (i) Porches, balconies, bay windows, entry stairs and cantilevered roofs forming part of the principal **building** may project into the Dyke Road setback for a distance of not more than 2.0 m (6.6 ft) and into the Princess Street setback for a distances of not more than 0.6 m (2.0 ft);
  - (ii) Gateways, pergolas, and similar landscape **structures** that do not form part of the principal **building** may be located within the **public road** setback, but shall be no closer to a **property line** than 2 m (6.6 ft.); and
  - (iii) Parking **structure** below finished grade may project into the **public road** setback, but shall be no closer to a property line than 3 m (9.8 ft.).

.02 **Side & Rear Yards:** 3 m (9.8 ft.);

- (a) Notwithstanding the limitations imposed above:
  - (i) Cantilevered roofs forming part of the principal **building** may project into the **side** and **rear yards** for a distance of not more than 1.2 m (3.9 ft.); and
  - (ii) Parking **structure** below finished grade may project into the **side** and **rear yards**, but shall be no closer to a **property line** than .45 m (1.5 ft.).

291.174.6 **MAXIMUM HEIGHTS**

.01 **Buildings and Structures:** 18 m (59 ft.).

.02 **Accessory Buildings:** 5 m (16.4 ft.).

291.174.7 **OFF-STREET PARKING**

.01 Off street parking shall be provided, developed and maintained in accordance with Division 400 of this Bylaw.

- (a) Where two spaces are intended to be **used** by the residents of a single **dwelling unit**, they may be provided in a tandem arrangement with one parking space located behind the other and, typically, both spaces set perpendicular to the adjacent manoeuvring aisle.

- 1. The Zoning Map of the City of Richmond, which accompanies and forms part of Richmond Zoning and Development Bylaw 5300, is amended by repealing the existing zoning designation of the following area and by designating it **Comprehensive Development District (CD/174)**:

P.I.D. 003-566-226

Lot 13 Section 18 Block 3 North Range 6 West New Westminster District Plan 693; and

P.I.D. 015-220-869

Lot B Section 18 Block 3 North Range 6 West New Westminster District Plan 693

- 2. This Bylaw may be cited as "**Richmond Zoning and Development Bylaw 5300, Amendment Bylaw 8078**".

FIRST READING

A PUBLIC HEARING WAS HELD ON

SECOND READING

THIRD READING

DEVELOPMENT REQUIREMENTS SATISFIED

ADOPTED

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_



\_\_\_\_\_  
MAYOR

\_\_\_\_\_  
CORPORATE OFFICER